


# **Appendix D**

## **Historic Drawings**




Map of Alameda County showing proposed Chabot Dam and Reservoir, 1874  
(Source: EBMUD)




Site plan of Chabot Dam and associated features by William Boardman, 1888  
(Source: EBMUD)




Site plan of Chabot Dam and associated features showing buildings on the knoll to the north of Chabot Dam, 1888  
(Source: EBMUD)




Details and sections of Tunnel No. 1 inlet and tower, 1888  
(Source: EBMUD)



Profiles and sections of Tunnel No. 3, 1888  
 (Source: EBMUD)




Plans, sections, and profiles of Tunnel No. 3 Spillway and Tunnel No. 3, date unknown but likely 1880s (Source:EBMUD)




Plans, profiles, and details of Tunnel No. 3 Spillway and Tunnel No. 3, date unknown but likely 1880s  
(Source:EBMUD)







Plans, sections, and details of a filtration basin, 1889  
(Source: EBMUD)




Plan for Hyatt filters at the filtration basin, circa 1890s  
(Source: EBMUD)




Elevation showing progress of brick work at Tunnel No. 3, 1889  
(Source: EBMUD)




Section through center of Spillway No. 1, 1891  
 (Source: EBMUD)




Plan of Spillway No. 1 and Chabot Dam wall, circa 1880s-1890s  
(Source: EBMUD)



Plans, sections, and details of Tunnel No. 2, 1889  
(Source: EBMUD)




Sections showing additions to the Chabot Dam wall, 1892  
(Source: EBMUD)




Section and detail of Tunnel No. 2 and Tunnel No. 2 Intake Tower, 1892  
(Source: EBMUD)






Sections, plans, and details of Spillway No. 3 Bridge and Weir, 1892  
(Source: EBMUD)




Sections of Spillway No. 1, 1892  
(Source: EBMUD)




Site plan of Chabot Dam and associated features, date unknown but likely 1890s-1800s  
(Source: EBMUD)




Tunnel No. 2 elevation and sections, date unknown but likely 1890s-1800s  
(Source: EBMUD)




Sections of the Chabot Dam, date unknown but likely 1890s-1800s  
(Source: EBMUD)



Plans and sections of Spillway No. 1, 1910  
(Source: EBMUD)




Plans and sections of the Tunnel No. 3 flume, 1916  
(Source: EBMUD)



Plan of the upper filtering basin, circa 1910s  
(Source: EBMUD)









Elevation and details of Tunnel No. 2 Intake Tower, 1923  
 (Source: EBMUD)






Plan of Spillway No. 1 and surrounding topography, 1933  
(Source: EBMUD)





Sections and details of concrete bulkhead at Tunnel No. 1, 1938  
 (Source: EBMUD)



Plan and sections of Spillway No. 3, 1942  
 (Source: EBMUD)

# **Appendix E**

## **Project Area Photographs**





Aerial photograph of Chabot Dam and Reservoir, looking west  
(Source: EBMUD)



Aerial photograph of Chabot Dam and Reservoir, looking west  
(Source: EBMUD)



Upstream face of the Chabot Dam at center, with the Spillway No. 1 at right, looking south  
(Source: AECOM 2013)



Downstream face of Chabot Dam, looking north  
(Source: AECOM 2013)



Chabot Reservoir, looking south  
(Source: AECOM 2013)



Chabot Spillway No. 1 at center left and Tunnel No. 2 Intake Tower at right, looking west  
(Source: AECOM 2013)



Tunnel No. 2 Intake Tower, looking northwest  
(Source: AECOM 2013)



Tunnel No. 2 Intake Tower, looking southeast  
(Source: AECOM 2013)



Tunnel No. 2 Intake Tower interior, looking northeast  
(Source: AECOM 2013)



Tunnel No. 2 inlet, looking through floor grate in  
Tunnel No. 2 Intake Tower  
(Source: AECOM 2013)



Tunnel No. 2 Intake Tower roof detail, looking northeast  
(Source: AECOM 2013)



Tunnel No. 3 Spillway control weir, looking northeast  
(Source: AECOM 2013)





Tunnel No. 3 inlet, looking northwest  
(Source: AECOM 2013)





Tunnel No. 3 wasteway chute, looking west  
(Source: AECOM 2013)



Tunnel No. 3 wasteway chute spillway where it meets San Leandro Creek, looking northeast  
(Source: AECOM 2013)



Tunnel No. 1 control tower base on the ridge northwest of Chabot Dam, looking north  
(Source: AECOM 2013)



Spillway No. 1 at right, looking west  
(Source: AECOM 2013)



Spillway No. 1 at center and Chabot Dam at right, looking northeast  
(Source: AECOM 2013)



Base of downstream face of Chabot Dam, looking west toward San Leandro Creek  
(Source: AECOM 2013)



San Leandro Creek, looking west  
(Source: EBMUD)



Lower filtration basin, looking south  
(Source: AECOM 2013)





Hyatt filters, looking northwest  
(Source: AECOM 2013)



Sunken basin lined with rubble-rock walls on hill northwest of Chabot Dam  
(Source: AECOM 2013)



Sunken basin lined with rubble-rock walls on hill northwest of Chabot Dam  
(Source: AECOM 2013)



Brick tank on top of hillside northwest of Chabot Dam  
(Source: AECOM 2013)

## **APPENDIX E-2**

---

NAHC Consultation Letters



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
[www.aecom.com](http://www.aecom.com)

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Muwekma Ohlone Indian Tribe of the SF Bay Area  
Rosemary Cambra, Chairperson  
P.O. Box 360791  
Milpitas, CA 95036

**Subject: Chabot Dam Seismic Upgrade**

Ms. Cambra:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
www.aecom.com

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Coastanoan Rumsen Carmel Tribe  
Tony Cerda, Chairperson  
240 E, 1<sup>st</sup> Street  
Pomona, CA 91766

**Subject: Chabot Dam Seismic Upgrade**

Mr. Cerda:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
www.aecom.com

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Katherine Erolinda Perez  
P.O. Box 717  
Linden, CA 95236

**Subject: Chabot Dam Seismic Upgrade**

Ms. Erolinda Perez:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
[www.aecom.com](http://www.aecom.com)

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Amah/Matsun Tribal Band  
Jean-Marie Feyling  
19350 Hunter Court  
Redding, CA 96003

**Subject: Chabot Dam Seismic Upgrade**

Ms. Feyling:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
[www.aecom.com](http://www.aecom.com)

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

The Ohlone Indian Tribe  
Andrew Galvan  
P.O. Box 3152  
Fremont, CA 94539

**Subject: Chabot Dam Seismic Upgrade**

Mr. Galvan:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure





AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
www.aecom.com

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Trina Marine Ruano Family  
Ramona Garibay, Representative  
30940 Watkins Street  
Union City, CA 94587

**Subject: Chabot Dam Seismic Upgrade**

Ms. Garibay:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
[www.aecom.com](http://www.aecom.com)

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Ms. Jakki Kehl  
720 North 2<sup>nd</sup> Street  
Patterson, CA 95363

**Subject: Chabot Dam Seismic Upgrade**

Ms. Kehl:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
www.aecom.com

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Indian Canyon Mutsun Band of Costanoan  
Ann Marie Sayers, Chairperson  
P.O. Box 28  
Hollister, CA 95024

**Subject: Chabot Dam Seismic Upgrade**

Ms. Sayers:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.

We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry.boutte@aecom.com](mailto:kerry.boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



AECOM  
300 California Street  
Suite 400  
San Francisco, CA 94104  
[www.aecom.com](http://www.aecom.com)

415 796 8100 tel  
415 796 8200 fax

July 30, 2013

Amah/Mutsun Tribal Band  
Irene Zwierlein, Chairperson  
789 Canada Road  
Woodside, CA 94062

**Subject: Chabot Dam Seismic Upgrade**

Ms. Zwierlein:

AECOM is conducting an Environmental Impact Report for the above-referenced project. Chabot Dam is located at the end of Estudillo Avenue, and on the west end of Chabot Lake (Chabot Reservoir), California and is delineated on the enclosed map.

The proposed project includes improvement of the embankment soils on the downstream side of Chabot Dam to withstand shaking generated by the maximum credible earthquake on the Hayward Fault without significant strength loss, to limit permanent deformation or settlement at the dam crest to acceptable levels, to prevent damage to the outlet works from the design level earthquake, and to continue reservoir and outlet works operation during construction.


We are pleased to bring this activity to your attention and would appreciate any information you can provide regarding prehistoric, historic, or ethnographic Native American land use. We are also interested in any contemporary Native American values that may be present near or within the project area.

If you have any questions or comments, please contact me at (415) 955-2892 or by mail, expressing your concerns at your earliest convenience. You may also contact me at [kerry\\_boutte@aecom.com](mailto:kerry_boutte@aecom.com). I look forward to hearing from you in the near future.

Respectfully yours,

Kerry L. Boutte  
Senior Archaeologist

Enclosure



Source: AECOM 2013, Terra Engineers 2013, EBMUD 2013

# General Site Plan

DRAFT - Not for Public Review

## **APPENDIX F-1**

---

Trip Generation



**Table 1 - Construction Vehicle Trip Details by Phase**

| OUTLET WORK |                                |         |         |                 |                    |    |    |   |    |    |          |                 |    |          |    |                                    |               |    |    |                                   |    |    |    |    |
|-------------|--------------------------------|---------|---------|-----------------|--------------------|----|----|---|----|----|----------|-----------------|----|----------|----|------------------------------------|---------------|----|----|-----------------------------------|----|----|----|----|
| Phase       | Activity                       | From    | To      | Duration (Week) | Equipment Delivery |    |    | Material Delivery   |    |    | Hauling  |                 |    | Worker   |    |                                    | Vehicle Trips |    |    |                                   |    |    |    |    |
|             |                                |         |         |                 | # of Veh           | IB | OB | # of Veh  | IB | OB | # of Veh | IB              | OB | # of Veh | IB | OB                                 | Assumption    | IB | OB | 1-Way                             | RT |    |    |    |
| 1           | Mobilization                   | week 1  | week 2  | 2               | 9                  | 9  | 0  | 1 work skiff;<br>2 specialized cranes;<br>1 loader;<br>1 dozer;<br>3 trucks onsite;<br>1 barge;<br>(IB@Start)   | 20 | 20 | 20       | Table 2-8 in PD | 0  | 0        | 0  | N/A                                | 23            | 23 | 23 | 18 equipment drivers +<br>5 staff | 52 | 43 | 95 | 48 |
| 2           | Demolition                     | week 3  | week 4  | 2               | 4                  | 2  | 2  | 2 specialized cranes<br>(OB@End);<br>2 cranes (IB@End)  | 0  | 0  | 0        | None            | 4  | 2        | 2  | 2 dump trucks<br>(IB@Start/OB@End) | 27            | 27 | 27 | 22 equipment drivers +<br>5 staff | 31 | 31 | 62 | 31 |
| 3           | Construct Outlet Works Upgrade | week 5  | week 13 | 9               | 12                 | 8  | 12 | 2 air compressor ;<br>1 generator;<br>1 winch;<br>2 welding set;<br>2 dumptruck<br>(IB@Start/OB@End)<br>1 work skiff;<br>1 truck<br>1 loader;<br>1 dozer;<br>(OB@End) | 10 | 10 | 10       | Table 2-8 in PD | 0  | 0        | 0  | N/A                                | 27            | 27 | 27 | 22 equipment drivers +<br>5 staff | 45 | 49 | 94 | 47 |
| 4           | Demobilization                 | week 14 | week 15 | 2               | 5                  | 0  | 5  | 2 cranes;<br>2 trucks onsite;<br>1 barge<br>(OB@End)  | 20 | 20 | 20       | Table 2-8 in PD | 0  | 0        | 0  | N/A                                | 15            | 15 | 15 | 10 equipment drivers +<br>5 staff | 35 | 40 | 75 | 38 |
| Total       |                                |         |         |                 | 15                 | 19 | 19 |   | 50 | 50 |          |                 | 2  | 2        |    |                                    |               |    |    |                                   |    |    |    |    |

PD=Project Description; IB=Inbound Trips; OB=Outbound Trips

| DEWATERING FOR CONVENTIONAL EARTHWORK |                |         |         |                 |                    |    |    |  |    |    |          |                                 |    |          |    |     |               |    |    |                                   |    |   |    |    |
|---------------------------------------|----------------|---------|---------|-----------------|--------------------|----|----|--|----|----|----------|---------------------------------|----|----------|----|-----|---------------|----|----|-----------------------------------|----|---|----|----|
| Phase                                 | Activity       | From    | To      | Duration (Week) | Equipment Delivery |    |    | Material Delivery  |    |    | Hauling  |                                 |    | Worker   |    |     | Vehicle Trips |    |    |                                   |    |   |    |    |
|                                       |                |         |         |                 | # of Veh           | IB | OB | # of Veh   | IB | OB | # of Veh | IB                              | OB | # of Veh | IB | OB  | Assumption    | IB | OB | 1-Way                             | RT |   |    |    |
| 1                                     | Mobilization   | week 1  | week 2  | 2               | 4                  | 4  | 0  | 1 bulldozer;<br>1 drill rig;<br>2 support vehicles<br>(IB@Start) | 0  | 0  | 0        | N/A                             | 0  | 0        | 0  | N/A | 8             | 8  | 8  | 8 equipment drivers<br>(Daily RT) | 12 | 8 | 20 | 10 |
| 2                                     | Installation   | week 3  | week 10 | 8               | 0                  | 0  | 0  | N/A  | 1  | 1  | 1        | 1 truck                         | 0  | 0        | 0  | N/A | 8             | 8  | 8  | 8 equipment drivers<br>(Daily RT) | 9  | 9 | 18 | 9  |
| 3                                     | Operation      | week 11 | week 40 | 30              | 2                  | 2  | 2  | 2 generators<br>(IB@Start/OB@End)                                | 1  | 1  | 1        | 1 fuel tank truck<br>(Daily RT) | 0  | 0        | 0  | N/A | 1             | 2  | 2  | 3 workers/shifts<br>(Daily RT)    | 5  | 5 | 10 | 5  |
| 4                                     | Demobilization | week 41 | week 42 | 2               | 4                  | 0  | 4  | 1 bulldozer;<br>1 drill rig;<br>2 support vehicles<br>(OB@End)   | 0  | 0  | 0        | N/A                             | 0  | 0        | 0  | N/A | 4             | 4  | 4  | 4 workers<br>(Daily RT)           | 4  | 8 | 12 | 6  |
| Total                                 |                |         |         |                 | 42                 | 6  | 6  |  | 2  | 2  |          |                                 |    |          |    |     | 22            | 22 |    |                                   |    |   |    |    |

IB@Start=Inbound at the start of phase; OB@End=Outbound at the end of phase; RT=round trip

| CONVENTIONAL EARTHWORK |   |          |         |                 |                    |    |    |  |   |     |          |   |   |          |    |  |  |     |    |  |  |     |     |     |    |
|------------------------|---|----------|---------|-----------------|--------------------|----|----|--|---|-----|----------|---|---|----------|----|--|--|-----|----|--|--|-----|-----|-----|----|
| Phase                  | Activity  | From     | To      | Duration (Week) | Equipment Delivery |    |    | Material Delivery  |   |     | Hauling  |   |   | Worker   |    |  | Vehicle Trips                              |     |    |  |  |     |     |     |    |
|                        |   |          |         |                 | # of Veh           | IB | OB | # of Veh   | IB  | OB  | # of Veh | IB  | OB  | # of Veh | IB | OB   | Assumption                                 | IB  | OB | 1-Way  | RT   |     |     |     |    |
| 1                      | Mobilization  | week 1   | week 2  | 2               | 4                  | 4  | 0  | 1 water truck;<br>3 trailers<br>(IB@Start)   | 0   | 0   | 0        | N/A   | 0   | 0        | 0  | N/A  | 28   | 28  | 28 | 8 equipment drivers +<br>20 admin staff<br>(Daily RT)                        | 32   | 28  | 60  | 30  |    |
| 2                      | Preparation of Haul Route(s) and Stockpile Areas            | Lower HR | week 3  | week 6          | 4                  | 8  | 8  | 4 tree trimming veh;<br>1 300-HP bulldozer;<br>1 compactor;<br>2 wood grinder/chipper<br>(IB@Start/OB@End) | 2   | 2   | 2        | 2 stone delivery trucks<br>(Daily RT)               | 0   | 0        | 0  | N/A  | 36   | 36  | 36 | 16 equipment drivers +<br>20 admin staff<br>(Daily RT)                       | 46   | 46  | 92  | 46  |    |
|                        |   | Upper HR |         |                 |                    |    |    | 1 stone delivery trucks<br>(Daily RT)  | 1   | 1   | 1        |   |   |          |    |  |  |     |    | 45   | 45   | 90  | 45  |     |    |
| 3                      | Excavation  | Lower HR | week 7  | week 22         | 16                 | 5  | 5  | 2 300-HP bulldozer;<br>2 5CY hydraulic excavator;<br>3 5CY rubber tire loaders<br>(IB@Start/OB@End)        | 2   | 2   | 2        | 2 fuel tank truck<br>(Daily RT)                     | 5   | 11       | 11 | Number of trucks used<br>(IB@Start/OB@End) | 41   | 41  | 41 | 10 equipment drivers +<br>11 truck drivers + 20<br>admin staff<br>(Daily RT) | 59   | 59  | 118 | 59  |    |
|                        |   | Upper HR |         |                 |                    | 7  | 5  | 3  | 2 300-HP bulldozer;<br>2 5CY hydraulic excavator;<br>1 5CY rubber tire loaders<br>(IB@Start/OB@End) |     |          |   | 2 fuel tank truck<br>(Daily RT)                     | 11       | 29 | 29   | Number of trucks used<br>(IB@Start/OB@End) | 63  | 63 | 63   | 14 equipment drivers +<br>29 truck drivers + 20<br>admin staff<br>(Daily RT) | 99  | 97  | 196 | 98 |
| 4                      | Site Preparation for Filling                                | week 23  | week 24 | 2               | 3                  | 3  | 0  | 3 compactor;<br>(IB@Start)   | 20  | 20  | 20       | 20 filter drain (Daily RT)                          | 0   | 0        | 0  | N/A  | 20   | 20  | 20 | 20 admin staff<br>(Daily RT)   | 43   | 40  | 83  | 42  |    |
| 5                      | Placement and Compaction of Fill                            | Lower HR | week 25 | week 34         | 10                 | 5  | 0  | 4  | 2 300-HP bulldozer;<br>2 compactor;<br>(OB@End)   | 22  | 22       | 22  | 2 fuel tank truck;<br>20 filter drain<br>(Daily RT) | 7        | 7  | 7  | Number of trucks used<br>(IB@Start/OB@End) | 37  | 37 | 37   | 10 equipment drivers +<br>7 truck drivers + 20<br>admin staff<br>(Daily RT)  | 66  | 70  | 136 | 68 |
|                        |   | Upper HR |         |                 |                    |    |    |  | 37  | 37  | 37       | 2 fuel tank truck;<br>35 filter drain<br>(Daily RT) | 18  | 18       | 18 | Number of trucks used<br>(IB@Start/OB@End) | 48   | 48  | 48 | 10 equipment drivers +<br>18 truck drivers + 20<br>admin staff<br>(Daily RT) | 103  | 107 | 210 | 105 |    |
| 6                      | Site Finishing and Restoration of Haul Roads and Stockpiles | week 35  | week 38 | 4               | 5                  | 4  | 5  | 1 5CY loader;<br>3 10CY trucks;<br>(IB@Start/OB@End)<br>1 compactor  | 25  | 25  | 25       | 25 10CY trucks<br>(Daily RT)                        | 0   | 0        | 0  | N/A  | 30   | 30  | 30 | 10 equipment drivers +<br>20 admin staff<br>(Daily RT)                       | 59   | 60  | 119 | 60  |    |
| 7                      | Demobilization  | week 39  | week 40 | 2               | 4                  | 0  | 4  | 1 water truck;<br>3 trailers<br>(OB@End)   | 0   | 0   | 0        | N/A   | 0   | 0        | 0  | N  | 28   | 28  | 28 | 8 equipment drivers +<br>20 admin staff<br>(Daily RT)                        | 28   | 32  | 60  | 30  |    |
| Total                  |   |          |         |                 | 40                 | 29 | 29 |  | 109   | 109 |          |   | 65  | 65       |    |  | 331  | 331 |    |  |  |     |     |     |    |

HP=Horse Power; HR=Haul Route

| CDSM (DAY & NIGHT SHIFTS) |   |          |         |                 |                    |    |    |   |  |    |          |   |   |          |    |  |  |    |    |   |   |    |     |     |    |
|---------------------------|---|----------|---------|-----------------|--------------------|----|----|---|--|----|----------|---|---|----------|----|--|--|----|----|---|---|----|-----|-----|----|
| Phase                     | Activity  | From     | To      | Duration (Week) | Equipment Delivery |    |    | Material Delivery   |  |    | Hauling  |   |   | Worker   |    |  | Vehicle Trips                              |    |    |   |   |    |     |     |    |
|                           |   |          |         |                 | # of Veh           | IB | OB | # of Veh  | IB   | OB | # of Veh | IB                                      | OB                                      | # of Veh | IB | OB   | Assumption                                 | IB | OB | 1-Way   | RT  |    |     |     |    |
| 1                         | Mobilization  | week 1   | week 2  | 2               | 4                  | 4  | 0  | 1 water truck;<br>3 trailers<br>(IB@Start)                          | 0  | 0  | 0        | N/A                                     | 0                                       | 0        | 0  | N/A  | 28   | 28 | 28 | 8 equipment drivers +<br>20 admin staff<br>(Daily RT)                       | 32  | 28 | 60  | 30  |    |
| 2                         | Preparation of Haul Route(s) and Stockpile Areas            | Lower HR | week 3  | week 4          | 2                  | 8  | 8  | 8   | 4 tree trimming veh;<br>1 300-HP bulldozer;<br>1 compactor;<br>2 wood grinder/chipper<br>(IB@Start/OB@End) | 2  | 2        | 2                                       | 2 stone delivery trucks<br>(Daily RT)   | 0        | 0  | 0  | N/A  | 36 | 36 | 36  | 16 equipment drivers +<br>20 admin staff<br>(Daily RT)                      | 46 | 46  | 92  | 46 |
|                           |   | Upper HR |         |                 |                    |    |    |   | 1 stone delivery trucks<br>(Daily RT)  | 1  | 1        | 1                                       |   |          |    |  |  |    |    |   | 45  | 45 | 90  | 45  |    |
| 3                         | Excavation of CDSM Working Platform                         | Lower HR | week 5  | week 5          | 1                  | 5  | 5  | 2   | 2 300-HP bulldozer;<br>(IB@Start/OB@End)<br>3 5CY rubber tire loaders<br>(IB@Start)                        | 2  | 2        | 2                                       | 2 fuel tank truck<br>(Daily RT)         | 3        | 3  | 3  | Number of trucks used<br>(IB@Start/OB@End) | 33 | 33 | 33  | 10 equipment drivers +<br>3 truck drivers + 20<br>admin staff<br>(Daily RT) | 43 | 40  | 83  | 42 |
|                           |   | Upper HR |         |                 |                    |    |    |   |  |    |          |   | 8                                       | 8        | 8  | Number of trucks used<br>(IB@Start/OB@End) | 38   | 38 | 38 | 10 equipment drivers +<br>8 truck drivers + 20<br>admin staff<br>(Daily RT) | 53  | 50 | 103 | 52  |    |
| 4                         | Setup of Two CDSM Rig                                       | Lower HR | week 6  | week 7          | 2                  | 7  | 7  | 3   | 2 big cranes;<br>2 trailers (IB@Start);<br>1 small crane;<br>2 grout plants<br>(IB@Start/OB@End)           | 10 | 10       | 10                                      | 10 cement delivery trucks               | 0        | 0  | 0  | N/A  | 36 | 36 | 36  | 12 equipment drivers +<br>20 admin staff<br>(Daily RT)                      | 53 | 49  | 102 | 51 |
|                           |   | Upper HR |         |                 |                    |    |    |   | 20   | 20 | 20       | 20 cement delivery trucks               |   |          |    |  |  |    |    |   | 63  | 59 | 122 | 61  |    |
| 5                         | CDSM Construction using Two Rigs (a)                        | Lower HR | week 8  | week 15         | 8                  | 5  | 0  | 5   | 3 5CY rubber tire loader;<br>2 trailers (OB@End)   | 10 | 10       | 10                                      | 10 cement delivery trucks               | 0        | 0  | 0  | N/A  | 36 | 36 | 36  | 12 equipment drivers +<br>20 admin staff<br>(Daily RT)                      | 46 | 51  | 97  | 49 |
|                           |   | Upper HR |         |                 |                    |    |    |   | 20   | 20 | 20       | 20 cement delivery trucks               |   |          |    |  |  |    |    |   | 56  | 61 | 117 | 59  |    |
| 6                         | Wait for Results of 14-day Strength Test Results            | week 16  | week 17 | 2               | 0                  | 0  | 0  | N/A   | 0  | 0  | 0        | N/A                                     | 0                                       | 0        | 0  | N/A  | 20   | 20 | 20 | 20 admin staff<br>(Daily RT)  | 20  | 20 | 40  | 20  |    |
| 7                         | Tear Down of Two CDSM Rigs                                  | Lower HR | week 18 | week 18         | 1                  | 4  | 2  | 4   | 2 big cranes (OB@End);<br>2 low-boys<br>(IB@Start/OB@End)  | 20 | 20       | 20                                      | 15-20 filler/drain material<br>delivery | 0        | 0  | 0  | N/A  | 28 | 28 | 28  | 8 equipment drivers +<br>20 admin staff<br>(Daily RT)                       | 50 | 52  | 102 | 51 |
|                           |   | Upper HR |         |                 |                    |    |    |   | 35   | 35 | 35       | 25-35 filler/drain material<br>delivery |   |          |    |  |  |    |    |   | 65  | 67 | 132 | 66  |    |
| 8                         | Placement and Compaction of Fill                            | Lower HR | week 19 | week 22         | 4                  | 5  | 5  | 5   | 2 300-HP bulldozer;<br>3 5CY rubber tire loaders<br>(IB@Start/OB@End)                                      | 20 | 20       | 20                                      | 15-20 filler/drain material<br>delivery | 5        | 5  | 5  | Number of trucks used<br>(IB@Start/OB@End) | 32 | 32 | 32  | 10 equipment drivers +<br>2 truck drivers + 20<br>admin staff<br>(Daily RT) | 62 | 62  | 124 | 62 |
|                           |   | Upper HR |         |                 |                    |    |    |   | 35   | 35 | 35       | 25-35 filler/drain material<br>delivery | 12                                      | 12       | 12 | Number of trucks used<br>(IB@Start/OB@End) | 35   | 35 | 35 | 10 equipment drivers +<br>5 truck drivers + 20<br>admin staff<br>(Daily RT) | 87  | 87 | 174 | 87  |    |
| 9                         | Site Finishing and Restoration of Haul Roads and Stockpiles | week 23  | week 24 | 2               | 5                  | 5  | 5  | 1 5CY loader;<br>3 10CY trucks;<br>1 compactor<br>(IB@Start/OB@End) | 25   | 25 | 25       | 25 10CY trucks<br>(Daily RT)            | 0                                       | 0        | 0  | N/A  | 30   | 30 | 30 | 10 equipment drivers +<br>20 admin staff<br>(Daily RT)                      | 60  | 60 | 120 | 60  |    |
| 10                        | Demobilization  | week 25  | week 26 | 2               | 4                  | 0  | 4  | 1 water truck;<br>3 trailers<br>(OB@End)                            | 0  | 0  | 0        | N/A                                     | 0                                       | 0        | 0  | N  | 28   | 28 | 28 | 8 equipment drivers +<br>20 admin staff<br>(Daily RT)                       | 28  | 32 | 60  | 30  |    |
| Total                     |   |          |         |                 | 26                 | 36 | 36 |   |  |    |          |   |   |          |    |  |  |    |    |   |   |    |     |     |    |

(a) Notes about the CDSM Construction

The number of worker vehicles shown in the table is day shift only. Daily number of worker vehicles during the CDSM Construction Activity over Day and Night Shifts would be 72 vehicles











**Table 4A - External Vehicle Trip Summary (Conventional Earth Work)**

| Construction Trips      | Daily      |            |            | AM Peak-Hour |          | PM Peak-Hour |           |
|-------------------------|------------|------------|------------|--------------|----------|--------------|-----------|
|                         | IB         | OB         | Total      | IB           | OB       | IB           | OB        |
| - Equipment (a)         | 7          | 5          | 12         | 1            | 1        | 1            | 1         |
| - Material Delivery (a) | 3          | 3          | 6          | 1            | 1        | 1            | 1         |
| - Hauling Trucks (a)    | 29         | 29         | 58         | 3            | 4        | 4            | 4         |
| - Worker (b)            | 65         | 65         | 130        | 65           | 0        | 0            | 65        |
| <b>Total</b>            | <b>104</b> | <b>102</b> | <b>206</b> | <b>70</b>    | <b>6</b> | <b>6</b>     | <b>71</b> |

(a) Equipment, material delivery and hauling truck trips are conservatively assumed to be spread out over 10-hour day (PD assumes 12-hour shift).  
 (b) All workers are conservatively assumed to arrive during the AM peak-hour and leave during the PM peak-hour (PD assumes 7am-7pm shift).

**Table 4B- Internal Hauling Truck Trip Summary**

| Alternative Description |              |             |                 | Size of Trucks Used<br>(A) | Round-Trip Cycle Time (min)<br>(B) | Max Number of Round Trips per Day per Truck<br>(C=60*10/B) | Quantities (CY)                 |                           | Hauling Truck Trips during Excavation Phase |                        |                              |                                      | Hauling Truck Trips during Replacement Phase |                        |                                  |                                      |
|-------------------------|--------------|-------------|-----------------|----------------------------|------------------------------------|--|---------------------------------|---------------------------|---|------------------------|------------------------------|--------------------------------------|--|------------------------|----------------------------------|--------------------------------------|
| Combination             | Method       | Haul Route  | Stockpile       |                            |                                    |  | Excavated Soil and Spoil<br>(D) | Transported Volume<br>(E) | Total Round Trips<br>(F=E/A)                | Duration (days)<br>(G) | Daily Round Trips<br>(H=F/G) | Number of Trucks Required<br>(I=H/C) | Total Round Trips<br>(J=E/A)                 | Duration (days)<br>(K) | Daily Round Trips (L)<br>(L=J/K) | Number of Trucks Required<br>(M=L/C) |
| 1A                      | Conventional | Lower       | Park/Filterpond | 20 CY                      | 22.2                               | 27   | 140,000                         | 175,000                   | 8,750                                       | 80                     | 109                          | 5                                    | 8,750  | 50                     | 175                              | 7                                    |
| 1B                      | Conventional | Lower/Upper | Park/Filterpond | 10 CY                      | 24.5                               | 25   | 140,000                         | 175,000                   | 17,500                                      | 80                     | 219                          | 9                                    | 17,500                                       | 50                     | 350                              | 15                                   |
| 1C                      | Conventional | Upper       | Park/Filterpond | 10 CY                      | 29.6                               | 20   | 140,000                         | 175,000                   | 17,500                                      | 80                     | 219                          | 11                                   | 17,500                                       | 50                     | 350                              | 18                                   |
| 8A                      | CDSM         | Lower       | Filterpond      | 20 CY                      | 22.2                               | 27   | 38,500                          | 45,500                    | 2,275                                       | 25                     | 91                           | 4                                    | 2,275  | 20                     | 114                              | 5                                    |
| 8C                      | CDSM         | Upper       | Filterpond      | 10 CY                      | 28.2                               | 21   | 38,500                          | 45,500                    | 4,550                                       | 25                     | 182                          | 9                                    | 4,550  | 20                     | 228                              | 11                                   |

(A) Assume 20 CY trucks for Lower Haul Route and 10 CY trucks for Upper Haul Route.  
 (B) Includes on-site travel time between excavation site and stockpile, waiting time at loading and unloading, time to load and unload, and convoy waiting time for 1-way traffic (provided by Terra Engineers).  
 (C) 10-hour day divided by cycle time.  
 (D) Project Description Tables 2-1 and 2-2 (excluding material delivery).  
 (E) Assume 25% bulk factor for soil and 15% bulk factor for spoil.  
 (F) Total amount of volume transported divided by the size of truck.  
 (G) Assume 6 weeks for conventional earth work and 5 weeks for CDSM option (Tables 2-3 and 2-6 in PD).  
 (H) Total number of round trips spread over the duration of excavation.  
 (I) Total number of daily truck trips divided by the maximum number of daily trips per truck.  
 (J) Total amount of volume transported divided by the size of truck.  
 (K) Assume 10 weeks for conventional earthwork and 4 weeks for CDSM option (Tables 2-3 and 2-6 in PD).  
 (L) Total number of round trips spread over the duration of replacement phase.  
 (M) Total number of daily truck trips divided by the maximum number of daily trips per truck.

**Table 4C- Off-site Hauling Truck Trip Summary (Alternative 1)**

| Alternative Description |        |            |           | Size of Trucks Used<br>(A) | Round-Trip Cycle Time (min)<br>(B) | Max Number of Round Trips per Day per Truck<br>(C=60*10/B) | Quantities (CY)                 |                           | Hauling Truck Trips during Excavation Phase |                        |                              |                                      | Hauling Truck Trips during Replacement Phase |                        |                                  |                                      |
|-------------------------|--------|------------|-----------|----------------------------|------------------------------------|--|---------------------------------|---------------------------|---|------------------------|------------------------------|--------------------------------------|--|------------------------|----------------------------------|--------------------------------------|
| Combination             | Method | Haul Route | Stockpile |                            |                                    |  | Excavated Soil and Spoil<br>(D) | Transported Volume<br>(E) | Total Round Trips<br>(F=E/A)                | Duration (days)<br>(G) | Daily Round Trips<br>(H=F/G) | Number of Trucks Required<br>(I=H/C) | Total Round Trips<br>(J=E/A)                 | Duration (days)<br>(K) | Daily Round Trips (L)<br>(L=J/K) | Number of Trucks Required<br>(M=L/C) |
|                         |        | Lower      | Off-Site  | 20 CY                      | 40.4                               | 14.9   | 140,000                         | 175,000                   | 8,750                                       | 36                     | 243                          | 17.0                                 | 8,750  | 60                     | 146                              | 10                                   |

505 297

**External Vehicle Trips**

|                   | Proposed Project |              |              | Alternative 1 during Excavation |              |              | Alternative 1 during Replacement |              |              |
|-------------------|------------------|--------------|--------------|---------------------------------|--------------|--------------|----------------------------------|--------------|--------------|
|                   | Daily            | AM Peak-Hour | PM Peak-Hour | Daily                           | AM Peak-Hour | PM Peak-Hour | Daily                            | AM Peak-Hour | PM Peak-Hour |
| Worker            | 198              | 99           | 99           | 198                             | 99           | 99           | 198                              | 99           | 99           |
| Material Delivery | 60               | 6            | 6            | 60                              | 6            | 6            | 60                               | 6            | 6            |
| Hauling           | 0                | 0            | 0            | 505                             | 51           | 51           | 297                              | 30           | 30           |
| <b>Total</b>      | <b>258</b>       | <b>105</b>   | <b>105</b>   | <b>763</b>                      | <b>156</b>   | <b>156</b>   | <b>555</b>                       | <b>135</b>   | <b>135</b>   |

|                   | Proposed Project |              |              | Alternative 1  |                |                |
|-------------------|------------------|--------------|--------------|----------------|----------------|----------------|
|                   | Daily            | AM Peak-Hour | PM Peak-Hour | Daily          | AM Peak-Hour   | PM Peak-Hour   |
| Worker            | 198              | 99           | 99           | 198            | 99             | 99             |
| Material Delivery | 60               | 6            | 6            | 60             | 6              | 6              |
| Hauling           | 0                | 0            | 0            | 297-505        | 30-51          | 30-51          |
| <b>Total</b>      | <b>258</b>       | <b>105</b>   | <b>105</b>   | <b>555-763</b> | <b>135-156</b> | <b>135-156</b> |

**Table 5 - Daily Round-Trip Summary\***

| Outlet Work |                        |         |                  |           |          |               |             |              |                |               |
|-------------|------------------------|---------|------------------|-----------|----------|---------------|-------------|--------------|----------------|---------------|
| Activity    | From                   | To      | Duration (weeks) | External  |          |               |             |              | Internal       |               |
|             |                        |         |                  | Trucks    |          |               |             | Personal Veh | External Total | Hauling Truck |
|             |                        |         |                  | Equipment | Material | Hauling Truck | Truck Total | Workers      |                |               |
| O1          | week 1                 | week 2  | 2                | 5         | 20       | 0             | 25          | 23           | 48             | 0             |
| O2          | week 2                 | week 4  | 2                | 2         | 0        | 4             | 6           | 27           | 31             | 0             |
| O3          | Construct Outlet Works | week 4  | week 13          | 9         | 10       | 10            | 0           | 20           | 27             | 47            |
| O4          | Demobilization         | week 13 | week 15          | 2         | 3        | 20            | 0           | 23           | 15             | 38            |
|             |                        |         |                  | 15        |          |               |             |              |                |               |

| Dewatering |                |         |                  |           |          |               |             |              |                |               |
|------------|----------------|---------|------------------|-----------|----------|---------------|-------------|--------------|----------------|---------------|
| Activity   | From           | To      | Duration (weeks) | External  |          |               |             |              | Internal       |               |
|            |                |         |                  | Trucks    |          |               |             | Personal Veh | External Total | Hauling Truck |
|            |                |         |                  | Equipment | Material | Hauling Truck | Truck Total | Workers      |                |               |
| D1         | week 1         | week 2  | 2                | 2         | 0        | 0             | 2           | 8            | 10             | 0             |
| D2         | week 2         | week 10 | 8                | 0         | 1        | 0             | 1           | 8            | 9              | 0             |
| D3         | Operation      | week 10 | week 40          | 30        | 2        | 1             | 0           | 3            | 2              | 5             |
| D4         | Demobilization | week 40 | week 42          | 2         | 2        | 0             | 0           | 2            | 4              | 6             |
|            |                |         |                  | 42        |          |               |             |              |                |               |

| Conventional Earthwork |   |         |                  |           |          |               |             |              |                |               |
|------------------------|---|---------|------------------|-----------|----------|---------------|-------------|--------------|----------------|---------------|
| Activity               | From                                      | To      | Duration (weeks) | External  |          |               |             |              | Internal       |               |
|                        |   |         |                  | Trucks    |          |               |             | Personal Veh | External Total | Hauling Truck |
|                        |   |         |                  | Equipment | Material | Hauling Truck | Truck Total | Workers      |                |               |
| CE1                    | week 1                                    | week 2  | 2                | 2         | 0        | 0             | 2           | 28           | 30             | 0             |
| CE2                    | Preparation of haul routes and stockpiles | week 2  | week 6           | 4         | 8        | 2 - 1         | 0           | 10 - 9       | 36             | 46 - 45       |
| CE3                    | Excavation                                | week 6  | week 22          | 16        | 5 - 4    | 2             | 11 - 29     | 18 - 35      | 41 - 63        | 59 - 98       |
| CE4                    | Site preparation for filling              | week 22 | week 24          | 2         | 2        | 20            | 0           | 22           | 20             | 42            |
| CE5                    | Placement and compaction of fill          | week 24 | week 34          | 10        | 2        | 22 - 37       | 7 - 18      | 31 - 57      | 37 - 48        | 68 - 105      |
| CE6                    | Site finishing and restoration of routes  | week 34 | week 38          | 4         | 5        | 25            | 0           | 30           | 30             | 60            |
| CE7                    | Demobilization                            | week 38 | week 40          | 2         | 2        | 0             | 0           | 2            | 28             | 30            |
|                        |   |         |                  | 40        |          |               |             |              |                |               |

| CDSM     |   |            |                  |           |          |               |             |              |                |               |
|----------|---|------------|------------------|-----------|----------|---------------|-------------|--------------|----------------|---------------|
| Activity | From                                      | To         | Duration (weeks) | External  |          |               |             |              | Internal       |               |
|          |   |            |                  | Trucks    |          |               |             | Personal Veh | External Total | Hauling Truck |
|          |   |            |                  | Equipment | Material | Hauling Truck | Truck Total | Workers      |                |               |
| CD1      | week 1                                    | week 2     | 2                | 2         | 0        | 0             | 2           | 28           | 30             | 0             |
| CD2      | Preparation of haul routes and stockpiles | week 2     | week 4           | 2         | 8        | 2 - 1         | 0           | 10 - 9       | 36             | 46 - 45       |
| CD3      | Excavation of CDSM working platform       | week 4     | week 5           | 1         | 4        | 2             | 3 - 8       | 9 - 14       | 33 - 38        | 42 - 52       |
| CD4      | Setup of CDSM rigs                        | week 5     | week 7           | 2         | 5        | 10 - 20       | 0           | 15 - 25      | 36             | 51 - 61       |
| CD5      | CDSM Construction                         | week 7     | week 15-20       | 8         | 3        | 10 - 20       | 0           | 13 - 23      | 72             | 85 - 95       |
| CD6      | Wait for 14-day strength test results     | week 15-20 | week 17-22       | 2         | 0        | 0             | 0           | 0            | 20             | 20            |
| CD7      | Tear down of CDSM rigs                    | week 17-22 | week 18-23       | 1         | 3        | 20 - 35       | 0           | 23 - 38      | 28             | 51 - 66       |
| CD8      | Placement and compaction of fill          | week 18-23 | week 22-27       | 4         | 5        | 20 - 35       | 5 - 12      | 30 - 52      | 32 - 35        | 62 - 87       |
| CD9      | Site finishing and restoration of routes  | week 22-27 | week 24-29       | 2         | 5        | 25            | 0           | 30           | 30             | 60            |
| CD10     | Demobilization                            | week 24-29 | week 26-31       | 2         | 2        | 0             | 0           | 2            | 28             | 30            |
|          |   |            |                  | 26 - 31   |          |               |             |              |                |               |

**\*Notes about a range in numbers**

Lower number in the range indicates the scenario in which lower haul route is used, and the the higher number indicates the scenario in which upper haul route is used.

**\*Peak Trip Generation**

**Conventional Earth Work Option** - The peak trip generation would occur when Dewatering operation (5 trips in D3) and Placement and Compaction of Fill (105 trips in CE5) occur simultaneously for a total of 110 trips between week 17 and week 26.

**CDSM Option** - The peak trip generation would occur when Outlet Work upgrades (47 trips in Phase O2) and CDSM Construction (95 trips in CD5) occur simultaneously for a total of 142 trips between week 8 and week 13

Tables used in Section 2.7 (Project Description)

| Construction Activity  | Round Trip Vehicle Trips per Day |          |               |        | Total |
|------------------------|----------------------------------|----------|---------------|--------|-------|
|                        | Equipment                        | Material | Hauling Truck | Worker |       |
| Mobilization           | 5                                | 20       | 0             | 23     | 48    |
| Demolition             | 2                                | 0        | 4             | 27     | 33    |
| Construct Outlet Works | 10                               | 10       | 0             | 27     | 47    |
| Demobilization         | 3                                | 20       | 0             | 15     | 38    |

Tables for Section 2.7 (Project Description - rounded to nearest 5)

| Construction Activity | Round Trip Vehicle Trips per Day |          |               |        | Total |
|-----------------------|----------------------------------|----------|---------------|--------|-------|
|                       | Equipment                        | Material | Hauling Truck | Worker |       |
| Mobilization          | 2                                | 0        | 0             | 8      | 10    |
| Installation          | 0                                | 1        | 0             | 8      | 9     |
| Operation             | 2                                | 1        | 0             | 2      | 5     |
| Demobilization        | 2                                | 0        | 0             | 4      | 6     |

| Construction Activity                     | Round Trip Vehicle Trips per Day |          |               |        | Total  |
|---|----------------------------------|----------|---------------|--------|--------|
|   | Equipment                        | Material | Hauling Truck | Worker |        |
| Mobilization                              | 2                                | 0        | 0             | 28     | 30     |
| Preparation of haul routes and stockpiles | 8                                | 2-1      | 0             | 36     | 45-46  |
| Excavation                                | 4-5                              | 2        | 11-29         | 41-63  | 59-98  |
| Site preparation for filling              | 2                                | 20       | 0             | 20     | 42     |
| Placement and compaction of fill          | 2                                | 22-37    | 7-18          | 37-48  | 68-105 |
| Site finishing and restoration of routes  | 5                                | 25       | 0             | 30     | 60     |
| Demobilization                            | 2                                | 0        | 0             | 28     | 30     |

| Construction Activity                     | Round Trip Vehicle Trips per Day |          |               |        | Total |
|---|----------------------------------|----------|---------------|--------|-------|
|   | Equipment                        | Material | Hauling Truck | Worker |       |
| Mobilization                              | 2                                | 0        | 0             | 28     | 30    |
| Preparation of haul routes and stockpiles | 8                                | 2-1      | 0             | 36     | 46-45 |
| Excavation of CDSM working platform       | 4                                | 2        | 3-8           | 33-38  | 42-52 |
| Setup of CDSM rigs                        | 5                                | 10-20    | 0             | 36     | 51-61 |
| CDSM Construction(Day and Night Shifts)   | 3                                | 10-20    | 0             | 72     | 85-95 |
| CDSM Construction (Day Shift)             | 3                                | 10-21    | 0             | 36     | 49-59 |
| Wait for 14-day strength test results     | 0                                | 0        | 0             | 20     | 20    |
| Tear down of CDSM rigs                    | 3                                | 20-35    | 0             | 28     | 51-66 |
| Placement and compaction of fill          | 5                                | 20-35    | 5-12          | 32-35  | 62-87 |
| Site finishing and restoration of routes  | 5                                | 25       | 0             | 30     | 60    |
| Demobilization                            | 2                                | 0        | 0             | 28     | 30    |

## **APPENDIX F-1**

---

Trip Generation





## Scenario Report

Scenario: EX AM  
 Command: EX AM  
 Volume: EX AM  
 Geometry: Default Geometry  
 Impact Fee: Default Impact Fee  
 Trip Generation: None  
 Trip Distribution: None  
 Paths: Default Path  
 Routes: Default Route  
 Configuration: Default Configuration

Turning Movement Report  
None

| Volume Type                         | Northbound |      |       | Southbound |      |       | Eastbound |      |       | Westbound |      |       | Total Volume |
|-------------------------------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|--------------|
|                                     | Left       | Thru | Right | Left       | Thru | Right | Left      | Thru | Right | Left      | Thru | Right |              |
| #5                                  |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #15 Grand/MacArthur/Off-Ramp        |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #101                                |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 4     | 380       | 59   | 0     | 0         | 53   | 13    | 509          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 4     | 380       | 59   | 0     | 0         | 53   | 13    | 509          |
| #102 MacArthur Blvd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 439        | 238  | 141   | 113        | 243  | 167   | 29        | 320  | 127   | 66        | 178  | 42    | 2103         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 439        | 238  | 141   | 113        | 243  | 167   | 29        | 320  | 127   | 66        | 178  | 42    | 2103         |
| #103 Benedict Dr / Estudillo Ave    |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 68         | 34   | 9     | 2          | 0    | 38    | 467       | 96   | 5     | 3         | 169  | 97    | 988          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 68         | 34   | 9     | 2          | 0    | 38    | 467       | 96   | 5     | 3         | 169  | 97    | 988          |
| #104 Lake Chabot Rd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 3          | 0    | 29    | 23        | 102  | 0     | 0         | 268  | 5     | 430          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 3          | 0    | 29    | 23        | 102  | 0     | 0         | 268  | 5     | 430          |
| #105 SB-Off-Grand                   |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 5          | 133  | 0     | 0          | 550  | 34    | 27        | 0    | 35    | 217       | 110  | 71    | 1182         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 5          | 133  | 0     | 0          | 550  | 34    | 27        | 0    | 35    | 217       | 110  | 71    | 1182         |

Impact Analysis Report  
Level Of Service

| Intersection                        | Base    |             | Future  |             | Change<br>in |
|-------------------------------------|---------|-------------|---------|-------------|--------------|
|                                     | Del/    | V/          | Del/    | V/          |              |
| #101                                | LOS Veh | C           | LOS Veh | C           |              |
|                                     | A       | 8.6 0.289   | A       | 8.6 0.289   | + 0.000 D/V  |
| #102 MacArthur Blvd / Estudillo Ave | B       | 18.9 0.658  | B       | 18.9 0.658  | + 0.000 D/V  |
| #103 Benedict Dr / Estudillo Ave    | F       | 593.1 1.454 | F       | 593.1 1.454 | + 0.000 D/V  |
| #104 Lake Chabot Rd / Estudillo Ave | A       | 10.0 0.038  | A       | 10.0 0.038  | + 0.000 D/V  |
| #105 SB-Off-Grand                   | C       | 17.8 0.645  | C       | 17.8 0.645  | + 0.000 V/C  |

Level Of Service Computation Report  
2000 HCM Unsignalized Method (Base Volume Alternative)

```

*****
Intersection #101
*****
Average Delay (sec/veh):      6.2      Worst Case Level Of Service: A[ 8.6]
*****

Approach:      North Bound      South Bound      East Bound      West Bound
Movement:      L - T - R      L - T - R      L - T - R      L - T - R
-----|-----|-----|-----|
Control:      Stop Sign      Stop Sign      Uncontrolled      Uncontrolled
Rights:      Include      Include      Include      Include
Lanes:      0 0 0 0 0      0 0 0 0 1      0 1 0 0 0      0 0 0 1 0
-----|-----|-----|-----|
Volume Module: >> Count Date: 6 Nov 2012 << 7:30
Base Vol:      0 0 0      0 0 4      380 59 0      0 0 53 13
Growth Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
Initial Bse: 0 0 0      0 0 0      380 59 0      0 0 53 13
User Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
PHF Adj: 1.00 1.00 1.00 0.50 0.50 0.50 0.86 0.86 1.00 1.00 0.83 0.83
PHF Volume: 0 0 0      0 0 0      8 442 69 0      0 0 64 16
Reduct Vol: 0 0 0      0 0 0      0 0 0 0 0      0 0 0 0
FinalVolume: 0 0 0      0 0 0      8 442 69 0      0 0 64 16
-----|-----|-----|-----|
Critical Gap Module:
Critical Gp:xxxxx xxxx xxxxx xxxxx xxxxx 6.2 4.1 xxxx xxxxx xxxxx xxxx xxxxx
FollowUpTim:xxxxx xxxx xxxxx xxxxx xxxxx 3.3 2.2 xxxx xxxxx xxxxx xxxx xxxxx
-----|-----|-----|-----|
Capacity Module:
Cnflct Vol: xxxx xxxx xxxxx xxxx xxxxx 72 80 xxxx xxxxx xxxx xxxx xxxxx
Potent Cap.: xxxx xxxx xxxxx xxxx xxxxx 996 1531 xxxx xxxxx xxxx xxxx xxxxx
Move Cap.: xxxx xxxx xxxxx xxxx xxxxx 996 1531 xxxx xxxxx xxxx xxxx xxxxx
Volume/Cap: xxxx xxxx xxxxx xxxx xxxxx 0.01 0.29 xxxx xxxxx xxxx xxxx xxxxx
-----|-----|-----|-----|
Level Of Service Module:
2Way95thQ: xxxx xxxx xxxxx xxxx xxxxx 0.0 1.2 xxxx xxxxx xxxx xxxx xxxxx
Control Del:xxxxx xxxx xxxxx xxxxx xxxxx 8.6 8.3 xxxx xxxxx xxxxx xxxx xxxxx
LOS by Move: * * * * * A A * * * * *
Movement: LT - LTR - RT LT - LTR - RT LT - LTR - RT LT - LTR - RT
Shared Cap.: xxxx xxxx xxxxx xxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx xxxxx
SharedQueue:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 1.2 xxxx xxxxx xxxxx xxxx xxxxx
Shrd ConDel:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 8.3 xxxx xxxxx xxxxx xxxx xxxxx
Shared LOS: * * * * * A * * * * *
ApproachDel: xxxxxxx 8.6 xxxxxxx xxxxxxx
ApproachLOS: * A * * *
*****
Note: Queue reported is the number of cars per lane.
*****

```

Level Of Service Computation Report
2000 HCM Operations Method (Base Volume Alternative)

Intersection #102 MacArthur Blvd / Estudillo Ave

Cycle (sec): 65 Critical Vol./Cap.(X): 0.658
Loss Time (sec): 0 Average Delay (sec/veh): 18.9
Optimal Cycle: 54 Level Of Service: B

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes, Min. Green, Y+R, and Lanes.

Table with 12 columns for Volume Module. Rows include Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, Reduct Vol, Reduced Vol, PCE Adj, MLF Adj, and Final Volume.

Table with 12 columns for Saturation Flow Module. Rows include Sat/Lane, Adjustment, Lanes, and Final Sat.

Table with 12 columns for Capacity Analysis Module. Rows include Vol/Sat, Crit Moves, Green/Cycle, Volume/Cap, Uniform Del, IncrementDel, InitQueueDel, Delay Adj, Delay/Veh, User DelAdj, AdjDel/Veh, LOS by Move, and HCM2kAvgQ.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM Unsignalized Method (Base Volume Alternative)

Intersection #103 Benedict Dr / Estudillo Ave

Average Delay (sec/veh): 86.3 Worst Case Level Of Service: F[593.1]

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes, and Volume Module.

Table with 12 columns for Volume Module. Rows include Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, Reduct Vol, and Final Volume.

Table with 12 columns for Critical Gap Module. Rows include Critical Gap and FollowUpTim.

Table with 12 columns for Capacity Module. Rows include Cnflct Vol, Potent Cap., Move Cap., and Volume/Cap.

Table with 12 columns for Level Of Service Module. Rows include 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., SharedQueue, Shrd ConDel, Shared LOS, ApproachDel, and ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM Unsignalized Method (Base Volume Alternative)

Intersection #104 Lake Chabot Rd / Estudillo Ave

Average Delay (sec/veh): 1.2 Worst Case Level Of Service: A[ 10.0]

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign, Uncontrolled), Rights (Include), Lanes (0-1).

Table with 12 columns: Volume Module, Count, Date (6 Nov 2012), and various traffic volume metrics (Base Vol, Growth Adj, etc.).

Table with 12 columns: Critical Gap Module, Critical Gp, FollowUpTim, and various delay metrics.

Table with 12 columns: Capacity Module, Cnflct Vol, Potent Cap., Move Cap., Volume/Cap., and various capacity metrics.

Table with 12 columns: Level Of Service Module, 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., Shared Queue, Shrd ConDel, Shared LOS, ApproachDel, ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM 4-Way Stop Method (Base Volume Alternative)

Intersection #105 SB-Off-Grand

Cycle (sec): 100 Critical Vol./Cap.(X): 0.645

Loss Time (sec): 0 Average Delay (sec/veh): 17.8

Optimal Cycle: 0 Level Of Service: C

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign), Rights (Include), Lanes (0-1).

Table with 12 columns: Volume Module, Count, Date (28 Feb 2013), and various traffic volume metrics.

Table with 12 columns: Saturation Flow Module, Adjustment, Lanes, Final Sat., and various saturation metrics.

Table with 12 columns: Capacity Analysis Module, Vol/Sat, Crit Moves, Delay/Veh, AdjDel/Veh, LOS by Move, ApproachDel, Delay Adj, ApprAdjDel, LOS by Appr, AllWayAvgQ.

Note: Queue reported is the number of cars per lane.

## Scenario Report

Scenario: EX PM  
 Command: EX PM  
 Volume: EX PM  
 Geometry: Default Geometry  
 Impact Fee: Default Impact Fee  
 Trip Generation: None  
 Trip Distribution: None  
 Paths: Default Path  
 Routes: Default Route  
 Configuration: Default Configuration

Turning Movement Report  
None

| Volume Type                         | Northbound |      |       | Southbound |      |       | Eastbound |      |       | Westbound |      |       | Total Volume |
|-------------------------------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|--------------|
|                                     | Left       | Thru | Right | Left       | Thru | Right | Left      | Thru | Right | Left      | Thru | Right |              |
| #5                                  |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #15 Grand/MacArthur/Off-Ramp        |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #101                                |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 4     | 360       | 102  | 0     | 0         | 35   | 8     | 509          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 4     | 360       | 102  | 0     | 0         | 35   | 8     | 509          |
| #102 MacArthur Blvd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 204        | 190  | 200   | 127        | 212  | 173   | 43        | 522  | 259   | 39        | 86   | 23    | 2078         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 204        | 190  | 200   | 127        | 212  | 173   | 43        | 522  | 259   | 39        | 86   | 23    | 2078         |
| #103 Benedict Dr / Estudillo Ave    |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 28         | 17   | 8     | 6          | 2    | 15    | 584       | 198  | 66    | 6         | 106  | 51    | 1087         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 28         | 17   | 8     | 6          | 2    | 15    | 584       | 198  | 66    | 6         | 106  | 51    | 1087         |
| #104 Lake Chabot Rd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 4          | 0    | 39    | 41        | 185  | 0     | 0         | 114  | 5     | 388          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 4          | 0    | 39    | 41        | 185  | 0     | 0         | 114  | 5     | 388          |
| #105 SB-Off-Grand                   |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 3          | 68   | 0     | 0          | 595  | 38    | 54        | 0    | 79    | 253       | 118  | 73    | 1281         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 3          | 68   | 0     | 0          | 595  | 38    | 54        | 0    | 79    | 253       | 118  | 73    | 1281         |

Impact Analysis Report  
Level Of Service

| Intersection                        | Base    |             | Future  |             | Change<br>in |
|-------------------------------------|---------|-------------|---------|-------------|--------------|
|                                     | Del/    | V/          | Del/    | V/          |              |
| #101                                | LOS Veh | C           | LOS Veh | C           |              |
|                                     | A       | 8.5 0.274   | A       | 8.5 0.274   | + 0.000 D/V  |
| #102 MacArthur Blvd / Estudillo Ave | B       | 16.6 0.566  | B       | 16.6 0.566  | + 0.000 D/V  |
| #103 Benedict Dr / Estudillo Ave    | F       | 221.1 0.670 | F       | 221.1 0.670 | + 0.000 D/V  |
| #104 Lake Chabot Rd / Estudillo Ave | A       | 9.4 0.052   | A       | 9.4 0.052   | + 0.000 D/V  |
| #105 SB-Off-Grand                   | C       | 17.9 0.666  | C       | 17.9 0.666  | + 0.000 V/C  |

Level Of Service Computation Report  
2000 HCM Unsignalized Method (Base Volume Alternative)

```

*****
Intersection #101
*****
Average Delay (sec/veh):      5.8      Worst Case Level Of Service: A[ 8.5]
*****
Approach:      North Bound      South Bound      East Bound      West Bound
Movement:      L - T - R      L - T - R      L - T - R      L - T - R
-----|-----|-----|-----|
Control:      Stop Sign      Stop Sign      Uncontrolled      Uncontrolled
Rights:      Include      Include      Include      Include
Lanes:      0 0 0 0 0      0 0 0 0 1      0 1 0 0 0      0 0 0 1 0
-----|-----|-----|-----|
Volume Module: >> Count Date: 6 Nov 2012 << 4:45
Base Vol:      0 0 0 0 0      4 360 102 0 0 35 8
Growth Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
Initial Bse: 0 0 0 0 0      4 360 102 0 0 35 8
User Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
PHF Adj: 1.00 1.00 1.00 0.50 0.50 0.50 0.84 0.84 0.84 0.77 0.77 0.77
PHF Volume: 0 0 0 0 0      8 429 121 0 0 45 10
Reduct Vol: 0 0 0 0 0      0 0 0 0 0 0 0 0
FinalVolume: 0 0 0 0 0      8 429 121 0 0 45 10
-----|-----|-----|-----|
Critical Gap Module:
Critical Gp:xxxxx xxxx xxxxx xxxxx xxxxx 6.2 4.1 xxxx xxxxx xxxxx xxxx xxxxx
FollowUpTim:xxxxx xxxx xxxxx xxxxx xxxxx 3.3 2.2 xxxx xxxxx xxxxx xxxx xxxxx
-----|-----|-----|-----|
Capacity Module:
Cnflct Vol: xxxx xxxx xxxxx xxxx xxxxx 51 56 xxxx xxxxx xxxx xxxx xxxxx
Potent Cap.: xxxx xxxx xxxxx xxxx xxxxx 1023 1562 xxxx xxxxx xxxx xxxx xxxxx
Move Cap.: xxxx xxxx xxxxx xxxx xxxxx 1023 1562 xxxx xxxxx xxxx xxxx xxxxx
Volume/Cap: xxxx xxxx xxxxx xxxx xxxxx 0.01 0.27 xxxx xxxxx xxxx xxxx xxxxx
-----|-----|-----|-----|
Level Of Service Module:
2Way95thQ: xxxx xxxx xxxxx xxxx xxxxx 0.0 1.1 xxxx xxxxx xxxx xxxx xxxxx
Control Del:xxxxx xxxx xxxxx xxxxx xxxxx 8.5 8.2 xxxx xxxxx xxxxx xxxx xxxxx
LOS by Move: * * * * * A A * * * * *
Movement: LT - LTR - RT LT - LTR - RT LT - LTR - RT LT - LTR - RT
Shared Cap.: xxxx xxxx xxxxx xxxx xxxxx xxxxx xxxxx xxxxx xxxx xxxx xxxxx
SharedQueue:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 1.1 xxxx xxxxx xxxxx xxxx xxxxx
Shrd ConDel:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 8.2 xxxx xxxxx xxxxx xxxx xxxxx
Shared LOS: * * * * * A * * * * *
ApproachDel: xxxxxx 8.5 xxxxxx xxxxxx
ApproachLOS: * A * * *
*****
Note: Queue reported is the number of cars per lane.
*****

```

Level Of Service Computation Report
2000 HCM Operations Method (Base Volume Alternative)

Intersection #102 MacArthur Blvd / Estudillo Ave

Cycle (sec): 65 Critical Vol./Cap.(X): 0.566
Loss Time (sec): 0 Average Delay (sec/veh): 16.6
Optimal Cycle: 43 Level Of Service: B

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes, Min. Green, Y+R, and Lanes.

Table with 12 columns for counts and 12 columns for delay values. Rows include Volume Module, Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, PHF Volume, Reduct Vol, Reduced Vol, PCE Adj, MLF Adj, and Final Volume.

Table with 12 columns for counts and 12 columns for delay values. Rows include Saturation Flow Module, Vol/Lane, Adjustment, Lanes, and Final Sat.

Table with 12 columns for counts and 12 columns for delay values. Rows include Capacity Analysis Module, Vol/Sat, Crit Moves, Green/Cycle, Volume/Cap, Uniform Del, IncrementDel, InitQueueDel, Delay Adj, Delay/Veh, User DelAdj, AdjDel/Veh, LOS by Move, and HCM2kAvgQ.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM Unsignalized Method (Base Volume Alternative)

Intersection #103 Benedict Dr / Estudillo Ave

Average Delay (sec/veh): 18.5 Worst Case Level Of Service: F[221.1]

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes.

Table with 12 columns for counts and 12 columns for delay values. Rows include Volume Module, Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, PHF Volume, Reduct Vol, and Final Volume.

Table with 12 columns for counts and 12 columns for delay values. Rows include Critical Gap Module, Critical Gp, and FollowUpTim.

Table with 12 columns for counts and 12 columns for delay values. Rows include Capacity Module, Cnflct Vol, Potent Cap., Move Cap., and Volume/Cap.

Table with 12 columns for counts and 12 columns for delay values. Rows include Level Of Service Module, 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., SharedQueue, Shrd ConDel, Shared LOS, ApproachDel, and ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM Unsignalized Method (Base Volume Alternative)

Intersection #104 Lake Chabot Rd / Estudillo Ave

Average Delay (sec/veh): 1.8 Worst Case Level Of Service: A[ 9.4]

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign, Uncontrolled), Rights (Include), Lanes (0-1).

Volume Module: >> Count Date: 6 Nov 2012 << 4:30. Table with 12 columns for volume counts and 4 rows for Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, PHF Volume, Reduct Vol, Final Volume.

Critical Gap Module: Table with 4 columns for approaches and 4 rows for Critical Gp, FollowUpTim, Capacity Module, and Level Of Service Module.

Capacity Module: Table with 4 columns for approaches and 4 rows for Cnflct Vol, Potent Cap., Move Cap., Volume/Cap.

Level Of Service Module: Table with 4 columns for approaches and 4 rows for 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., Shared Queue, Shrd ConDel, Shared LOS, ApproachDel, ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level Of Service Computation Report
2000 HCM 4-Way Stop Method (Base Volume Alternative)

Intersection #105 SB-Off-Grand

Cycle (sec): 100 Critical Vol./Cap.(X): 0.666

Loss Time (sec): 0 Average Delay (sec/veh): 17.9

Optimal Cycle: 0 Level Of Service: C

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign), Rights (Include), Min. Green (0-1), Lanes (0-1).

Volume Module: >> Count Date: 28 Feb 2013 << 4:45-5:45. Table with 12 columns for volume counts and 8 rows for Base Vol, Growth Adj, Initial Bse, User Adj, PHF Adj, PHF Volume, Reduct Vol, Reduced Vol, PCE Adj, MLF Adj, Final Volume.

Saturation Flow Module: Table with 12 columns for approaches and 4 rows for Adjustment, Lanes, Final Sat., Capacity Analysis Module.

Capacity Analysis Module: Table with 12 columns for approaches and 4 rows for Vol/Sat, Crit Moves, Delay/Veh, AdjDel/Veh, LOS by Move, ApproachDel, Delay Adj, ApprAdjDel, LOS by Appr, AllWayAvgQ.

Note: Queue reported is the number of cars per lane.



Scenario Report

Scenario: EX + Project AM

Command: EX + Project AM

Volume: EX AM

Geometry: Default Geometry

Impact Fee: Default Impact Fee

Trip Generation: AM TG

Trip Distribution: TD

Paths: Default Path

Routes: Default Route

Configuration: Default Configuration

Trip Generation Report

Forecast for AM TG

| Zone # | Subzone         | Amount | Units          | Rate In | Rate Out | Trips In | Trips Out | Total Trips | % Of Total |
|--------|-----------------|--------|----------------|---------|----------|----------|-----------|-------------|------------|
| 1      | Worker          | 1.00   | Worker         | 63.00   | 0.00     | 63       | 0         | 63          | 91.3       |
|        | Zone 1 Subtotal |        |                |         |          | 63       | 0         | 63          | 91.3       |
| 2      | Truck           | 1.00   | Material Truck | 3.00    | 3.00     | 3        | 3         | 6           | 8.7        |
|        | Zone 2 Subtotal |        |                |         |          | 3        | 3         | 6           | 8.7        |
| TOTAL  |                 |        |                |         |          | 66       | 3         | 69          | 100.0      |

## Trip Distribution Report

## Percent Of Trips TD

| Zone | To Gates |       |
|------|----------|-------|
|      | 1        | 6     |
| 1    | 50.0     | 50.0  |
| 2    | 0.0      | 100.0 |

Turning Movement Report  
AM TG

| Volume Type                         | Northbound |      |       | Southbound |      |       | Eastbound |      |       | Westbound |      |       | Total Volume |
|-------------------------------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|--------------|
|                                     | Left       | Thru | Right | Left       | Thru | Right | Left      | Thru | Right | Left      | Thru | Right |              |
| #5                                  |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #15 Grand/MacArthur/Off-Ramp        |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 32   | 0     | 0          | 3    | 0     | 0         | 0    | 0     | 0         | 0    | 35    | 70           |
| Total                               | 0          | 32   | 0     | 0          | 3    | 0     | 0         | 0    | 0     | 0         | 0    | 35    | 70           |
| #101                                |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 4     | 380       | 59   | 0     | 0         | 53   | 13    | 509          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 4     | 380       | 59   | 0     | 0         | 53   | 13    | 509          |
| #102 MacArthur Blvd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 439        | 238  | 141   | 113        | 243  | 167   | 29        | 320  | 127   | 66        | 178  | 42    | 2103         |
| Added                               | 0          | 0    | 66    | 0          | 0    | 0     | 0         | 0    | 0     | 3         | 0    | 0     | 69           |
| Total                               | 439        | 238  | 207   | 113        | 243  | 167   | 29        | 320  | 127   | 69        | 178  | 42    | 2172         |
| #103 Benedict Dr / Estudillo Ave    |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 68         | 34   | 9     | 2          | 0    | 38    | 467       | 96   | 5     | 3         | 169  | 97    | 988          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 66   | 0     | 0         | 3    | 0     | 69           |
| Total                               | 68         | 34   | 9     | 2          | 0    | 38    | 467       | 162  | 5     | 3         | 172  | 97    | 1057         |
| #104 Lake Chabot Rd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 3          | 0    | 29    | 23        | 102  | 0     | 0         | 268  | 5     | 430          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 3     | 66        | 0    | 0     | 0         | 0    | 0     | 69           |
| Total                               | 0          | 0    | 0     | 3          | 0    | 32    | 89        | 102  | 0     | 0         | 268  | 5     | 499          |
| #105 SB-Off-Grand                   |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 5          | 133  | 0     | 0          | 550  | 34    | 27        | 0    | 35    | 217       | 110  | 71    | 1182         |
| Added                               | 0          | 0    | 0     | 0          | 3    | 0     | 0         | 0    | 0     | 0         | 0    | 32    | 35           |
| Total                               | 5          | 133  | 0     | 0          | 553  | 34    | 27        | 0    | 35    | 217       | 110  | 103   | 1217         |

Impact Analysis Report  
Level Of Service

| Intersection                        | Base    |             | Future  |             | Change<br>in |
|-------------------------------------|---------|-------------|---------|-------------|--------------|
|                                     | Del/    | V/          | Del/    | V/          |              |
| #101                                | LOS Veh | C           | LOS Veh | C           |              |
|                                     | A       | 8.6 0.289   | A       | 8.6 0.289   | + 0.000 D/V  |
| #102 MacArthur Blvd / Estudillo Ave | B       | 18.9 0.658  | B       | 18.8 0.658  | -0.117 D/V   |
| #103 Benedict Dr / Estudillo Ave    | F       | 593.1 1.454 | F       | 723.1 1.653 | +130.056 D/V |
| #104 Lake Chabot Rd / Estudillo Ave | A       | 10.0 0.038  | B       | 10.1 0.068  | + 0.135 D/V  |
| #105 SB-Off-Grand                   | C       | 17.8 0.645  | C       | 18.4 0.657  | + 0.012 V/C  |

Level Of Service Computation Report  
2000 HCM Unsignalized Method (Future Volume Alternative)

```

*****
Intersection #101
*****
Average Delay (sec/veh):      6.2      Worst Case Level Of Service: A[ 8.6]
*****
Approach:      North Bound      South Bound      East Bound      West Bound
Movement:      L - T - R      L - T - R      L - T - R      L - T - R
-----|-----|-----|-----|
Control:      Stop Sign      Stop Sign      Uncontrolled      Uncontrolled
Rights:      Include      Include      Include      Include
Lanes:      0 0 0 0 0      0 0 0 0 1      0 1 0 0 0      0 0 0 1 0
-----|-----|-----|-----|
Volume Module: >> Count Date: 6 Nov 2012 << 7:30
Base Vol:      0 0 0 0 0      4 380 59 0 0 53 13
Growth Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
Initial Bse: 0 0 0 0 0      4 380 59 0 0 53 13
Added Vol: 0 0 0 0 0      0 0 0 0 0 0 0
PasserByVol: 0 0 0 0 0      0 0 0 0 0 0 0
Initial Fut: 0 0 0 0 0      4 380 59 0 0 53 13
User Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
PHF Adj: 1.00 1.00 1.00 0.50 0.50 0.50 0.86 0.86 1.00 1.00 0.83 0.83
PHF Volume: 0 0 0 0 0      8 442 69 0 0 64 16
Reduct Vol: 0 0 0 0 0      0 0 0 0 0 0 0
FinalVolume: 0 0 0 0 0      8 442 69 0 0 64 16
-----|-----|-----|-----|
Critical Gap Module:
Critical Gp:xxxxx xxxx xxxxx xxxxx xxxxx 6.2 4.1 xxxx xxxxx xxxxx xxxx xxxxx
FollowUpTim:xxxxx xxxx xxxxx xxxxx xxxxx 3.3 2.2 xxxx xxxxx xxxxx xxxx xxxxx
-----|-----|-----|-----|
Capacity Module:
Cnflct Vol: xxxx xxxx xxxxx xxxx xxxxx 72 80 xxxx xxxxx xxxx xxxx xxxxx
Potent Cap.: xxxx xxxx xxxxx xxxx xxxxx 996 1531 xxxx xxxxx xxxx xxxx xxxxx
Move Cap.: xxxx xxxx xxxxx xxxx xxxxx 996 1531 xxxx xxxxx xxxx xxxx xxxxx
Volume/Cap: xxxx xxxx xxxxx xxxx xxxxx 0.01 0.29 xxxx xxxxx xxxx xxxx xxxxx
-----|-----|-----|-----|
Level Of Service Module:
2Way95thQ: xxxx xxxx xxxxx xxxx xxxxx 0.0 1.2 xxxx xxxxx xxxx xxxx xxxxx
Control Del:xxxxx xxxx xxxxx xxxxx xxxxx 8.6 8.3 xxxx xxxxx xxxxx xxxx xxxxx
LOS by Move: * * * * * A A * * * * *
Movement: LT - LTR - RT LT - LTR - RT LT - LTR - RT LT - LTR - RT
Shared Cap.: xxxx xxxx xxxxx xxxx xxxxx xxxxx xxxx xxxx xxxxx xxxx xxxx xxxxx
SharedQueue:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 1.2 xxxx xxxxx xxxxx xxxx xxxxx
Shrd ConDel:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 8.3 xxxx xxxxx xxxxx xxxx xxxxx
Shared LOS: * * * * * A * * * * *
ApproachDel: xxxxxx 8.6 xxxxxx xxxxxx
ApproachLOS: * A *
*****
Note: Queue reported is the number of cars per lane.
*****

```

Level of Service Computation Report
2000 HCM Operations Method (Future Volume Alternative)

Intersection #102 MacArthur Blvd / Estudillo Ave

Cycle (sec): 65 Critical Vol./Cap.(X): 0.658
Loss Time (sec): 0 Average Delay (sec/veh): 18.8
Optimal Cycle: 54 Level Of Service: B

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Approach, Movement, Control, Rights, Lanes, Min. Green, Y+R, and Lanes.

Table with 12 columns for volume counts. Rows include Volume Module, Base Vol, Growth Adj, Initial Bse, Added Vol, PasserByVol, Initial Fut, User Adj, PHF Adj, PHF Volume, Reduct Vol, Reduced Vol, PCE Adj, MLF Adj, and FinalVolume.

Table with 12 columns for saturation flow. Rows include Sat/Lane, Adjustment, Lanes, and Final Sat.

Table with 12 columns for capacity analysis. Rows include Vol/Sat, Crit Moves, Green/Cycle, Volume/Cap, Uniform Del, IncrementDel, InitQueueDel, Delay Adj, Delay/Veh, User DelAdj, AdjDel/Veh, LOS by Move, and HCM2kAvgQ.

Note: Queue reported is the number of cars per lane.

Level of Service Computation Report
2000 HCM Unsignalized Method (Future Volume Alternative)

Intersection #103 Benedict Dr / Estudillo Ave

Average Delay (sec/veh): 97.7 Worst Case Level Of Service: F[723.1]

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Approach, Movement, Control, Rights, Lanes.

Table with 12 columns for volume counts. Rows include Volume Module, Base Vol, Growth Adj, Initial Bse, Added Vol, PasserByVol, Initial Fut, User Adj, PHF Adj, PHF Volume, Reduct Vol, and FinalVolume.

Table with 12 columns for critical gap. Rows include Critical Gap Module, Critical Gp, and FollowUpTim.

Table with 12 columns for capacity. Rows include Capacity Module, Cnflct Vol, Potent Cap., Move Cap., and Volume/Cap.

Table with 12 columns for level of service. Rows include Level Of Service Module, 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., Shared Queue, Shrd ConDel, Shared LOS, ApproachDel, and ApproachLOS.

Note: Queue reported is the number of cars per lane.

\*\*\*\*\*

Level of Service Computation Report
2000 HCM Unsignalized Method (Future Volume Alternative)

Intersection #104 Lake Chabot Rd / Estudillo Ave

Average Delay (sec/veh): 2.1 Worst Case Level of Service: B[ 10.1]

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign, Uncontrolled), Rights (Include), and Lanes (0-1).

Table with 12 columns: Volume Module, Count, Date (6 Nov 2012), and various traffic volume metrics (Base Vol, Growth Adj, Initial Bse, etc.).

Table with 12 columns: Critical Gap Module, Critical Gp, FollowUpTim, and various gap and timing metrics.

Table with 12 columns: Capacity Module, Cnflct Vol, Potent Cap., Move Cap., and Volume/Cap.

Table with 12 columns: Level of Service Module, 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., Shared Queue, Shrd ConDel, Shared LOS, ApproachDel, and ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level of Service Computation Report
2000 HCM 4-Way Stop Method (Future Volume Alternative)

Intersection #105 SB-Off-Grand

Cycle (sec): 100 Critical Vol./Cap.(X): 0.657

Loss Time (sec): 0 Average Delay (sec/veh): 18.4

Optimal Cycle: 0 Level of Service: C

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound), Movement (L-T-R), Control (Stop Sign), Rights (Include), and Lanes (0-1).

Table with 12 columns: Volume Module, Count, Date (28 Feb 2013), and various traffic volume metrics.

Table with 12 columns: Saturation Flow Module, Adjustment, Lanes, and Final Sat.

Table with 12 columns: Capacity Analysis Module, Vol/Sat, Crit Moves, Delay/Veh, Delay Adj, AdjDel/Veh, LOS by Move, ApproachDel, Delay Adj, ApprAdjDel, LOS by Appr, and AllWayAvgQ.

Note: Queue reported is the number of cars per lane.

Scenario Report

Scenario: EX + Project PM  
 Command: EX + Project PM  
 Volume: EX PM  
 Geometry: Default Geometry  
 Impact Fee: Default Impact Fee  
 Trip Generation: PM TG  
 Trip Distribution: TD  
 Paths: Default Path  
 Routes: Default Route  
 Configuration: Default Configuration

Trip Generation Report

Forecast for PM TG

| Zone # | Subzone         | Amount | Units          | Rate In | Rate Out | Trips In | Trips Out | Total Trips | % Of Total |
|--------|-----------------|--------|----------------|---------|----------|----------|-----------|-------------|------------|
| 1      | Worker          | 1.00   | Worker         | 0.00    | 63.00    | 0        | 63        | 63          | 91.3       |
|        | Zone 1 Subtotal |        |                |         |          | 0        | 63        | 63          | 91.3       |
| 2      | Truck           | 1.00   | Material Truck | 3.00    | 3.00     | 3        | 3         | 6           | 8.7        |
|        | Zone 2 Subtotal |        |                |         |          | 3        | 3         | 6           | 8.7        |
| TOTAL  |                 |        |                |         |          | 3        | 66        | 69          | 100.0      |

## Trip Distribution Report

## Percent Of Trips TD

| Zone | To Gates |       |
|------|----------|-------|
|      | 1        | 6     |
| 1    | 50.0     | 50.0  |
| 2    | 0.0      | 100.0 |

Turning Movement Report  
PM TG

| Volume Type                         | Northbound |      |       | Southbound |      |       | Eastbound |      |       | Westbound |      |       | Total Volume |
|-------------------------------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|--------------|
|                                     | Left       | Thru | Right | Left       | Thru | Right | Left      | Thru | Right | Left      | Thru | Right |              |
| #5                                  |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| #15 Grand/MacArthur/Off-Ramp        |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Added                               | 0          | 0    | 0     | 0          | 35   | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 3            |
| Total                               | 0          | 0    | 0     | 0          | 35   | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 3            |
| #101                                |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 0          | 0    | 4     | 360       | 102  | 0     | 0         | 35   | 8     | 509          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 0            |
| Total                               | 0          | 0    | 0     | 0          | 0    | 4     | 360       | 102  | 0     | 0         | 35   | 8     | 509          |
| #102 MacArthur Blvd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 204        | 190  | 200   | 127        | 212  | 173   | 43        | 522  | 259   | 39        | 86   | 23    | 2078         |
| Added                               | 0          | 0    | 3     | 0          | 0    | 0     | 0         | 0    | 0     | 35        | 0    | 0     | 38           |
| Total                               | 204        | 190  | 203   | 127        | 212  | 173   | 43        | 522  | 259   | 74        | 86   | 23    | 2116         |
| #103 Benedict Dr / Estudillo Ave    |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 28         | 17   | 8     | 6          | 2    | 15    | 584       | 198  | 66    | 6         | 106  | 51    | 1087         |
| Added                               | 0          | 0    | 0     | 0          | 0    | 0     | 0         | 3    | 0     | 0         | 35   | 32    | 70           |
| Total                               | 28         | 17   | 8     | 6          | 2    | 15    | 584       | 201  | 66    | 6         | 141  | 83    | 1157         |
| #104 Lake Chabot Rd / Estudillo Ave |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 0          | 0    | 0     | 4          | 0    | 39    | 41        | 185  | 0     | 0         | 114  | 5     | 388          |
| Added                               | 0          | 0    | 0     | 0          | 0    | 66    | 3         | 0    | 0     | 0         | 0    | 0     | 69           |
| Total                               | 0          | 0    | 0     | 4          | 0    | 105   | 44        | 185  | 0     | 0         | 114  | 5     | 457          |
| #105 SB-Off-Grand                   |            |      |       |            |      |       |           |      |       |           |      |       |              |
| Base                                | 3          | 68   | 0     | 0          | 595  | 38    | 54        | 0    | 79    | 253       | 118  | 73    | 1281         |
| Added                               | 0          | 0    | 0     | 0          | 35   | 0     | 0         | 0    | 0     | 0         | 0    | 0     | 35           |
| Total                               | 3          | 68   | 0     | 0          | 630  | 38    | 54        | 0    | 79    | 253       | 118  | 73    | 1316         |

Impact Analysis Report  
Level Of Service

| Intersection                        | Base    |             | Future  |             | Change<br>in |
|-------------------------------------|---------|-------------|---------|-------------|--------------|
|                                     | Del/    | V/          | Del/    | V/          |              |
| #101                                | LOS Veh | C           | LOS Veh | C           |              |
|                                     | A       | 8.5 0.274   | A       | 8.5 0.274   | + 0.000 D/V  |
| #102 MacArthur Blvd / Estudillo Ave | B       | 16.6 0.566  | B       | 16.5 0.566  | -0.079 D/V   |
| #103 Benedict Dr / Estudillo Ave    | F       | 221.1 0.670 | F       | 276.2 0.759 | +55.089 D/V  |
| #104 Lake Chabot Rd / Estudillo Ave | A       | 9.4 0.052   | A       | 9.7 0.140   | + 0.285 D/V  |
| #105 SB-Off-Grand                   | C       | 17.9 0.666  | C       | 19.1 0.704  | + 0.038 V/C  |

Level Of Service Computation Report  
2000 HCM Unsignalized Method (Future Volume Alternative)

```

*****
Intersection #101
*****
Average Delay (sec/veh):      5.8      Worst Case Level Of Service: A[ 8.5]
*****
Approach:      North Bound      South Bound      East Bound      West Bound
Movement:      L - T - R      L - T - R      L - T - R      L - T - R
-----|-----|-----|-----|
Control:      Stop Sign      Stop Sign      Uncontrolled      Uncontrolled
Rights:      Include      Include      Include      Include
Lanes:      0 0 0 0 0      0 0 0 0 1      0 1 0 0 0      0 0 0 1 0
-----|-----|-----|-----|
Volume Module: >> Count Date: 6 Nov 2012 << 4:45
Base Vol:      0 0 0 0 0      4 360 102 0 0 35 8
Growth Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
Initial Bse: 0 0 0 0 0      4 360 102 0 0 35 8
Added Vol: 0 0 0 0 0      0 0 0 0 0 0 0
PasserByVol: 0 0 0 0 0      0 0 0 0 0 0 0
Initial Fut: 0 0 0 0 0      4 360 102 0 0 35 8
User Adj: 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00 1.00
PHF Adj: 1.00 1.00 1.00 0.50 0.50 0.50 0.84 0.84 0.84 0.77 0.77 0.77
PHF Volume: 0 0 0 0 0      8 429 121 0 0 45 10
Reduct Vol: 0 0 0 0 0      0 0 0 0 0 0 0
FinalVolume: 0 0 0 0 0      8 429 121 0 0 45 10
-----|-----|-----|-----|
Critical Gap Module:
Critical Gp:xxxxx xxxx xxxxx xxxxx xxxxx 6.2 4.1 xxxx xxxxx xxxxx xxxx xxxxx
FollowUpTim:xxxxx xxxx xxxxx xxxxx xxxxx 3.3 2.2 xxxx xxxxx xxxxx xxxx xxxxx
-----|-----|-----|-----|
Capacity Module:
Cnflct Vol: xxxx xxxx xxxxx xxxx xxxxx 51 56 xxxx xxxxx xxxx xxxx xxxxx
Potent Cap.: xxxx xxxx xxxxx xxxx xxxxx 1023 1562 xxxx xxxxx xxxx xxxx xxxxx
Move Cap.: xxxx xxxx xxxxx xxxx xxxxx 1023 1562 xxxx xxxxx xxxx xxxx xxxxx
Volume/Cap: xxxx xxxx xxxxx xxxx xxxxx 0.01 0.27 xxxx xxxxx xxxx xxxx xxxxx
-----|-----|-----|-----|
Level Of Service Module:
2Way95thQ: xxxx xxxx xxxxx xxxx xxxxx 0.0 1.1 xxxx xxxxx xxxx xxxx xxxxx
Control Del:xxxxx xxxx xxxxx xxxxx xxxxx 8.5 8.2 xxxx xxxxx xxxxx xxxx xxxxx
LOS by Move: * * * * * A A * * * * *
Movement: LT - LTR - RT LT - LTR - RT LT - LTR - RT LT - LTR - RT
Shared Cap.: xxxx xxxx xxxxx xxxx xxxxx xxxxx xxxx xxxxx xxxxx xxxx xxxxx xxxxx
SharedQueue:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 1.1 xxxx xxxxx xxxxx xxxx xxxxx
Shrd ConDel:xxxxx xxxx xxxxx xxxxx xxxxx xxxxx 8.2 xxxx xxxxx xxxxx xxxx xxxxx
Shared LOS: * * * * * A * * * * *
ApproachDel: xxxxxx 8.5 xxxxxx xxxxxx
ApproachLOS: * A *
*****
Note: Queue reported is the number of cars per lane.
*****

```



Level of Service Computation Report
2000 HCM Operations Method (Future Volume Alternative)

Intersection #102 MacArthur Blvd / Estudillo Ave

Cycle (sec): 65 Critical Vol./Cap.(X): 0.566
Loss Time (sec): 0 Average Delay (sec/veh): 16.5
Optimal Cycle: 43 Level Of Service: B

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes, Min. Green, Y+R, and Lanes.

Table with 12 columns: Volume Module, Count, Date, and 10 traffic volume categories. Includes rows for Base Vol, Growth Adj, Initial Bse, etc.

Table with 12 columns: Sat/Lane, Adjustment, Lanes, Final Sat. Rows show saturation flow and final saturation values.

Table with 12 columns: Capacity Analysis Module. Rows include Vol/Sat, Crit Moves, Green/Cycle, Volume/Cap, etc.

Note: Queue reported is the number of cars per lane.

Level of Service Computation Report
2000 HCM Unsignalized Method (Future Volume Alternative)

Intersection #103 Benedict Dr / Estudillo Ave

Average Delay (sec/veh): 20.5 Worst Case Level Of Service: F[276.2]

Table with 4 columns: North Bound, South Bound, East Bound, West Bound. Rows include Movement, Control, Rights, Lanes.

Table with 12 columns: Volume Module, Count, Date, and 10 traffic volume categories. Includes rows for Base Vol, Growth Adj, Initial Bse, etc.

Table with 12 columns: Critical Gap Module. Rows show critical gap and follow-up time values.

Table with 12 columns: Capacity Module. Rows include Cnflct Vol, Potent Cap., Move Cap., Volume/Cap.

Table with 12 columns: Level of Service Module. Rows include 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., etc.

Note: Queue reported is the number of cars per lane.

Level of Service Computation Report
2000 HCM Unsignalized Method (Future Volume Alternative)

Intersection #104 Lake Chabot Rd / Estudillo Ave

Average Delay (sec/veh): 3.1 Worst Case Level of Service: A[ 9.7]

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound) and Movement (L-T-R). Rows include Control, Rights, and Lanes.

Table with 12 columns: Volume Module, Count, Date, and 11 volume categories (Base Vol, Growth Adj, Initial Bse, etc.).

Table with 12 columns: Critical Gap Module, Critical Gp, FollowUpTim, and 10 gap categories.

Table with 12 columns: Capacity Module, Cnflct Vol, Potent Cap., Move Cap., Volume/Cap, and 10 capacity categories.

Table with 12 columns: Level of Service Module, 2Way95thQ, Control Del, LOS by Move, Movement, Shared Cap., Shared Queue, Shrd ConDel, Shared LOS, ApproachDel, ApproachLOS.

Note: Queue reported is the number of cars per lane.

Level of Service Computation Report
2000 HCM 4-Way Stop Method (Future Volume Alternative)

Intersection #105 SB-Off-Grand

Cycle (sec): 100 Critical Vol./Cap.(X): 0.704

Loss Time (sec): 0 Average Delay (sec/veh): 19.1

Optimal Cycle: 0 Level of Service: C

Table with 4 columns: Approach (North Bound, South Bound, East Bound, West Bound) and Movement (L-T-R). Rows include Control, Rights, and Lanes.

Table with 12 columns: Volume Module, Count, Date, and 11 volume categories (Base Vol, Growth Adj, Initial Bse, etc.).

Table with 12 columns: Saturation Flow Module, Adjustment, Lanes, Final Sat., and 10 saturation categories.


Table with 12 columns: Capacity Analysis Module, Vol/Sat, Crit Moves, Delay/Veh, Delay Adj, AdjDel/Veh, LOS by Move, ApproachDel, Delay Adj, ApprAdjDel, LOS by Appr, AllWayAvgQ.

Note: Queue reported is the number of cars per lane.

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|   |                                  |                          |
|---|----------------------------------|--------------------------|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY          | <b>SURVEY DATE:</b> 11/6/2012    | <b>DAY:</b> TUESDAY      |
| <b>N-S APPROACH:</b> FOOTHILL BOULEVARD           | <b>SURVEY TIME:</b> 7:00 AM      | <b>TO:</b> 9:00 AM       |
| <b>E-W APPROACH:</b> DUTTON AVENUE - MARLOW DRIVE | <b>JURISDICTION:</b> SAN LEANDRO | <b>FILE:</b> 3211076-1AM |



| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM |            |      |       | 0          |      | 2     | 58        | 12   |       |           | 13   | 1     | 86    |
| 7:15 AM                | to 7:30 AM |            |      |       | 0          |      | 3     | 139       | 17   |       |           | 23   | 5     | 187   |
| 7:30 AM                | to 7:45 AM |            |      |       | 0          |      | 4     | 255       | 29   |       |           | 36   | 11    | 335   |
| 7:45 AM                | to 8:00 AM |            |      |       | 0          |      | 4     | 344       | 39   |       |           | 53   | 13    | 453   |
| 8:00 AM                | to 8:15 AM |            |      |       | 0          |      | 6     | 441       | 60   |       |           | 72   | 14    | 593   |
| 8:15 AM                | to 8:30 AM |            |      |       | 0          |      | 7     | 519       | 76   |       |           | 76   | 18    | 696   |
| 8:30 AM                | to 8:45 AM |            |      |       | 0          |      | 8     | 570       | 85   |       |           | 83   | 20    | 766   |
| 8:45 AM                | to 9:00 AM |            |      |       | 0          |      | 9     | 625       | 100  |       |           | 99   | 21    | 854   |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM | 0          | 0    | 0     | 0          | 0    | 2     | 58        | 12   | 0     | 0         | 13   | 1     | 86    |
| 7:15 AM                | to 7:30 AM | 0          | 0    | 0     | 0          | 0    | 1     | 81        | 5    | 0     | 0         | 10   | 4     | 101   |
| 7:30 AM                | to 7:45 AM | 0          | 0    | 0     | 0          | 0    | 1     | 116       | 12   | 0     | 0         | 13   | 6     | 148   |
| 7:45 AM                | to 8:00 AM | 0          | 0    | 0     | 0          | 0    | 0     | 89        | 10   | 0     | 0         | 17   | 2     | 118   |
| 8:00 AM                | to 8:15 AM | 0          | 0    | 0     | 0          | 0    | 2     | 97        | 21   | 0     | 0         | 19   | 1     | 140   |
| 8:15 AM                | to 8:30 AM | 0          | 0    | 0     | 0          | 0    | 1     | 78        | 16   | 0     | 0         | 4    | 4     | 103   |
| 8:30 AM                | to 8:45 AM | 0          | 0    | 0     | 0          | 0    | 1     | 51        | 9    | 0     | 0         | 7    | 2     | 70    |
| 8:45 AM                | to 9:00 AM | 0          | 0    | 0     | 0          | 0    | 1     | 55        | 15   | 0     | 0         | 16   | 1     | 88    |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 8:00 AM | 0          | 0    | 0     | 0          | 0    | 4     | 344       | 39   | 0     | 0         | 53   | 13    | 453   |
| 7:15 AM                | to 8:15 AM | 0          | 0    | 0     | 0          | 0    | 4     | 383       | 48   | 0     | 0         | 59   | 13    | 507   |
| 7:30 AM                | to 8:30 AM | 0          | 0    | 0     | 0          | 0    | 4     | 380       | 59   | 0     | 0         | 53   | 13    | 509   |
| 7:45 AM                | to 8:45 AM | 0          | 0    | 0     | 0          | 0    | 4     | 315       | 56   | 0     | 0         | 47   | 9     | 431   |
| 8:00 AM                | to 9:00 AM | 0          | 0    | 0     | 0          | 0    | 5     | 281       | 61   | 0     | 0         | 46   | 8     | 401   |

TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|   |  |                                  |  |                          |  |
|---|--|----------------------------------|--|--------------------------|--|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY          |  | <b>SURVEY DATE:</b> 11/6/2012    |  | <b>DAY:</b> TUESDAY      |  |
| <b>N-S APPROACH:</b> FOOTHILL BOULEVARD           |  | <b>SURVEY TIME:</b> 4:00 PM      |  | <b>TO:</b> 6:00 PM       |  |
| <b>E-W APPROACH:</b> DUTTON AVENUE - MARLOW DRIVE |  | <b>JURISDICTION:</b> SAN LEANDRO |  | <b>FILE:</b> 3211076-1PM |  |

|  |     |   |   |  |   |     |
|--|-----|---|---|--|---|-----|
| <p style="text-align: center;">PEAK HOUR<br/>4:45 PM TO 5:45 PM</p> <p style="text-align: center;">↑<br/>NORTH</p> <div style="text-align: center;"> <table border="1" style="margin: 0 auto;"> <tr><td>4</td><td>0</td><td>0</td></tr> </table> <p style="text-align: center;">MARLOW DRIVE</p> <p style="text-align: center;">DUTTON AVENUE</p> <p style="text-align: center;">FOOTHILL BOULEVARD</p> </div> | 4   | 0 | 0 | <p style="text-align: center;">ARRIVAL / DEPARTURE VOLUMES</p> <p style="text-align: center;">PHF = 0.50</p> <div style="text-align: center;"> <table border="1" style="margin: 0 auto;"> <tr><td>4</td><td>368</td></tr> </table> <p style="text-align: center;">PHF = 0.77</p> <p style="text-align: center;">PHF = 0.84</p> <p style="text-align: center;">PHF = #DIV/0!</p> </div> | 4 | 368 |
| 4  | 0   | 0 |   |  |   |     |
| 4  | 368 |   |   |  |   |     |


| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM |            |      |       | 0          |      | 0     | 70        | 18   |       |           | 8    | 1     | 97    |
| 4:15 PM                | to 4:30 PM |            |      |       | 0          |      | 1     | 146       | 47   |       |           | 19   | 1     | 214   |
| 4:30 PM                | to 4:45 PM |            |      |       | 0          |      | 1     | 219       | 64   |       |           | 28   | 3     | 315   |
| 4:45 PM                | to 5:00 PM |            |      |       | 0          |      | 2     | 294       | 83   |       |           | 36   | 6     | 421   |
| 5:00 PM                | to 5:15 PM |            |      |       | 0          |      | 4     | 391       | 111  |       |           | 45   | 7     | 558   |
| 5:15 PM                | to 5:30 PM |            |      |       | 0          |      | 5     | 503       | 136  |       |           | 56   | 10    | 710   |
| 5:30 PM                | to 5:45 PM |            |      |       | 0          |      | 5     | 579       | 166  |       |           | 63   | 11    | 824   |
| 5:45 PM                | to 6:00 PM |            |      |       | 0          |      | 5     | 645       | 194  |       |           | 72   | 12    | 928   |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM | 0          | 0    | 0     | 0          | 0    | 0     | 70        | 18   | 0     | 0         | 8    | 1     | 97    |
| 4:15 PM                | to 4:30 PM | 0          | 0    | 0     | 0          | 0    | 1     | 76        | 29   | 0     | 0         | 11   | 0     | 117   |
| 4:30 PM                | to 4:45 PM | 0          | 0    | 0     | 0          | 0    | 0     | 73        | 17   | 0     | 0         | 9    | 2     | 101   |
| 4:45 PM                | to 5:00 PM | 0          | 0    | 0     | 0          | 0    | 1     | 75        | 19   | 0     | 0         | 8    | 3     | 106   |
| 5:00 PM                | to 5:15 PM | 0          | 0    | 0     | 0          | 0    | 2     | 97        | 28   | 0     | 0         | 9    | 1     | 137   |
| 5:15 PM                | to 5:30 PM | 0          | 0    | 0     | 0          | 0    | 1     | 112       | 25   | 0     | 0         | 11   | 3     | 152   |
| 5:30 PM                | to 5:45 PM | 0          | 0    | 0     | 0          | 0    | 0     | 76        | 30   | 0     | 0         | 7    | 1     | 114   |
| 5:45 PM                | to 6:00 PM | 0          | 0    | 0     | 0          | 0    | 0     | 66        | 28   | 0     | 0         | 9    | 1     | 104   |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 5:00 PM | 0          | 0    | 0     | 0          | 0    | 2     | 294       | 83   | 0     | 0         | 36   | 6     | 421   |
| 4:15 PM                | to 5:15 PM | 0          | 0    | 0     | 0          | 0    | 4     | 321       | 93   | 0     | 0         | 37   | 6     | 461   |
| 4:30 PM                | to 5:30 PM | 0          | 0    | 0     | 0          | 0    | 4     | 357       | 89   | 0     | 0         | 37   | 9     | 496   |
| 4:45 PM                | to 5:45 PM | 0          | 0    | 0     | 0          | 0    | 4     | 360       | 102  | 0     | 0         | 35   | 8     | 509   |
| 5:00 PM                | to 6:00 PM | 0          | 0    | 0     | 0          | 0    | 3     | 351       | 111  | 0     | 0         | 36   | 6     | 507   |

TEL: (510) 232 - 1271      FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|  |                                  |                          |
|--|----------------------------------|--------------------------|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY | <b>SURVEY DATE:</b> 11/6/2012    | <b>DAY:</b> TUESDAY      |
| <b>N-S APPROACH:</b> MacARTHUR BOULEVARD | <b>SURVEY TIME:</b> 7:00 AM      | <b>TO:</b> 9:00 AM       |
| <b>E-W APPROACH:</b> ESTUDILLO AVENUE    | <b>JURISDICTION:</b> SAN LEANDRO | <b>FILE:</b> 3211076-2AM |



| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM | 38         | 22   | 20    | 14         | 45   | 31    | 6         | 61   | 21    | 15        | 24   | 7     | 304   |
| 7:15 AM                | to 7:30 AM | 121        | 47   | 45    | 29         | 78   | 57    | 8         | 123  | 43    | 27        | 52   | 14    | 644   |
| 7:30 AM                | to 7:45 AM | 221        | 84   | 79    | 56         | 124  | 94    | 16        | 207  | 77    | 44        | 97   | 27    | 1126  |
| 7:45 AM                | to 8:00 AM | 330        | 150  | 109   | 86         | 203  | 133   | 25        | 273  | 102   | 62        | 137  | 38    | 1648  |
| 8:00 AM                | to 8:15 AM | 448        | 216  | 139   | 119        | 268  | 177   | 30        | 374  | 144   | 82        | 192  | 45    | 2234  |
| 8:15 AM                | to 8:30 AM | 560        | 285  | 186   | 142        | 321  | 224   | 37        | 443  | 170   | 93        | 230  | 56    | 2747  |
| 8:30 AM                | to 8:45 AM | 669        | 333  | 216   | 169        | 358  | 301   | 42        | 509  | 195   | 106       | 249  | 62    | 3209  |
| 8:45 AM                | to 9:00 AM | 759        | 359  | 237   | 193        | 398  | 381   | 48        | 569  | 214   | 114       | 272  | 67    | 3611  |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM | 38         | 22   | 20    | 14         | 45   | 31    | 6         | 61   | 21    | 15        | 24   | 7     | 304   |
| 7:15 AM                | to 7:30 AM | 83         | 25   | 25    | 15         | 33   | 26    | 2         | 62   | 22    | 12        | 28   | 7     | 340   |
| 7:30 AM                | to 7:45 AM | 100        | 37   | 34    | 27         | 46   | 37    | 8         | 84   | 34    | 17        | 45   | 13    | 482   |
| 7:45 AM                | to 8:00 AM | 109        | 66   | 30    | 30         | 79   | 39    | 9         | 66   | 25    | 18        | 40   | 11    | 522   |
| 8:00 AM                | to 8:15 AM | 118        | 66   | 30    | 33         | 65   | 44    | 5         | 101  | 42    | 20        | 55   | 7     | 586   |
| 8:15 AM                | to 8:30 AM | 112        | 69   | 47    | 23         | 53   | 47    | 7         | 69   | 26    | 11        | 38   | 11    | 513   |
| 8:30 AM                | to 8:45 AM | 109        | 48   | 30    | 27         | 37   | 77    | 5         | 66   | 25    | 13        | 19   | 6     | 462   |
| 8:45 AM                | to 9:00 AM | 90         | 26   | 21    | 24         | 40   | 80    | 6         | 60   | 19    | 8         | 23   | 5     | 402   |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 8:00 AM | 330        | 150  | 109   | 86         | 203  | 133   | 25        | 273  | 102   | 62        | 137  | 38    | 1648  |
| 7:15 AM                | to 8:15 AM | 410        | 194  | 119   | 105        | 223  | 146   | 24        | 313  | 123   | 67        | 168  | 38    | 1930  |
| 7:30 AM                | to 8:30 AM | 439        | 238  | 141   | 113        | 243  | 167   | 29        | 320  | 127   | 66        | 178  | 42    | 2103  |
| 7:45 AM                | to 8:45 AM | 448        | 249  | 137   | 113        | 234  | 207   | 26        | 302  | 118   | 62        | 152  | 35    | 2083  |
| 8:00 AM                | to 9:00 AM | 429        | 209  | 128   | 107        | 195  | 248   | 23        | 296  | 112   | 52        | 135  | 29    | 1963  |

TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|  |  |                                  |  |                          |  |
|--|--|----------------------------------|--|--------------------------|--|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY |  | <b>SURVEY DATE:</b> 11/6/2012    |  | <b>DAY:</b> TUESDAY      |  |
| <b>N-S APPROACH:</b> MacARTHUR BOULEVARD |  | <b>SURVEY TIME:</b> 4:00 PM      |  | <b>TO:</b> 6:00 PM       |  |
| <b>E-W APPROACH:</b> ESTUDILLO AVENUE    |  | <b>JURISDICTION:</b> SAN LEANDRO |  | <b>FILE:</b> 3211076-2PM |  |

|   |  |
|---|--|
| <p style="text-align: center;">PEAK HOUR<br/>4:45 PM TO 5:45 PM</p> <p style="text-align: center;">↑<br/>NORTH</p> <p style="text-align: center;">ESTUDILLO AVENUE</p> <p style="text-align: center;">MacARTHUR BOULEVARD</p> | <p style="text-align: center;">ARRIVAL / DEPARTURE VOLUMES</p> <p style="text-align: center;">PHF = 0.94</p> <p style="text-align: center;">PHF = 0.90</p> <p style="text-align: center;">PHF = 0.95</p> <p style="text-align: center;">PHF = 0.95</p> |
|---|--|


| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM | 41         | 40   | 55    | 27         | 50   | 51    | 11        | 126  | 44    | 7         | 17   | 6     | 475   |
| 4:15 PM                | to 4:30 PM | 79         | 82   | 94    | 66         | 98   | 101   | 18        | 242  | 81    | 11        | 38   | 8     | 918   |
| 4:30 PM                | to 4:45 PM | 132        | 133  | 132   | 101        | 153  | 147   | 28        | 352  | 124   | 23        | 58   | 11    | 1394  |
| 4:45 PM                | to 5:00 PM | 183        | 181  | 187   | 136        | 196  | 200   | 37        | 480  | 204   | 32        | 83   | 17    | 1936  |
| 5:00 PM                | to 5:15 PM | 226        | 228  | 227   | 163        | 245  | 248   | 50        | 617  | 270   | 45        | 107  | 21    | 2447  |
| 5:15 PM                | to 5:30 PM | 284        | 272  | 281   | 198        | 309  | 285   | 57        | 743  | 334   | 52        | 126  | 28    | 2969  |
| 5:30 PM                | to 5:45 PM | 336        | 323  | 332   | 228        | 365  | 320   | 71        | 874  | 383   | 62        | 144  | 34    | 3472  |
| 5:45 PM                | to 6:00 PM | 393        | 371  | 369   | 258        | 398  | 356   | 82        | 971  | 429   | 72        | 155  | 41    | 3895  |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM | 41         | 40   | 55    | 27         | 50   | 51    | 11        | 126  | 44    | 7         | 17   | 6     | 475   |
| 4:15 PM                | to 4:30 PM | 38         | 42   | 39    | 39         | 48   | 50    | 7         | 116  | 37    | 4         | 21   | 2     | 443   |
| 4:30 PM                | to 4:45 PM | 53         | 51   | 38    | 35         | 55   | 46    | 10        | 110  | 43    | 12        | 20   | 3     | 476   |
| 4:45 PM                | to 5:00 PM | 51         | 48   | 55    | 35         | 43   | 53    | 9         | 128  | 80    | 9         | 25   | 6     | 542   |
| 5:00 PM                | to 5:15 PM | 43         | 47   | 40    | 27         | 49   | 48    | 13        | 137  | 66    | 13        | 24   | 4     | 511   |
| 5:15 PM                | to 5:30 PM | 58         | 44   | 54    | 35         | 64   | 37    | 7         | 126  | 64    | 7         | 19   | 7     | 522   |
| 5:30 PM                | to 5:45 PM | 52         | 51   | 51    | 30         | 56   | 35    | 14        | 131  | 49    | 10        | 18   | 6     | 503   |
| 5:45 PM                | to 6:00 PM | 57         | 48   | 37    | 30         | 33   | 36    | 11        | 97   | 46    | 10        | 11   | 7     | 423   |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 5:00 PM | 183        | 181  | 187   | 136        | 196  | 200   | 37        | 480  | 204   | 32        | 83   | 17    | 1936  |
| 4:15 PM                | to 5:15 PM | 185        | 188  | 172   | 136        | 195  | 197   | 39        | 491  | 226   | 38        | 90   | 15    | 1972  |
| 4:30 PM                | to 5:30 PM | 205        | 190  | 187   | 132        | 211  | 184   | 39        | 501  | 253   | 41        | 88   | 20    | 2051  |
| 4:45 PM                | to 5:45 PM | 204        | 190  | 200   | 127        | 212  | 173   | 43        | 522  | 259   | 39        | 86   | 23    | 2078  |
| 5:00 PM                | to 6:00 PM | 210        | 190  | 182   | 122        | 202  | 156   | 45        | 491  | 225   | 40        | 72   | 24    | 1959  |

TEL: (510) 232 - 1271      FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|                                   |                           |                   |
|-----------------------------------|---------------------------|-------------------|
| PROJECT: CHABOT DAM TRAFFIC STUDY | SURVEY DATE: 11/6/2012    | DAY: TUESDAY      |
| N-S APPROACH: BENEDICT DRIVE      | SURVEY TIME: 7:00 AM      | TO 9:00 AM        |
| E-W APPROACH: ESTUDILLO AVENUE    | JURISDICTION: SAN LEANDRO | FILE: 3211076-3AM |



| TIME            | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|-----------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                 |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| SURVEY DATA     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM         | to 7:15 AM | 8          | 4    | 0     | 0          | 1    | 5     | 70        | 17   | 1     | 1         | 33   | 17    | 157   |
| 7:15 AM         | to 7:30 AM | 13         | 9    | 0     | 2          | 1    | 12    | 168       | 28   | 1     | 1         | 72   | 38    | 345   |
| 7:30 AM         | to 7:45 AM | 24         | 15   | 0     | 2          | 1    | 23    | 289       | 44   | 2     | 2         | 119  | 69    | 590   |
| 7:45 AM         | to 8:00 AM | 45         | 31   | 4     | 3          | 1    | 33    | 408       | 59   | 2     | 2         | 157  | 99    | 844   |
| 8:00 AM         | to 8:15 AM | 70         | 39   | 6     | 3          | 1    | 47    | 543       | 85   | 5     | 3         | 200  | 118   | 1120  |
| 8:15 AM         | to 8:30 AM | 81         | 43   | 9     | 4          | 1    | 50    | 635       | 124  | 6     | 4         | 241  | 135   | 1333  |
| 8:30 AM         | to 8:45 AM | 91         | 51   | 9     | 5          | 2    | 56    | 711       | 169  | 8     | 4         | 274  | 143   | 1523  |
| 8:45 AM         | to 9:00 AM | 95         | 53   | 12    | 6          | 2    | 61    | 776       | 208  | 12    | 6         | 301  | 159   | 1691  |
| TOTAL BY PERIOD |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM         | to 7:15 AM | 8          | 4    | 0     | 0          | 1    | 5     | 70        | 17   | 1     | 1         | 33   | 17    | 157   |
| 7:15 AM         | to 7:30 AM | 5          | 5    | 0     | 2          | 0    | 7     | 98        | 11   | 0     | 0         | 39   | 21    | 188   |
| 7:30 AM         | to 7:45 AM | 11         | 6    | 0     | 0          | 0    | 11    | 121       | 16   | 1     | 1         | 47   | 31    | 245   |
| 7:45 AM         | to 8:00 AM | 21         | 16   | 4     | 1          | 0    | 10    | 119       | 15   | 0     | 0         | 38   | 30    | 254   |
| 8:00 AM         | to 8:15 AM | 25         | 8    | 2     | 0          | 0    | 14    | 135       | 26   | 3     | 1         | 43   | 19    | 276   |
| 8:15 AM         | to 8:30 AM | 11         | 4    | 3     | 1          | 0    | 3     | 92        | 39   | 1     | 1         | 41   | 17    | 213   |
| 8:30 AM         | to 8:45 AM | 10         | 8    | 0     | 1          | 1    | 6     | 76        | 45   | 2     | 0         | 33   | 8     | 190   |
| 8:45 AM         | to 9:00 AM | 4          | 2    | 3     | 1          | 0    | 5     | 65        | 39   | 4     | 2         | 27   | 16    | 168   |
| HOURLY TOTALS   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM         | to 8:00 AM | 45         | 31   | 4     | 3          | 1    | 33    | 408       | 59   | 2     | 2         | 157  | 99    | 844   |
| 7:15 AM         | to 8:15 AM | 62         | 35   | 6     | 3          | 0    | 42    | 473       | 68   | 4     | 2         | 167  | 101   | 963   |
| 7:30 AM         | to 8:30 AM | 68         | 34   | 9     | 2          | 0    | 38    | 467       | 96   | 5     | 3         | 169  | 97    | 988   |
| 7:45 AM         | to 8:45 AM | 67         | 36   | 9     | 3          | 1    | 33    | 422       | 125  | 6     | 2         | 155  | 74    | 933   |
| 8:00 AM         | to 9:00 AM | 50         | 22   | 8     | 3          | 1    | 28    | 368       | 149  | 10    | 4         | 144  | 60    | 847   |

TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|  |  |  |                                  |  |  |                          |  |  |
|--|--|--|----------------------------------|--|--|--------------------------|--|--|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY |  |  | <b>SURVEY DATE:</b> 11/6/2012    |  |  | <b>DAY:</b> TUESDAY      |  |  |
| <b>N-S APPROACH:</b> BENEDICT DRIVE      |  |  | <b>SURVEY TIME:</b> 4:00 PM      |  |  | <b>TO:</b> 6:00 PM       |  |  |
| <b>E-W APPROACH:</b> ESTUDILLO AVENUE    |  |  | <b>JURISDICTION:</b> SAN LEANDRO |  |  | <b>FILE:</b> 3211076-3PM |  |  |

|  |      |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
|--|------|-----|---|---|--|--|-----|------|----|-----|--|-----|----|--|---|---|--|--|----|----|---|---|----|-----|---|--|-----|------|-----|-----|--|-----|---|--|----|----|
| <p style="text-align: center;">PEAK HOUR<br/>4:45 PM TO 5:45 PM</p> <p style="text-align: center;">↑<br/>NORTH</p> <div style="text-align: center;"> <table border="1" style="margin: auto;"> <tr><td>15</td><td>2</td><td>6</td></tr> <tr><td colspan="3" style="text-align: center;">↓</td></tr> <tr><td>584</td><td style="border: 1px solid black; padding: 5px;">1087</td><td>51</td></tr> <tr><td>198</td><td></td><td>106</td></tr> <tr><td>66</td><td></td><td>6</td></tr> <tr><td colspan="3" style="text-align: center;">↑</td></tr> <tr><td>28</td><td>17</td><td>8</td></tr> </table> <p>ESTUDILLO AVENUE</p> <p>BENEDICT DRIVE</p> </div> | 15   | 2   | 6 | ↓ |  |  | 584 | 1087 | 51 | 198 |  | 106 | 66 |  | 6 | ↑ |  |  | 28 | 17 | 8 | <p style="text-align: center;">ARRIVAL / DEPARTURE VOLUMES</p> <p style="text-align: center;">PHF = 0.82</p> <div style="text-align: center;"> <table border="1" style="margin: auto;"> <tr><td>23</td><td>652</td></tr> <tr><td colspan="2" style="text-align: center;">↓</td></tr> <tr><td>149</td><td style="border: 1px solid black; padding: 5px;">1087</td><td>163</td></tr> <tr><td>848</td><td></td><td>212</td></tr> <tr><td colspan="2" style="text-align: center;">↑</td></tr> <tr><td>74</td><td>53</td></tr> </table> <p>PHF = 0.83</p> <p>PHF = 0.97</p> <p>PHF = 0.78</p> </div> | 23 | 652 | ↓ |  | 149 | 1087 | 163 | 848 |  | 212 | ↑ |  | 74 | 53 |
| 15   | 2    | 6   |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| ↓  |      |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 584  | 1087 | 51  |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 198  |      | 106 |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 66   |      | 6   |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| ↑  |      |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 28   | 17   | 8   |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 23   | 652  |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| ↓  |      |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 149  | 1087 | 163 |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 848  |      | 212 |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| ↑  |      |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |
| 74   | 53   |     |   |   |  |  |     |      |    |     |  |     |    |  |   |   |  |  |    |    |   |   |    |     |   |  |     |      |     |     |  |     |   |  |    |    |

| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM | 7          | 2    | 5     | 1          | 0    | 2     | 139       | 46   | 14    | 1         | 21   | 8     | 246   |
| 4:15 PM                | to 4:30 PM | 17         | 5    | 5     | 1          | 1    | 3     | 273       | 88   | 32    | 2         | 40   | 11    | 478   |
| 4:30 PM                | to 4:45 PM | 19         | 5    | 6     | 1          | 2    | 7     | 398       | 132  | 49    | 3         | 67   | 21    | 710   |
| 4:45 PM                | to 5:00 PM | 28         | 10   | 8     | 2          | 2    | 13    | 535       | 190  | 72    | 7         | 92   | 41    | 1000  |
| 5:00 PM                | to 5:15 PM | 38         | 15   | 10    | 4          | 2    | 17    | 684       | 237  | 80    | 7         | 119  | 55    | 1268  |
| 5:15 PM                | to 5:30 PM | 42         | 19   | 12    | 6          | 3    | 18    | 831       | 286  | 99    | 7         | 148  | 63    | 1534  |
| 5:30 PM                | to 5:45 PM | 47         | 22   | 14    | 7          | 4    | 22    | 982       | 330  | 115   | 9         | 173  | 72    | 1797  |
| 5:45 PM                | to 6:00 PM | 48         | 25   | 16    | 8          | 4    | 22    | 1105      | 360  | 125   | 9         | 201  | 74    | 1997  |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 4:15 PM | 7          | 2    | 5     | 1          | 0    | 2     | 139       | 46   | 14    | 1         | 21   | 8     | 246   |
| 4:15 PM                | to 4:30 PM | 10         | 3    | 0     | 0          | 1    | 1     | 134       | 42   | 18    | 1         | 19   | 3     | 232   |
| 4:30 PM                | to 4:45 PM | 2          | 0    | 1     | 0          | 1    | 4     | 125       | 44   | 17    | 1         | 27   | 10    | 232   |
| 4:45 PM                | to 5:00 PM | 9          | 5    | 2     | 1          | 0    | 6     | 137       | 58   | 23    | 4         | 25   | 20    | 290   |
| 5:00 PM                | to 5:15 PM | 10         | 5    | 2     | 2          | 0    | 4     | 149       | 47   | 8     | 0         | 27   | 14    | 268   |
| 5:15 PM                | to 5:30 PM | 4          | 4    | 2     | 2          | 1    | 1     | 147       | 49   | 19    | 0         | 29   | 8     | 266   |
| 5:30 PM                | to 5:45 PM | 5          | 3    | 2     | 1          | 1    | 4     | 151       | 44   | 16    | 2         | 25   | 9     | 263   |
| 5:45 PM                | to 6:00 PM | 1          | 3    | 2     | 1          | 0    | 0     | 123       | 30   | 10    | 0         | 28   | 2     | 200   |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM                | to 5:00 PM | 28         | 10   | 8     | 2          | 2    | 13    | 535       | 190  | 72    | 7         | 92   | 41    | 1000  |
| 4:15 PM                | to 5:15 PM | 31         | 13   | 5     | 3          | 2    | 15    | 545       | 191  | 66    | 6         | 98   | 47    | 1022  |
| 4:30 PM                | to 5:30 PM | 25         | 14   | 7     | 5          | 2    | 15    | 558       | 198  | 67    | 5         | 108  | 52    | 1056  |
| 4:45 PM                | to 5:45 PM | 28         | 17   | 8     | 6          | 2    | 15    | 584       | 198  | 66    | 6         | 106  | 51    | 1087  |
| 5:00 PM                | to 6:00 PM | 20         | 15   | 8     | 6          | 2    | 9     | 570       | 170  | 53    | 2         | 109  | 33    | 997   |


TEL: (510) 232 - 1271      FAX: (510) 232 - 1272



# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|                                   |                           |                   |
|-----------------------------------|---------------------------|-------------------|
| PROJECT: CHABOT DAM TRAFFIC STUDY | SURVEY DATE: 11/6/2012    | DAY: TUESDAY      |
| N-S APPROACH: LAKE CHABOT ROAD    | SURVEY TIME: 7:00 AM      | TO 9:00 AM        |
| E-W APPROACH: ESTUDILLO AVENUE    | JURISDICTION: SAN LEANDRO | FILE: 3211076-4AM |



| TIME                   | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|------------------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                        |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| <b>SURVEY DATA</b>     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM | 48         | 0    |       |            |      |       | 7         | 15   |       | 0         | 7    |       | 77    |
| 7:15 AM                | to 7:30 AM | 104        | 0    |       |            |      |       | 12        | 20   |       | 1         | 10   |       | 147   |
| 7:30 AM                | to 7:45 AM | 177        | 1    |       |            |      |       | 13        | 45   |       | 2         | 18   |       | 256   |
| 7:45 AM                | to 8:00 AM | 258        | 1    |       |            |      |       | 20        | 80   |       | 2         | 27   |       | 388   |
| 8:00 AM                | to 8:15 AM | 322        | 4    |       |            |      |       | 29        | 100  |       | 2         | 34   |       | 491   |
| 8:15 AM                | to 8:30 AM | 372        | 5    |       |            |      |       | 35        | 122  |       | 4         | 39   |       | 577   |
| 8:30 AM                | to 8:45 AM | 413        | 7    |       |            |      |       | 45        | 145  |       | 5         | 42   |       | 657   |
| 8:45 AM                | to 9:00 AM | 454        | 7    |       |            |      |       | 52        | 171  |       | 6         | 51   |       | 741   |
| <b>TOTAL BY PERIOD</b> |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 7:15 AM | 48         | 0    | 0     | 0          | 0    | 0     | 0         | 7    | 15    | 0         | 7    | 0     | 77    |
| 7:15 AM                | to 7:30 AM | 56         | 0    | 0     | 0          | 0    | 0     | 0         | 5    | 5     | 1         | 3    | 0     | 70    |
| 7:30 AM                | to 7:45 AM | 73         | 0    | 1     | 0          | 0    | 0     | 0         | 1    | 25    | 1         | 8    | 0     | 109   |
| 7:45 AM                | to 8:00 AM | 81         | 0    | 0     | 0          | 0    | 0     | 0         | 7    | 35    | 0         | 9    | 0     | 132   |
| 8:00 AM                | to 8:15 AM | 64         | 0    | 3     | 0          | 0    | 0     | 0         | 9    | 20    | 0         | 7    | 0     | 103   |
| 8:15 AM                | to 8:30 AM | 50         | 0    | 1     | 0          | 0    | 0     | 0         | 6    | 22    | 2         | 5    | 0     | 86    |
| 8:30 AM                | to 8:45 AM | 41         | 0    | 2     | 0          | 0    | 0     | 0         | 10   | 23    | 1         | 3    | 0     | 80    |
| 8:45 AM                | to 9:00 AM | 41         | 0    | 0     | 0          | 0    | 0     | 0         | 7    | 26    | 1         | 9    | 0     | 84    |
| <b>HOURLY TOTALS</b>   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 7:00 AM                | to 8:00 AM | 258        | 0    | 1     | 0          | 0    | 0     | 0         | 20   | 80    | 2         | 27   | 0     | 388   |
| 7:15 AM                | to 8:15 AM | 274        | 0    | 4     | 0          | 0    | 0     | 0         | 22   | 85    | 2         | 27   | 0     | 414   |
| 7:30 AM                | to 8:30 AM | 268        | 0    | 5     | 0          | 0    | 0     | 0         | 23   | 102   | 3         | 29   | 0     | 430   |
| 7:45 AM                | to 8:45 AM | 236        | 0    | 6     | 0          | 0    | 0     | 0         | 32   | 100   | 3         | 24   | 0     | 401   |
| 8:00 AM                | to 9:00 AM | 196        | 0    | 6     | 0          | 0    | 0     | 0         | 32   | 91    | 4         | 24   | 0     | 353   |

TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|  |  |                                  |  |                          |  |
|--|--|----------------------------------|--|--------------------------|--|
| <b>PROJECT:</b> CHABOT DAM TRAFFIC STUDY |  | <b>SURVEY DATE:</b> 11/6/2012    |  | <b>DAY:</b> TUESDAY      |  |
| <b>N-S APPROACH:</b> LAKE CHABOT ROAD    |  | <b>SURVEY TIME:</b> 4:00 PM      |  | <b>TO:</b> 6:00 PM       |  |
| <b>E-W APPROACH:</b> ESTUDILLO AVENUE    |  | <b>JURISDICTION:</b> SAN LEANDRO |  | <b>FILE:</b> 3211076-4PM |  |

|   |     |    |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
|---|-----|----|---|---|-----|---|----|--|----|-----|--|---|-----|---|---|--|---|---|-----|----|-----|----|-----|-----|
| <p style="text-align: center;">PEAK HOUR<br/>4:30 PM TO 5:30 PM</p> <p style="text-align: center;">↑<br/>NORTH</p> <div style="text-align: center;"> <table border="1" style="margin: auto;"> <tr><td>0</td><td>0</td><td>0</td></tr> <tr><td>0</td><td>388</td><td>0</td></tr> <tr><td>41</td><td></td><td>39</td></tr> <tr><td>185</td><td></td><td>4</td></tr> <tr><td>114</td><td>0</td><td>5</td></tr> </table> <p>ESTUDILLO AVENUE</p> <p>LAKE CHABOT ROAD</p> </div> | 0   | 0  | 0 | 0 | 388 | 0 | 41 |  | 39 | 185 |  | 4 | 114 | 0 | 5 | <p style="text-align: center;">ARRIVAL / DEPARTURE VOLUMES</p> <p style="text-align: center;">PHF = #DIV/0!</p> <div style="text-align: center;"> <table border="1" style="margin: auto;"> <tr><td>0</td><td>0</td></tr> <tr><td>153</td><td>43</td></tr> <tr><td>226</td><td>46</td></tr> <tr><td>189</td><td>119</td></tr> </table> <p>PHF = 0.83</p> <p>PHF = 0.90</p> <p>PHF = 0.80</p> </div> | 0 | 0 | 153 | 43 | 226 | 46 | 189 | 119 |
| 0   | 0   | 0  |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 0   | 388 | 0  |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 41  |     | 39 |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 185   |     | 4  |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 114   | 0   | 5  |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 0   | 0   |    |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 153   | 43  |    |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 226   | 46  |    |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |
| 189   | 119 |    |   |   |     |   |    |  |    |     |  |   |     |   |   |  |   |   |     |    |     |    |     |     |


| TIME            | PERIOD     | NORTHBOUND |      |       | SOUTHBOUND |      |       | EASTBOUND |      |       | WESTBOUND |      |       | TOTAL |
|-----------------|------------|------------|------|-------|------------|------|-------|-----------|------|-------|-----------|------|-------|-------|
|                 |            | LEFT       | THRU | RIGHT | LEFT       | THRU | RIGHT | LEFT      | THRU | RIGHT | LEFT      | THRU | RIGHT |       |
| SURVEY DATA     |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM         | to 4:15 PM | 22         |      | 1     |            |      |       | 13        | 37   |       | 0         | 8    |       | 81    |
| 4:15 PM         | to 4:30 PM | 39         |      | 2     |            |      |       | 24        | 81   |       | 1         | 15   |       | 162   |
| 4:30 PM         | to 4:45 PM | 69         |      | 4     |            |      |       | 28        | 125  |       | 3         | 23   |       | 252   |
| 4:45 PM         | to 5:00 PM | 97         |      | 4     |            |      |       | 45        | 168  |       | 4         | 33   |       | 351   |
| 5:00 PM         | to 5:15 PM | 132        |      | 6     |            |      |       | 53        | 223  |       | 5         | 45   |       | 464   |
| 5:15 PM         | to 5:30 PM | 153        |      | 7     |            |      |       | 65        | 266  |       | 5         | 54   |       | 550   |
| 5:30 PM         | to 5:45 PM | 176        |      | 7     |            |      |       | 73        | 301  |       | 6         | 72   |       | 635   |
| 5:45 PM         | to 6:00 PM | 200        |      | 8     |            |      |       | 78        | 333  |       | 6         | 77   |       | 702   |
| TOTAL BY PERIOD |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM         | to 4:15 PM | 22         | 0    | 1     | 0          | 0    | 0     | 0         | 13   | 37    | 0         | 8    | 0     | 81    |
| 4:15 PM         | to 4:30 PM | 17         | 0    | 1     | 0          | 0    | 0     | 0         | 11   | 44    | 1         | 7    | 0     | 81    |
| 4:30 PM         | to 4:45 PM | 30         | 0    | 2     | 0          | 0    | 0     | 0         | 4    | 44    | 2         | 8    | 0     | 90    |
| 4:45 PM         | to 5:00 PM | 28         | 0    | 0     | 0          | 0    | 0     | 0         | 17   | 43    | 1         | 10   | 0     | 99    |
| 5:00 PM         | to 5:15 PM | 35         | 0    | 2     | 0          | 0    | 0     | 0         | 8    | 55    | 1         | 12   | 0     | 113   |
| 5:15 PM         | to 5:30 PM | 21         | 0    | 1     | 0          | 0    | 0     | 0         | 12   | 43    | 0         | 9    | 0     | 86    |
| 5:30 PM         | to 5:45 PM | 23         | 0    | 0     | 0          | 0    | 0     | 0         | 8    | 35    | 1         | 18   | 0     | 85    |
| 5:45 PM         | to 6:00 PM | 24         | 0    | 1     | 0          | 0    | 0     | 0         | 5    | 32    | 0         | 5    | 0     | 67    |
| HOURLY TOTALS   |            |            |      |       |            |      |       |           |      |       |           |      |       |       |
| 4:00 PM         | to 5:00 PM | 97         | 0    | 4     | 0          | 0    | 0     | 0         | 45   | 168   | 4         | 33   | 0     | 351   |
| 4:15 PM         | to 5:15 PM | 110        | 0    | 5     | 0          | 0    | 0     | 0         | 40   | 186   | 5         | 37   | 0     | 383   |
| 4:30 PM         | to 5:30 PM | 114        | 0    | 5     | 0          | 0    | 0     | 0         | 41   | 185   | 4         | 39   | 0     | 388   |
| 4:45 PM         | to 5:45 PM | 107        | 0    | 3     | 0          | 0    | 0     | 0         | 45   | 176   | 3         | 49   | 0     | 383   |
| 5:00 PM         | to 6:00 PM | 103        | 0    | 4     | 0          | 0    | 0     | 0         | 33   | 165   | 2         | 44   | 0     | 351   |

TEL: (510) 232 - 1271      FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|                      |                                  |                      |                    |              |                   |
|----------------------|----------------------------------|----------------------|--------------------|--------------|-------------------|
| <b>PROJECT:</b>      | <b>CHABOT DAM TRAFFIC COUNTS</b> | <b>SURVEY DATE:</b>  | <b>2/28/2013</b>   | <b>DAY:</b>  | <b>THURSDAY</b>   |
| <b>N-S APPROACH:</b> | <b>GRAND AVENUE</b>              | <b>SURVEY TIME:</b>  | <b>4:00 PM</b>     | <b>TO</b>    | <b>6:00 PM</b>    |
| <b>E-W APPROACH:</b> | <b>DOLORES AVENUE</b>            | <b>JURISDICTION:</b> | <b>SAN LEANDRO</b> | <b>FILE:</b> | <b>3302022-PM</b> |



| TIME PERIOD        | NORTHBOUND |    |        |      | SOUTHBOUND |       |        |      | EASTBOUND |       |        |      | WESTBOUND |       |        |      | TOTAL |      |       |
|--------------------|------------|----|--------|------|------------|-------|--------|------|-----------|-------|--------|------|-----------|-------|--------|------|-------|------|-------|
|                    | From       | To | U-TURN | LEFT | THRU       | RIGHT | U-TURN | LEFT | THRU      | RIGHT | U-TURN | LEFT | THRU      | RIGHT | U-TURN | LEFT |       | THRU | RIGHT |
| <b>SURVEY DATA</b> |            |    |        |      |            |       |        |      |           |       |        |      |           |       |        |      |       |      |       |
| 4:00 PM to 4:15 PM |            |    | 2      | 24   |            |       | 121    | 3    | 6         | 8     | 56     | 21   | 24        |       |        |      |       |      | 265   |
| 4:15 PM to 4:30 PM |            |    | 2      | 47   |            |       | 244    | 14   | 15        | 20    | 111    | 50   | 47        |       |        |      |       |      | 550   |
| 4:30 PM to 4:45 PM |            |    | 4      | 62   |            |       | 387    | 19   | 20        | 32    | 178    | 75   | 61        |       |        |      |       |      | 838   |
| 4:45 PM to 5:00 PM |            |    | 6      | 78   |            |       | 522    | 28   | 31        | 46    | 249    | 111  | 75        |       |        |      |       |      | 1146  |
| 5:00 PM to 5:15 PM |            |    | 7      | 88   |            |       | 670    | 34   | 54        | 61    | 314    | 143  | 97        |       |        |      |       |      | 1468  |
| 5:15 PM to 5:30 PM |            |    | 7      | 110  |            |       | 837    | 49   | 61        | 87    | 376    | 165  | 116       |       |        |      |       |      | 1808  |
| 5:30 PM to 5:45 PM |            |    | 7      | 130  |            |       | 982    | 57   | 74        | 111   | 431    | 193  | 134       |       |        |      |       |      | 2119  |
| 5:45 PM to 6:00 PM |            |    | 8      | 149  |            |       | 1123   | 69   | 86        | 131   | 482    | 216  | 149       |       |        |      |       |      | 2413  |

| <b>TOTAL BY PERIOD</b> |        |      |      |       |        |      |      |       |        |      |      |       |        |      |      |       |       |  |  |
|------------------------|--------|------|------|-------|--------|------|------|-------|--------|------|------|-------|--------|------|------|-------|-------|--|--|
| TIME PERIOD            | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | TOTAL |  |  |
| 4:00 PM to 4:15 PM     | 0      | 2    | 24   | 0     | 0      | 0    | 121  | 3     | 0      | 6    | 0    | 8     | 0      | 56   | 21   | 24    | 265   |  |  |
| 4:15 PM to 4:30 PM     | 0      | 0    | 23   | 0     | 0      | 0    | 123  | 11    | 0      | 9    | 0    | 12    | 0      | 55   | 29   | 23    | 285   |  |  |
| 4:30 PM to 4:45 PM     | 0      | 2    | 15   | 0     | 0      | 0    | 143  | 5     | 0      | 5    | 0    | 12    | 0      | 67   | 25   | 14    | 288   |  |  |
| 4:45 PM to 5:00 PM     | 0      | 2    | 16   | 0     | 0      | 0    | 135  | 9     | 0      | 11   | 0    | 14    | 0      | 71   | 36   | 14    | 308   |  |  |
| 5:00 PM to 5:15 PM     | 0      | 1    | 10   | 0     | 0      | 0    | 148  | 6     | 0      | 23   | 0    | 15    | 0      | 65   | 32   | 22    | 322   |  |  |
| 5:15 PM to 5:30 PM     | 0      | 0    | 22   | 0     | 0      | 0    | 167  | 15    | 0      | 7    | 0    | 26    | 0      | 62   | 22   | 19    | 340   |  |  |
| 5:30 PM to 5:45 PM     | 0      | 0    | 20   | 0     | 0      | 0    | 145  | 8     | 0      | 13   | 0    | 24    | 0      | 55   | 28   | 18    | 311   |  |  |
| 5:45 PM to 6:00 PM     | 0      | 1    | 19   | 0     | 0      | 0    | 141  | 12    | 0      | 12   | 0    | 20    | 0      | 51   | 23   | 15    | 294   |  |  |

| <b>HOURLY TOTALS</b> |        |      |      |       |        |      |      |       |        |      |      |       |        |      |      |       |       |  |  |
|----------------------|--------|------|------|-------|--------|------|------|-------|--------|------|------|-------|--------|------|------|-------|-------|--|--|
| TIME PERIOD          | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | U-TURN | LEFT | THRU | RIGHT | TOTAL |  |  |
| 4:00 PM to 5:00 PM   | 0      | 6    | 78   | 0     | 0      | 0    | 522  | 28    | 0      | 31   | 0    | 46    | 0      | 249  | 111  | 75    | 1146  |  |  |
| 4:15 PM to 5:15 PM   | 0      | 5    | 64   | 0     | 0      | 0    | 549  | 31    | 0      | 48   | 0    | 53    | 0      | 258  | 122  | 73    | 1203  |  |  |
| 4:30 PM to 5:30 PM   | 0      | 5    | 63   | 0     | 0      | 0    | 593  | 35    | 0      | 46   | 0    | 67    | 0      | 265  | 115  | 69    | 1258  |  |  |
| 4:45 PM to 5:45 PM   | 0      | 3    | 68   | 0     | 0      | 0    | 595  | 38    | 0      | 54   | 0    | 79    | 0      | 253  | 118  | 73    | 1281  |  |  |
| 5:00 PM to 6:00 PM   | 0      | 2    | 71   | 0     | 0      | 0    | 601  | 41    | 0      | 55   | 0    | 85    | 0      | 233  | 105  | 74    | 1267  |  |  |

| <b>PEAK HOUR SUMMARY</b> |      |      |      |      |      |      |      |      |      |      |      |      |      |      |      |      |         |  |  |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|---------|--|--|
| TIME PERIOD              | NBU  | NBL  | NBT  | NBR  | SBU  | SBL  | SBT  | SBR  | EBU  | EBL  | EBT  | EBR  | WBU  | WBL  | WBT  | WBR  | TOTAL   |  |  |
| 4:45 PM to 5:45 PM       | 0    | 3    | 68   | 0    | 0    | 0    | 595  | 38   | 0    | 54   | 0    | 79   | 0    | 253  | 118  | 73   | 1281    |  |  |
| PHF BY MOVEMENT          | 0.00 | 0.38 | 0.77 | 0.00 | 0.00 | 0.00 | 0.89 | 0.63 | 0.00 | 0.59 | 0.00 | 0.76 | 0.00 | 0.89 | 0.82 | 0.83 | OVERALL |  |  |
| PHF BY APPROACH          | 0.81 |      |      |      | 0.87 |      |      |      | 0.88 |      |      |      | 0.92 |      |      |      | 0.94    |  |  |


TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B.A.Y.M.E.T.R.I.C.S.

## INTERSECTION TURNING MOVEMENT SUMMARY

|                      |                                  |                      |                    |              |                   |
|----------------------|----------------------------------|----------------------|--------------------|--------------|-------------------|
| <b>PROJECT:</b>      | <b>CHABOT DAM TRAFFIC COUNTS</b> | <b>SURVEY DATE:</b>  | <b>2/28/2013</b>   | <b>DAY:</b>  | <b>THURSDAY</b>   |
| <b>N-S APPROACH:</b> | <b>GRAND AVENUE</b>              | <b>SURVEY TIME:</b>  | <b>7:00 AM</b>     | <b>TO</b>    | <b>9:00 AM</b>    |
| <b>E-W APPROACH:</b> | <b>DOLORES AVENUE</b>            | <b>JURISDICTION:</b> | <b>SAN LEANDRO</b> | <b>FILE:</b> | <b>3302022-AM</b> |



| TIME PERIOD        | NORTHBOUND |    |        |      | SOUTHBOUND |       |        |      | EASTBOUND |       |        |      | WESTBOUND |       |        |      | TOTAL |      |       |
|--------------------|------------|----|--------|------|------------|-------|--------|------|-----------|-------|--------|------|-----------|-------|--------|------|-------|------|-------|
|                    | From       | To | U-TURN | LEFT | THRU       | RIGHT | U-TURN | LEFT | THRU      | RIGHT | U-TURN | LEFT | THRU      | RIGHT | U-TURN | LEFT |       | THRU | RIGHT |
| <b>SURVEY DATA</b> |            |    |        |      |            |       |        |      |           |       |        |      |           |       |        |      |       |      |       |
| 7:00 AM to 7:15 AM |            |    | 0      | 10   |            |       | 66     | 0    | 4         | 3     | 20     | 6    | 2         |       |        |      |       |      | 111   |
| 7:15 AM to 7:30 AM |            |    | 0      | 26   |            |       | 147    | 2    | 10        | 7     | 53     | 20   | 7         |       |        |      |       |      | 272   |
| 7:30 AM to 7:45 AM |            |    | 1      | 41   |            |       | 248    | 8    | 19        | 16    | 107    | 40   | 14        |       |        |      |       |      | 494   |
| 7:45 AM to 8:00 AM |            |    | 2      | 75   |            |       | 388    | 10   | 34        | 27    | 189    | 73   | 27        |       |        |      |       |      | 825   |
| 8:00 AM to 8:15 AM |            |    | 2      | 131  |            |       | 551    | 17   | 41        | 34    | 251    | 96   | 46        |       |        |      |       |      | 1169  |
| 8:15 AM to 8:30 AM |            |    | 3      | 156  |            |       | 676    | 30   | 42        | 43    | 286    | 121  | 66        |       |        |      |       |      | 1423  |
| 8:30 AM to 8:45 AM |            |    | 6      | 174  |            |       | 798    | 42   | 46        | 51    | 324    | 150  | 85        |       |        |      |       |      | 1676  |
| 8:45 AM to 9:00 AM |            |    | 6      | 190  |            |       | 874    | 44   | 49        | 59    | 372    | 178  | 102       |       |        |      |       |      | 1874  |

| <b>TOTAL BY PERIOD</b> |   |   |    |   |   |   |     |    |   |    |   |    |   |    |    |    |  |  |     |
|------------------------|---|---|----|---|---|---|-----|----|---|----|---|----|---|----|----|----|--|--|-----|
| 7:00 AM to 7:15 AM     | 0 | 0 | 10 | 0 | 0 | 0 | 66  | 0  | 0 | 4  | 0 | 3  | 0 | 20 | 6  | 2  |  |  | 111 |
| 7:15 AM to 7:30 AM     | 0 | 0 | 16 | 0 | 0 | 0 | 81  | 2  | 0 | 6  | 0 | 4  | 0 | 33 | 14 | 5  |  |  | 161 |
| 7:30 AM to 7:45 AM     | 0 | 1 | 15 | 0 | 0 | 0 | 101 | 6  | 0 | 9  | 0 | 9  | 0 | 54 | 20 | 7  |  |  | 222 |
| 7:45 AM to 8:00 AM     | 0 | 1 | 34 | 0 | 0 | 0 | 140 | 2  | 0 | 15 | 0 | 11 | 0 | 82 | 33 | 13 |  |  | 331 |
| 8:00 AM to 8:15 AM     | 0 | 0 | 56 | 0 | 0 | 0 | 163 | 7  | 0 | 7  | 0 | 7  | 0 | 62 | 23 | 19 |  |  | 344 |
| 8:15 AM to 8:30 AM     | 0 | 1 | 25 | 0 | 0 | 0 | 125 | 13 | 0 | 1  | 0 | 9  | 0 | 35 | 25 | 20 |  |  | 254 |
| 8:30 AM to 8:45 AM     | 0 | 3 | 18 | 0 | 0 | 0 | 122 | 12 | 0 | 4  | 0 | 8  | 0 | 38 | 29 | 19 |  |  | 253 |
| 8:45 AM to 9:00 AM     | 0 | 0 | 16 | 0 | 0 | 0 | 76  | 2  | 0 | 3  | 0 | 8  | 0 | 48 | 28 | 17 |  |  | 198 |

| <b>HOURLY TOTALS</b> |   |   |     |   |   |   |     |    |   |    |   |    |   |     |     |    |  |  |      |
|----------------------|---|---|-----|---|---|---|-----|----|---|----|---|----|---|-----|-----|----|--|--|------|
| 7:00 AM to 8:00 AM   | 0 | 2 | 75  | 0 | 0 | 0 | 388 | 10 | 0 | 34 | 0 | 27 | 0 | 189 | 73  | 27 |  |  | 825  |
| 7:15 AM to 8:15 AM   | 0 | 2 | 121 | 0 | 0 | 0 | 485 | 17 | 0 | 37 | 0 | 31 | 0 | 231 | 90  | 44 |  |  | 1058 |
| 7:30 AM to 8:30 AM   | 0 | 3 | 130 | 0 | 0 | 0 | 529 | 28 | 0 | 32 | 0 | 36 | 0 | 233 | 101 | 59 |  |  | 1151 |
| 7:45 AM to 8:45 AM   | 0 | 5 | 133 | 0 | 0 | 0 | 550 | 34 | 0 | 27 | 0 | 35 | 0 | 217 | 110 | 71 |  |  | 1182 |
| 8:00 AM to 9:00 AM   | 0 | 4 | 115 | 0 | 0 | 0 | 486 | 34 | 0 | 15 | 0 | 32 | 0 | 183 | 105 | 75 |  |  | 1049 |

| <b>PEAK HOUR SUMMARY</b> |      |      |      |      |      |      |      |      |      |      |      |      |      |      |      |      |  |  |         |
|--------------------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|--|--|---------|
| 7:45 AM to 8:45 AM       | NBU  | NBL  | NBT  | NBR  | SBU  | SBL  | SBT  | SBR  | EBU  | EBL  | EBT  | EBR  | WBU  | WBL  | WBT  | WBR  |  |  | TOTAL   |
| VOLUME                   | 0    | 5    | 133  | 0    | 0    | 0    | 550  | 34   | 0    | 27   | 0    | 35   | 0    | 217  | 110  | 71   |  |  | 1182    |
| PHF BY MOVEMENT          | 0.00 | 0.42 | 0.59 | 0.00 | 0.00 | 0.00 | 0.84 | 0.65 | 0.00 | 0.45 | 0.00 | 0.80 | 0.00 | 0.66 | 0.83 | 0.89 |  |  | OVERALL |
| PHF BY APPROACH          | 0.62 |      |      |      | 0.86 |      |      |      | 0.60 |      |      |      | 0.78 |      |      |      |  |  | 0.86    |

TEL: (510) 232 - 1271

FAX: (510) 232 - 1272

# B A Y M E T R I C S

## CHABOT DAM PROJECT IN SAN LEANDRO

| Date      | 2-Nov-12 Friday   |        |        |        | 3-Nov-12 Saturday |        |        |        | 4-Nov-12 Sunday** |        |        |        | 5-Nov-12 Monday |        |        |        | 6-Nov-12 Tuesday |        |        |        | 7-Nov-12 Wednesday |        |        |        | 8-Nov-12 Thursday |        |        |        |   |
|-----------|---|--------|--------|--------|-------------------|--------|--------|--------|-------------------|--------|--------|--------|-----------------|--------|--------|--------|------------------|--------|--------|--------|--------------------|--------|--------|--------|-------------------|--------|--------|--------|---|
| Location  | 1. Along Marlow Drive between Foothill Boulevard & Middleton Street |        |        |        |                   |        |        |        |                   |        |        |        |                 |        |        |        |                  |        |        |        |                    |        |        |        |                   |        |        |        |   |
| Direction | EB  |        | WB     |        | EB                |        | WB     |        | EB                |        | WB     |        | EB              |        | WB     |        | EB               |        | WB     |        | EB                 |        | WB     |        | EB                |        | WB     |        |   |
| Time      | 15 MIN  | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN          | 60 MIN | 15 MIN | 60 MIN | 15 MIN           | 60 MIN | 15 MIN | 60 MIN | 15 MIN             | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN |   |
| 1200      | 4   | 0      | 0      | 0      | 2                 | 0      | 1      | 0      | 5                 | 0      | 3      | 0      | 2               | 0      | 1      | 0      | 0                | 0      | 0      | 0      | 3                  | 0      | 2      | 0      | 1                 | 0      | 0      | 0      |   |
| 1215      | 2   | 0      | 1      | 0      | 3                 | 0      | 1      | 0      | 11                | 0      | 3      | 0      | 1               | 0      | 0      | 0      | 2                | 0      | 0      | 0      | 3                  | 0      | 1      | 0      | 2                 | 0      | 0      | 0      |   |
| 1230      | 0   | 0      | 1      | 0      | 1                 | 0      | 0      | 0      | 2                 | 0      | 4      | 0      | 0               | 0      | 1      | 0      | 2                | 0      | 0      | 0      | 3                  | 0      | 1      | 0      | 6                 | 0      | 1      | 0      |   |
| 1245      | 0   | 6      | 0      | 2      | 2                 | 8      | 0      | 2      | 9                 | 27     | 2      | 12     | 2               | 5      | 0      | 2      | 0                | 4      | 0      | 0      | 4                  | 13     | 1      | 5      | 5                 | 14     | 0      | 1      |   |
| 100       | 1   | 3      | 0      | 2      | 1                 | 7      | 2      | 3      | 3                 | 25     | 0      | 9      | 2               | 5      | 1      | 2      | 0                | 4      | 0      | 0      | 1                  | 11     | 2      | 5      | 1                 | 14     | 0      | 1      |   |
| 115       | 1   | 2      | 0      | 1      | 1                 | 5      | 0      | 2      | 4                 | 18     | 1      | 7      | 1               | 5      | 0      | 2      | 0                | 2      | 0      | 0      | 1                  | 9      | 2      | 6      | 0                 | 12     | 0      | 1      |   |
| 130       | 0   | 2      | 0      | 0      | 2                 | 6      | 0      | 2      | 1                 | 17     | 1      | 4      | 0               | 5      | 0      | 1      | 0                | 0      | 0      | 0      | 0                  | 6      | 0      | 5      | 0                 | 6      | 0      | 0      |   |
| 145       | 0   | 2      | 0      | 0      | 5                 | 9      | 1      | 3      | 3                 | 11     | 0      | 2      | 0               | 3      | 0      | 1      | 0                | 0      | 0      | 1      | 1                  | 4      | 6      | 0      | 4                 | 2      | 3      | 0      | 0 |
| 200       | 1   | 2      | 0      | 0      | 0                 | 8      | 0      | 1      | 0                 | 8      | 1      | 3      | 1               | 2      | 0      | 0      | 0                | 0      | 0      | 1      | 0                  | 5      | 0      | 2      | 1                 | 3      | 0      | 0      |   |
| 215       | 0   | 1      | 1      | 1      | 0                 | 7      | 0      | 1      | 1                 | 5      | 1      | 3      | 0               | 1      | 1      | 1      | 1                | 0      | 1      | 0      | 4                  | 0      | 0      | 0      | 3                 | 0      | 0      | 0      |   |
| 230       | 1   | 2      | 0      | 1      | 1                 | 6      | 1      | 2      | 2                 | 6      | 0      | 2      | 0               | 1      | 0      | 1      | 0                | 1      | 0      | 1      | 0                  | 4      | 0      | 0      | 0                 | 3      | 1      | 1      |   |
| 245       | 0   | 2      | 0      | 1      | 0                 | 1      | 1      | 2      | 1                 | 4      | 0      | 2      | 3               | 4      | 1      | 2      | 0                | 1      | 0      | 0      | 1                  | 1      | 1      | 1      | 0                 | 1      | 1      | 2      |   |
| 300       | 1   | 2      | 1      | 2      | 5                 | 6      | 1      | 3      | 1                 | 5      | 0      | 1      | 1               | 4      | 1      | 3      | 0                | 1      | 0      | 0      | 1                  | 2      | 1      | 2      | 0                 | 0      | 0      | 2      |   |
| 315       | 1   | 3      | 0      | 1      | 2                 | 8      | 0      | 3      | 1                 | 5      | 0      | 0      | 0               | 4      | 1      | 3      | 1                | 1      | 1      | 0      | 2                  | 0      | 2      | 0      | 0                 | 0      | 0      | 2      |   |
| 330       | 0   | 2      | 2      | 3      | 2                 | 9      | 0      | 2      | 0                 | 3      | 1      | 1      | 0               | 4      | 0      | 3      | 2                | 3      | 0      | 1      | 1                  | 3      | 0      | 2      | 0                 | 0      | 0      | 1      |   |
| 345       | 1   | 3      | 1      | 4      | 2                 | 11     | 0      | 1      | 0                 | 2      | 0      | 1      | 0               | 1      | 0      | 2      | 0                | 3      | 0      | 1      | 0                  | 2      | 0      | 1      | 1                 | 1      | 0      | 0      |   |
| 400       | 0   | 2      | 1      | 4      | 0                 | 6      | 1      | 1      | 0                 | 1      | 0      | 1      | 0               | 0      | 0      | 1      | 0                | 3      | 0      | 1      | 1                  | 2      | 1      | 1      | 0                 | 1      | 0      | 0      |   |
| 415       | 0   | 1      | 0      | 4      | 0                 | 4      | 3      | 4      | 1                 | 1      | 0      | 1      | 0               | 0      | 1      | 1      | 3                | 0      | 0      | 0      | 2                  | 0      | 2      | 0      | 1                 | 0      | 1      | 2      | 2 |
| 430       | 1   | 2      | 1      | 3      | 3                 | 5      | 0      | 4      | 1                 | 2      | 0      | 0      | 0               | 0      | 1      | 2      | 1                | 2      | 0      | 0      | 0                  | 1      | 0      | 1      | 0                 | 1      | 0      | 2      |   |
| 445       | 2   | 3      | 0      | 2      | 1                 | 4      | 0      | 4      | 1                 | 3      | 1      | 1      | 1               | 1      | 0      | 2      | 1                | 3      | 1      | 1      | 1                  | 2      | 0      | 1      | 1                 | 1      | 1      | 3      |   |
| 500       | 1   | 4      | 1      | 2      | 0                 | 4      | 0      | 3      | 1                 | 4      | 0      | 1      | 0               | 1      | 0      | 2      | 0                | 3      | 0      | 1      | 1                  | 2      | 3      | 3      | 1                 | 2      | 0      | 3      |   |
| 515       | 0   | 4      | 1      | 3      | 0                 | 4      | 0      | 0      | 1                 | 4      | 0      | 1      | 0               | 1      | 0      | 1      | 0                | 2      | 1      | 2      | 2                  | 4      | 0      | 3      | 1                 | 3      | 2      | 3      |   |
| 530       | 3   | 6      | 1      | 3      | 2                 | 3      | 1      | 1      | 4                 | 7      | 1      | 2      | 1               | 2      | 3      | 3      | 2                | 3      | 0      | 2      | 1                  | 5      | 1      | 4      | 1                 | 4      | 3      | 6      |   |
| 545       | 1   | 5      | 2      | 5      | 1                 | 3      | 0      | 1      | 0                 | 6      | 0      | 1      | 2               | 3      | 1      | 4      | 2                | 4      | 1      | 2      | 1                  | 5      | 0      | 4      | 1                 | 4      | 2      | 7      |   |
| 600       | 6   | 10     | 1      | 5      | 1                 | 4      | 2      | 3      | 2                 | 7      | 0      | 1      | 3               | 6      | 1      | 5      | 10               | 14     | 2      | 4      | 5                  | 9      | 0      | 1      | 8                 | 11     | 1      | 8      |   |
| 615       | 2   | 12     | 4      | 8      | 4                 | 8      | 0      | 3      | 0                 | 6      | 2      | 3      | 6               | 12     | 2      | 7      | 9                | 23     | 0      | 3      | 6                  | 13     | 3      | 4      | 9                 | 19     | 3      | 9      |   |
| 630       | 2   | 11     | 3      | 10     | 1                 | 7      | 4      | 6      | 2                 | 4      | 0      | 2      | 2               | 13     | 9      | 13     | 2                | 23     | 5      | 8      | 2                  | 14     | 9      | 12     | 3                 | 21     | 6      | 12     |   |
| 645       | 12  | 22     | 4      | 12     | 1                 | 7      | 4      | 10     | 1                 | 5      | 4      | 6      | 6               | 17     | 6      | 18     | 10               | 31     | 6      | 13     | 11                 | 24     | 8      | 20     | 16                | 36     | 12     | 22     |   |
| 700       | 4   | 20     | 5      | 16     | 4                 | 10     | 2      | 10     | 3                 | 6      | 5      | 11     | 3               | 17     | 10     | 27     | 4                | 25     | 8      | 19     | 2                  | 21     | 5      | 25     | 6                 | 34     | 3      | 24     |   |
| 715       | 12  | 30     | 8      | 20     | 6                 | 12     | 2      | 12     | 2                 | 8      | 4      | 13     | 6               | 17     | 6      | 31     | 14               | 30     | 13     | 32     | 11                 | 26     | 12     | 34     | 8                 | 33     | 10     | 31     |   |
| 730       | 7   | 35     | 9      | 26     | 3                 | 14     | 0      | 8      | 1                 | 7      | 11     | 24     | 15              | 30     | 14     | 36     | 8                | 36     | 14     | 41     | 9                  | 33     | 12     | 37     | 15                | 45     | 10     | 35     |   |
| 745       | 17  | 40     | 11     | 33     | 7                 | 20     | 7      | 11     | 2                 | 8      | 3      | 23     | 20              | 44     | 11     | 41     | 11               | 37     | 20     | 55     | 14                 | 36     | 11     | 40     | 18                | 47     | 18     | 41     |   |
| 800       | 11  | 47     | 16     | 44     | 5                 | 21     | 2      | 11     | 9                 | 14     | 0      | 18     | 6               | 47     | 18     | 49     | 12               | 45     | 15     | 62     | 7                  | 41     | 22     | 57     | 14                | 55     | 13     | 51     |   |
| 815       | 15  | 50     | 20     | 56     | 12                | 27     | 5      | 14     | 9                 | 21     | 8      | 22     | 17              | 58     | 14     | 57     | 22               | 53     | 16     | 65     | 24                 | 54     | 20     | 65     | 15                | 62     | 17     | 58     |   |
| 830       | 13  | 56     | 9      | 56     | 7                 | 31     | 11     | 25     | 4                 | 24     | 4      | 15     | 15              | 58     | 15     | 58     | 16               | 61     | 9      | 60     | 13                 | 58     | 5      | 58     | 18                | 65     | 8      | 56     |   |
| 845       | 15  | 54     | 8      | 53     | 8                 | 32     | 6      | 24     | 14                | 36     | 6      | 18     | 20              | 58     | 1      | 48     | 14               | 64     | 12     | 52     | 16                 | 60     | 15     | 62     | 11                | 58     | 10     | 48     |   |
| 900       | 9   | 52     | 8      | 45     | 8                 | 35     | 10     | 32     | 7                 | 34     | 5      | 23     | 18              | 70     | 2      | 32     | 10               | 62     | 13     | 50     | 8                  | 61     | 9      | 49     | 9                 | 53     | 8      | 43     |   |
| 915       | 15  | 52     | 12     | 37     | 12                | 35     | 11     | 38     | 15                | 40     | 6      | 21     | 16              | 69     | 14     | 32     | 10               | 50     | 9      | 43     | 10                 | 47     | 8      | 37     | 11                | 49     | 4      | 30     |   |
| 930       | 12  | 51     | 8      | 36     | 5                 | 33     | 7      | 34     | 8                 | 44     | 3      | 20     | 9               | 63     | 13     | 30     | 7                | 41     | 9      | 43     | 7                  | 41     | 7      | 39     | 6                 | 37     | 9      | 31     |   |
| 945       | 9   | 45     | 11     | 39     | 13                | 38     | 12     | 40     | 15                | 45     | 0      | 14     | 13              | 56     | 9      | 38     | 16               | 43     | 13     | 44     | 14                 | 39     | 5      | 29     | 10                | 36     | 7      | 28     |   |
| 1000      | 11  | 47     | 9      | 40     | 18                | 48     | 9      | 39     | 14                | 52     | 4      | 13     | 8               | 46     | 8      | 44     | 11               | 44     | 12     | 43     | 7                  | 38     | 10     | 30     | 15                | 42     | 5      | 25     |   |
| 1015      | 12  | 44     | 7      | 35     | 12                | 48     | 14     | 42     | 6                 | 43     | 9      | 16     | 19              | 49     | 9      | 39     | 12               | 46     | 5      | 39     | 11                 | 39     | 2      | 24     | 13                | 44     | 2      | 23     |   |
| 1030      | 18  | 50     | 2      | 29     | 13                | 56     | 5      | 40     | 17                | 52     | 5      | 18     | 13              | 53     | 8      | 34     | 11               | 50     | 6      | 36     | 11                 | 43     | 1      | 18     | 11                | 49     | 14     | 28     |   |
| 1045      | 26  | 67     | 13     | 31     | 15                | 58     | 13     | 41     | 14                | 51     | 8      | 26     | 14              | 54     | 2      | 27     | 14               | 48     | 2      | 25     | 17                 | 46     | 7      | 20     | 7                 | 46     | 4      | 25     |   |
| 1100      | 15  | 71     | 14     | 36     | 22                | 62     | 9      | 41     | 17                | 54     | 7      | 29     | 13              | 59     | 5      | 24     | 12               | 49     | 3      | 16     | 13                 | 52     | 4      | 14     | 11                | 42     | 7      | 27     |   |
| 1115      | 22  | 81     | 5      | 34     | 15                | 65     | 19     | 46     | 16                | 64     | 1      | 21     | 14              | 54     | 5      | 20     | 9                | 46     | 5      | 16     | 19                 | 60     | 5      | 17     | 14                | 43     | 9      | 34     |   |

|       |       |     |     |     |       |     |     |     |     |     |     |     |       |     |     |     |       |     |     |     |       |     |     |     |       |     |     |     |
|-------|-------|-----|-----|-----|-------|-----|-----|-----|-----|-----|-----|-----|-------|-----|-----|-----|-------|-----|-----|-----|-------|-----|-----|-----|-------|-----|-----|-----|
| 1130  | 9     | 72  | 15  | 47  | 18    | 70  | 5   | 46  | 10  | 57  | 4   | 20  | 8     | 49  | 8   | 20  | 13    | 48  | 6   | 16  | 7     | 56  | 5   | 21  | 8     | 40  | 11  | 31  |
| 1145  | 18    | 64  | 10  | 44  | 18    | 73  | 8   | 41  | 17  | 60  | 6   | 18  | 17    | 52  | 8   | 26  | 10    | 44  | 4   | 18  | 15    | 54  | 5   | 19  | 8     | 41  | 7   | 34  |
| 1200  | 19    | 68  | 9   | 39  | 30    | 81  | 11  | 43  | 14  | 57  | 11  | 22  | 18    | 57  | 3   | 24  | 20    | 52  | 7   | 22  | 21    | 62  | 6   | 21  | 23    | 53  | 1   | 28  |
| 1215  | 15    | 61  | 6   | 40  | 29    | 95  | 16  | 40  | 18  | 59  | 8   | 29  | 14    | 57  | 14  | 33  | 17    | 60  | 7   | 24  | 21    | 64  | 2   | 18  | 16    | 55  | 15  | 34  |
| 1230  | 18    | 70  | 6   | 31  | 10    | 87  | 10  | 45  | 23  | 72  | 5   | 30  | 12    | 61  | 8   | 33  | 17    | 64  | 8   | 26  | 17    | 74  | 9   | 22  | 19    | 66  | 10  | 33  |
| 1245  | 18    | 70  | 8   | 29  | 22    | 91  | 9   | 46  | 16  | 71  | 11  | 35  | 10    | 54  | 7   | 32  | 16    | 70  | 8   | 30  | 6     | 65  | 2   | 19  | 19    | 77  | 4   | 30  |
| 1300  | 18    | 69  | 7   | 27  | 15    | 76  | 13  | 48  | 20  | 77  | 6   | 30  | 9     | 45  | 4   | 33  | 11    | 61  | 4   | 27  | 11    | 55  | 7   | 20  | 8     | 62  | 7   | 36  |
| 1315  | 8     | 62  | 9   | 30  | 15    | 62  | 10  | 42  | 17  | 76  | 5   | 27  | 17    | 48  | 5   | 24  | 19    | 63  | 13  | 33  | 12    | 46  | 11  | 29  | 21    | 67  | 3   | 24  |
| 1330  | 16    | 60  | 10  | 34  | 28    | 80  | 2   | 34  | 19  | 72  | 3   | 25  | 15    | 51  | 12  | 28  | 10    | 56  | 9   | 34  | 19    | 48  | 10  | 30  | 15    | 63  | 3   | 17  |
| 1345  | 19    | 61  | 8   | 34  | 24    | 82  | 16  | 41  | 15  | 71  | 4   | 18  | 10    | 51  | 6   | 27  | 17    | 57  | 6   | 32  | 5     | 47  | 9   | 37  | 14    | 58  | 9   | 22  |
| 1400  | 19    | 62  | 13  | 40  | 19    | 86  | 15  | 43  | 18  | 69  | 8   | 20  | 19    | 61  | 9   | 32  | 16    | 62  | 8   | 36  | 13    | 49  | 11  | 41  | 18    | 68  | 3   | 18  |
| 1415  | 15    | 69  | 5   | 36  | 26    | 97  | 21  | 54  | 21  | 73  | 6   | 21  | 23    | 67  | 6   | 33  | 18    | 61  | 7   | 30  | 21    | 58  | 7   | 37  | 20    | 67  | 12  | 27  |
| 1430  | 20    | 73  | 8   | 34  | 16    | 85  | 11  | 63  | 27  | 81  | 11  | 29  | 24    | 76  | 7   | 28  | 12    | 63  | 3   | 24  | 10    | 49  | 8   | 35  | 25    | 77  | 0   | 24  |
| 1445  | 19    | 73  | 8   | 34  | 21    | 82  | 10  | 57  | 15  | 81  | 9   | 34  | 16    | 82  | 5   | 27  | 28    | 74  | 0   | 18  | 22    | 66  | 10  | 36  | 19    | 82  | 6   | 21  |
| 1500  | 27    | 81  | 7   | 28  | 17    | 80  | 5   | 47  | 15  | 78  | 11  | 37  | 15    | 78  | 12  | 30  | 15    | 73  | 14  | 24  | 22    | 75  | 8   | 33  | 18    | 82  | 7   | 25  |
| 1515  | 20    | 86  | 9   | 32  | 20    | 74  | 9   | 35  | 24  | 81  | 6   | 37  | 30    | 85  | 10  | 34  | 31    | 86  | 5   | 22  | 23    | 77  | 9   | 35  | 20    | 82  | 9   | 22  |
| 1530  | 20    | 86  | 10  | 34  | 22    | 80  | 7   | 31  | 15  | 69  | 8   | 34  | 21    | 82  | 7   | 34  | 28    | 102 | 8   | 27  | 32    | 99  | 7   | 34  | 17    | 74  | 3   | 25  |
| 1545  | 25    | 92  | 6   | 32  | 15    | 74  | 10  | 31  | 12  | 66  | 10  | 35  | 23    | 89  | 5   | 34  | 24    | 98  | 11  | 38  | 15    | 92  | 3   | 27  | 22    | 77  | 10  | 29  |
| 1600  | 32    | 97  | 8   | 33  | 11    | 68  | 12  | 38  | 20  | 71  | 5   | 29  | 25    | 99  | 5   | 27  | 28    | 111 | 3   | 27  | 29    | 99  | 6   | 25  | 23    | 82  | 8   | 30  |
| 1615  | 19    | 96  | 9   | 33  | 20    | 68  | 9   | 38  | 13  | 60  | 2   | 25  | 18    | 87  | 7   | 24  | 21    | 101 | 11  | 33  | 25    | 101 | 3   | 19  | 46    | 108 | 11  | 32  |
| 1630  | 31    | 107 | 7   | 30  | 27    | 73  | 2   | 33  | 23  | 68  | 6   | 23  | 19    | 85  | 7   | 24  | 28    | 101 | 10  | 35  | 19    | 88  | 9   | 21  | 30    | 121 | 5   | 34  |
| 1645  | 25    | 107 | 8   | 32  | 18    | 76  | 10  | 33  | 21  | 77  | 5   | 18  | 21    | 83  | 6   | 25  | 20    | 97  | 9   | 33  | 23    | 96  | 6   | 24  | 37    | 136 | 12  | 36  |
| 1700  | 21    | 96  | 11  | 35  | 20    | 85  | 12  | 33  | 16  | 73  | 5   | 18  | 22    | 80  | 2   | 22  | 20    | 89  | 11  | 41  | 23    | 90  | 8   | 26  | 35    | 148 | 11  | 39  |
| 1715  | 37    | 114 | 10  | 36  | 30    | 95  | 12  | 36  | 19  | 79  | 4   | 20  | 33    | 95  | 2   | 17  | 28    | 96  | 9   | 39  | 20    | 85  | 10  | 33  | 37    | 139 | 13  | 41  |
| 1730  | 28    | 111 | 6   | 35  | 18    | 86  | 9   | 43  | 33  | 89  | 6   | 20  | 23    | 99  | 6   | 16  | 23    | 91  | 13  | 42  | 23    | 89  | 10  | 34  | 32    | 141 | 6   | 42  |
| 1745  | 22    | 108 | 8   | 35  | 20    | 88  | 7   | 40  | 23  | 91  | 10  | 25  | 36    | 114 | 1   | 11  | 29    | 100 | 5   | 38  | 33    | 99  | 3   | 31  | 26    | 130 | 6   | 36  |
| 1800  | 30    | 117 | 11  | 35  | 14    | 82  | 7   | 35  | 14  | 89  | 3   | 23  | 37    | 129 | 11  | 20  | 30    | 110 | 9   | 36  | 42    | 118 | 14  | 37  | 31    | 126 | 10  | 35  |
| 1815  | 36    | 116 | 8   | 33  | 14    | 66  | 10  | 33  | 24  | 94  | 3   | 22  | 28    | 124 | 12  | 30  | 41    | 123 | 5   | 32  | 33    | 131 | 11  | 38  | 24    | 113 | 16  | 38  |
| 1830  | 27    | 115 | 7   | 34  | 25    | 73  | 7   | 31  | 14  | 75  | 9   | 25  | 23    | 124 | 10  | 34  | 28    | 128 | 8   | 27  | 26    | 134 | 7   | 35  | 33    | 114 | 8   | 40  |
| 1845  | 23    | 116 | 9   | 35  | 23    | 76  | 1   | 25  | 18  | 70  | 7   | 22  | 27    | 115 | 12  | 45  | 19    | 118 | 6   | 28  | 31    | 132 | 0   | 32  | 22    | 110 | 6   | 40  |
| 1900  | 13    | 99  | 11  | 35  | 19    | 81  | 1   | 19  | 24  | 80  | 3   | 22  | 24    | 102 | 9   | 43  | 16    | 104 | 11  | 30  | 27    | 117 | 7   | 25  | 13    | 92  | 3   | 33  |
| 1915  | 23    | 86  | 4   | 31  | 14    | 81  | 0   | 9   | 16  | 72  | 1   | 20  | 32    | 106 | 12  | 43  | 30    | 93  | 8   | 33  | 13    | 97  | 9   | 23  | 20    | 88  | 6   | 23  |
| 1930  | 11    | 70  | 7   | 31  | 17    | 73  | 3   | 5   | 8   | 66  | 1   | 12  | 15    | 98  | 5   | 38  | 28    | 93  | 1   | 26  | 28    | 99  | 8   | 24  | 9     | 64  | 5   | 20  |
| 1945  | 20    | 67  | 5   | 27  | 18    | 68  | 7   | 11  | 11  | 59  | 3   | 8   | 17    | 88  | 5   | 31  | 17    | 91  | 6   | 26  | 16    | 84  | 11  | 35  | 17    | 59  | 1   | 15  |
| 2000  | 20    | 74  | 3   | 19  | 11    | 60  | 2   | 12  | 12  | 47  | 4   | 9   | 14    | 78  | 2   | 24  | 19    | 94  | 3   | 18  | 21    | 78  | 5   | 33  | 14    | 60  | 4   | 16  |
| 2015  | 11    | 62  | 6   | 21  | 10    | 56  | 7   | 19  | 14  | 45  | 2   | 10  | 19    | 65  | 3   | 15  | 11    | 75  | 1   | 11  | 19    | 84  | 1   | 25  | 10    | 50  | 1   | 11  |
| 2030  | 7     | 58  | 2   | 16  | 9     | 48  | 2   | 18  | 11  | 48  | 5   | 14  | 11    | 61  | 2   | 12  | 12    | 59  | 2   | 12  | 19    | 75  | 3   | 20  | 19    | 60  | 1   | 7   |
| 2045  | 16    | 54  | 9   | 20  | 14    | 44  | 2   | 13  | 8   | 45  | 4   | 15  | 10    | 54  | 1   | 8   | 9     | 51  | 2   | 8   | 18    | 77  | 5   | 14  | 10    | 53  | 10  | 16  |
| 2100  | 8     | 42  | 7   | 24  | 11    | 44  | 2   | 13  | 9   | 42  | 1   | 12  | 13    | 53  | 8   | 14  | 11    | 43  | 3   | 8   | 12    | 68  | 4   | 13  | 6     | 45  | 7   | 19  |
| 2115  | 13    | 44  | 0   | 18  | 20    | 54  | 4   | 10  | 8   | 36  | 2   | 12  | 16    | 50  | 4   | 15  | 16    | 48  | 1   | 8   | 21    | 70  | 3   | 15  | 4     | 39  | 0   | 18  |
| 2130  | 12    | 49  | 15  | 31  | 7     | 52  | 1   | 9   | 5   | 30  | 0   | 7   | 13    | 52  | 1   | 14  | 24    | 60  | 2   | 8   | 16    | 67  | 2   | 14  | 7     | 27  | 1   | 18  |
| 2145  | 11    | 44  | 11  | 33  | 9     | 47  | 1   | 8   | 2   | 24  | 2   | 5   | 7     | 49  | 2   | 15  | 10    | 61  | 11  | 17  | 6     | 55  | 4   | 13  | 5     | 22  | 2   | 10  |
| 2200  | 16    | 52  | 0   | 26  | 14    | 50  | 1   | 7   | 7   | 22  | 0   | 4   | 6     | 42  | 0   | 7   | 7     | 57  | 10  | 24  | 10    | 53  | 4   | 13  | 1     | 17  | 1   | 4   |
| 2215  | 16    | 55  | 4   | 30  | 13    | 43  | 5   | 8   | 9   | 23  | 4   | 6   | 5     | 31  | 0   | 3   | 7     | 48  | 1   | 24  | 7     | 39  | 3   | 13  | 5     | 18  | 0   | 4   |
| 2230  | 8     | 51  | 4   | 19  | 12    | 48  | 0   | 7   | 2   | 20  | 2   | 8   | 2     | 20  | 0   | 2   | 4     | 28  | 1   | 23  | 8     | 31  | 1   | 12  | 6     | 17  | 1   | 4   |
| 2245  | 5     | 45  | 2   | 10  | 11    | 50  | 5   | 11  | 5   | 23  | 1   | 7   | 4     | 17  | 1   | 1   | 6     | 24  | 1   | 13  | 5     | 30  | 2   | 10  | 7     | 19  | 1   | 3   |
| 2300  | 8     | 37  | 0   | 10  | 3     | 39  | 2   | 12  | 4   | 20  | 5   | 12  | 4     | 15  | 1   | 2   | 5     | 22  | 0   | 3   | 5     | 25  | 0   | 6   | 4     | 22  | 0   | 2   |
| 2315  | 8     | 29  | 1   | 7   | 5     | 31  | 2   | 9   | 1   | 12  | 0   | 8   | 3     | 13  | 1   | 3   | 2     | 17  | 1   | 3   | 4     | 22  | 0   | 3   | 6     | 23  | 1   | 3   |
| 2330  | 11    | 32  | 4   | 7   | 11    | 30  | 0   | 9   | 0   | 10  | 0   | 6   | 6     | 17  | 0   | 3   | 11    | 24  | 1   | 3   | 1     | 15  | 1   | 3   | 4     | 21  | 0   | 2   |
| 2345  | 7     | 34  | 1   | 6   | 4     | 23  | 1   | 5   | 4   | 9   | 1   | 6   | 1     | 14  | 0   | 2   | 5     | 23  | 1   | 3   | 0     | 10  | 2   | 3   | 4     | 18  | 1   | 2   |
| TOTAL | 1,184 | N/A | 553 | N/A | 1,065 | N/A | 501 | N/A | 945 | N/A | 352 | N/A | 1,108 | N/A | 469 | N/A | 1,146 | N/A | 496 | N/A | 1,141 | N/A | 487 | N/A | 1,129 | N/A | 471 | N/A |
| AM    | 56    |     | 56  |     | 38    |     | 40  |     | 45  |     | 24  |     | 70    |     | 58  |     | 64    |     | 65  |     | 61    |     | 65  |     | 65    |     | 58  |     |
| NOON  | 81    |     | 47  |     | 97    |     | 63  |     | 81  |     | 35  |     | 82    |     | 44  |     | 74    |     | 43  |     | 74    |     | 41  |     | 82    |     | 36  |     |
| PM    | 117   |     | 36  |     | 95    |     | 47  |     | 94  |     | 37  |     | 129   |     | 45  |     | 128   |     | 42  |     | 134   |     | 38  |     | 148   |     | 42  |     |
| EVEN  | 74    |     | 33  |     | 60    |     | 19  |     | 48  |     | 15  |     | 78    |     | 24  |     | 94    |     | 24  |     | 84    |     | 33  |     | 60    |     | 19  |     |

Telephone: (510) 232-1271

Fax: (510) 232-1272

# B A Y M E T R I C S

## CHABOT DAM PROJECT IN SAN LEANDRO

| Date      | 2-Nov-12 Friday   |        |        |        | 3-Nov-12 Saturday |        |        |        | 4-Nov-12 Sunday** |        |        |        | 5-Nov-12 Monday |        |        |        | 6-Nov-12 Tuesday |        |        |        | 7-Nov-12 Wednesday |        |        |        | 8-Nov-12 Thursday |        |        |        |
|-----------|---|--------|--------|--------|-------------------|--------|--------|--------|-------------------|--------|--------|--------|-----------------|--------|--------|--------|------------------|--------|--------|--------|--------------------|--------|--------|--------|-------------------|--------|--------|--------|
| Location  | 2. Along Estudillo Avenue between Sylvan Circle & Lake Chabot Park entrance |        |        |        |                   |        |        |        |                   |        |        |        |                 |        |        |        |                  |        |        |        |                    |        |        |        |                   |        |        |        |
| Direction | NB  |        | SB     |        | NB                |        | SB     |        | NB                |        | SB     |        | NB              |        | SB     |        | NB               |        | SB     |        | NB                 |        | SB     |        | NB                |        | SB     |        |
| Time      | 15 MIN  | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN          | 60 MIN | 15 MIN | 60 MIN | 15 MIN           | 60 MIN | 15 MIN | 60 MIN | 15 MIN             | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN |
| 1200      | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 1215      | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 1230      | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 1245      | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 100       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 115       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 130       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 145       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 200       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 215       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 230       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 245       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 300       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 315       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 330       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 345       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 400       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 415       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 430       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 445       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 500       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 515       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 530       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 0                 | 2      | 2      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 545       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 1      | 1                 | 2      | 4      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 600       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 1                 | 0      | 4      | 0      | 0               | 0      | 0      | 0      | 8                | 8      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 615       | 0   | 0      | 0      | 0      | 0                 | 0      | 1      | 1      | 0                 | 1      | 0      | 4      | 0               | 0      | 0      | 0      | 0                | 8      | 0      | 0      | 0                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 630       | 0   | 0      | 0      | 0      | 0                 | 0      | 0      | 1      | 0                 | 1      | 1      | 3      | 0               | 0      | 0      | 0      | 8                | 0      | 0      | 1      | 1                  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      |
| 645       | 0   | 0      | 0      | 0      | 2                 | 2      | 4      | 5      | 0                 | 0      | 0      | 1      | 0               | 0      | 5      | 5      | 0                | 0      | 2      | 10     | 0                  | 0      | 1      | 2      | 0                 | 0      | 0      | 0      |
| 700       | 0   | 0      | 1      | 1      | 2                 | 4      | 5      | 10     | 0                 | 0      | 2      | 3      | 0               | 0      | 3      | 8      | 1                | 1      | 5      | 7      | 0                  | 0      | 0      | 2      | 0                 | 0      | 2      | 2      |
| 715       | 1   | 1      | 5      | 6      | 1                 | 5      | 4      | 13     | 0                 | 0      | 6      | 9      | 0               | 0      | 4      | 12     | 0                | 1      | 1      | 8      | 0                  | 0      | 4      | 6      | 1                 | 1      | 1      | 3      |
| 730       | 0   | 1      | 1      | 7      | 0                 | 5      | 3      | 16     | 1                 | 1      | 2      | 10     | 1               | 1      | 2      | 14     | 1                | 2      | 3      | 11     | 4                  | 4      | 2      | 7      | 1                 | 2      | 2      | 5      |
| 745       | 2   | 3      | 7      | 14     | 3                 | 6      | 10     | 22     | 0                 | 1      | 9      | 19     | 3               | 4      | 3      | 12     | 2                | 4      | 5      | 14     | 0                  | 4      | 5      | 11     | 0                 | 2      | 5      | 10     |
| 800       | 0   | 3      | 4      | 17     | 1                 | 5      | 6      | 23     | 5                 | 6      | 3      | 20     | 2               | 6      | 8      | 17     | 3                | 6      | 6      | 15     | 1                  | 5      | 4      | 15     | 2                 | 4      | 7      | 15     |
| 815       | 3   | 5      | 5      | 17     | 3                 | 7      | 5      | 24     | 3                 | 9      | 5      | 19     | 3               | 9      | 7      | 20     | 1                | 7      | 9      | 23     | 1                  | 6      | 7      | 18     | 2                 | 5      | 6      | 20     |
| 830       | 2   | 7      | 9      | 25     | 1                 | 8      | 7      | 28     | 5                 | 13     | 7      | 24     | 0               | 8      | 3      | 21     | 2                | 8      | 7      | 27     | 1                  | 3      | 6      | 22     | 1                 | 5      | 1      | 19     |
| 845       | 1   | 6      | 7      | 25     | 5                 | 10     | 4      | 22     | 4                 | 17     | 6      | 21     | 3               | 8      | 4      | 22     | 1                | 7      | 4      | 26     | 5                  | 8      | 5      | 22     | 3                 | 8      | 8      | 22     |
| 900       | 3   | 9      | 5      | 26     | 3                 | 12     | 9      | 25     | 3                 | 15     | 14     | 32     | 3               | 9      | 2      | 16     | 5                | 9      | 4      | 24     | 3                  | 10     | 8      | 26     | 2                 | 8      | 4      | 19     |
| 915       | 1   | 7      | 3      | 24     | 2                 | 11     | 12     | 32     | 1                 | 13     | 8      | 35     | 3               | 9      | 7      | 16     | 3                | 11     | 1      | 16     | 4                  | 13     | 5      | 24     | 5                 | 11     | 5      | 18     |
| 930       | 3   | 8      | 3      | 18     | 3                 | 13     | 4      | 29     | 4                 | 12     | 7      | 35     | 5               | 14     | 4      | 17     | 2                | 11     | 2      | 11     | 9                  | 21     | 7      | 25     | 3                 | 13     | 1      | 18     |
| 945       | 3   | 10     | 3      | 14     | 7                 | 15     | 9      | 34     | 5                 | 13     | 5      | 34     | 2               | 13     | 7      | 20     | 0                | 10     | 3      | 10     | 5                  | 21     | 2      | 22     | 5                 | 15     | 3      | 13     |
| 1000      | 4   | 11     | 5      | 14     | 4                 | 16     | 9      | 34     | 8                 | 18     | 6      | 26     | 3               | 13     | 2      | 20     | 5                | 10     | 5      | 11     | 3                  | 21     | 2      | 16     | 4                 | 17     | 5      | 14     |
| 1015      | 4   | 14     | 3      | 14     | 4                 | 18     | 9      | 31     | 1                 | 18     | 8      | 26     | 4               | 14     | 6      | 19     | 6                | 13     | 9      | 19     | 5                  | 22     | 10     | 21     | 6                 | 18     | 0      | 9      |
| 1030      | 3   | 14     | 4      | 15     | 8                 | 23     | 5      | 32     | 1                 | 15     | 9      | 28     | 2               | 11     | 10     | 25     | 4                | 15     | 3      | 20     | 5                  | 18     | 3      | 17     | 4                 | 19     | 8      | 16     |
| 1045      | 2   | 13     | 6      | 18     | 4                 | 20     | 9      | 32     | 2                 | 12     | 5      | 28     | 3               | 12     | 2      | 20     | 6                | 21     | 7      | 24     | 2                  | 15     | 6      | 21     | 2                 | 16     | 4      | 17     |
| 1100      | 2   | 11     | 4      | 17     | 4                 | 20     | 3      | 26     | 6                 | 10     | 4      | 26     | 5               | 14     | 1      | 19     | 2                | 18     | 4      | 23     | 6                  | 18     | 6      | 25     | 3                 | 15     | 5      | 17     |
| 1115      | 6   | 13     | 2      | 16     | 9                 | 25     | 9      | 26     | 5                 | 14     | 7      | 25     | 3               | 13     | 3      | 16     | 4                | 16     | 2      | 16     | 1                  | 14     | 4      | 19     | 6                 | 15     | 4      | 21     |

|       |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |     |
|-------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 1130  | 5   | 15  | 6   | 18  | 0   | 17  | 8   | 29  | 2   | 15  | 12  | 28  | 2   | 13  | 2   | 8   | 2   | 14  | 9   | 22  | 2   | 11  | 7   | 23  | 4   | 15  | 1   | 14  |
| 1145  | 1   | 14  | 8   | 20  | 6   | 19  | 4   | 24  | 4   | 17  | 8   | 31  | 3   | 13  | 7   | 13  | 1   | 9   | 7   | 22  | 6   | 15  | 4   | 21  | 2   | 15  | 4   | 14  |
| 1200  | 3   | 15  | 9   | 25  | 3   | 18  | 6   | 27  | 9   | 20  | 8   | 35  | 2   | 10  | 3   | 15  | 6   | 13  | 8   | 26  | 4   | 13  | 5   | 20  | 1   | 13  | 6   | 15  |
| 1215  | 0   | 9   | 7   | 30  | 3   | 12  | 6   | 24  | 2   | 17  | 10  | 38  | 4   | 11  | 4   | 16  | 3   | 12  | 5   | 29  | 3   | 15  | 2   | 18  | 4   | 11  | 8   | 19  |
| 1230  | 5   | 9   | 4   | 28  | 6   | 18  | 9   | 25  | 3   | 18  | 10  | 36  | 5   | 14  | 5   | 19  | 2   | 12  | 6   | 26  | 2   | 15  | 3   | 14  | 3   | 10  | 6   | 24  |
| 1245  | 2   | 10  | 2   | 22  | 5   | 17  | 8   | 29  | 2   | 16  | 5   | 33  | 3   | 14  | 3   | 15  | 13  | 24  | 4   | 23  | 0   | 9   | 4   | 14  | 4   | 12  | 4   | 24  |
| 1300  | 3   | 10  | 4   | 17  | 6   | 20  | 6   | 29  | 7   | 14  | 8   | 33  | 2   | 14  | 7   | 19  | 1   | 19  | 7   | 22  | 2   | 7   | 8   | 17  | 5   | 16  | 6   | 24  |
| 1315  | 4   | 14  | 4   | 14  | 4   | 21  | 6   | 29  | 3   | 15  | 4   | 27  | 0   | 10  | 6   | 21  | 3   | 19  | 9   | 26  | 3   | 7   | 2   | 17  | 4   | 16  | 6   | 22  |
| 1330  | 7   | 16  | 10  | 20  | 1   | 16  | 9   | 29  | 10  | 22  | 10  | 27  | 1   | 6   | 3   | 19  | 2   | 19  | 3   | 23  | 4   | 9   | 3   | 17  | 2   | 15  | 2   | 18  |
| 1345  | 2   | 16  | 8   | 26  | 0   | 11  | 8   | 29  | 2   | 22  | 4   | 26  | 3   | 6   | 5   | 21  | 4   | 10  | 0   | 19  | 3   | 12  | 1   | 14  | 3   | 14  | 5   | 19  |
| 1400  | 12  | 25  | 7   | 29  | 5   | 10  | 10  | 33  | 6   | 21  | 8   | 26  | 2   | 6   | 3   | 17  | 2   | 11  | 0   | 12  | 4   | 14  | 3   | 9   | 1   | 10  | 1   | 14  |
| 1415  | 2   | 23  | 4   | 29  | 3   | 9   | 15  | 42  | 8   | 26  | 14  | 36  | 1   | 7   | 2   | 13  | 3   | 11  | 3   | 6   | 1   | 12  | 3   | 10  | 1   | 7   | 4   | 12  |
| 1430  | 3   | 19  | 6   | 25  | 4   | 12  | 7   | 40  | 1   | 17  | 14  | 40  | 1   | 7   | 8   | 18  | 2   | 11  | 6   | 9   | 0   | 8   | 3   | 10  | 4   | 9   | 9   | 19  |
| 1445  | 4   | 21  | 8   | 25  | 5   | 17  | 7   | 39  | 0   | 15  | 6   | 42  | 1   | 5   | 5   | 18  | 0   | 7   | 3   | 12  | 2   | 7   | 9   | 18  | 5   | 11  | 7   | 21  |
| 1500  | 2   | 11  | 5   | 23  | 3   | 15  | 6   | 35  | 8   | 17  | 7   | 41  | 6   | 9   | 5   | 20  | 4   | 9   | 6   | 18  | 1   | 4   | 5   | 20  | 1   | 11  | 12  | 32  |
| 1515  | 4   | 13  | 8   | 27  | 11  | 23  | 9   | 29  | 5   | 14  | 4   | 31  | 4   | 12  | 3   | 21  | 4   | 10  | 4   | 19  | 5   | 8   | 10  | 27  | 10  | 20  | 7   | 35  |
| 1530  | 1   | 11  | 4   | 25  | 5   | 24  | 9   | 31  | 2   | 15  | 8   | 25  | 1   | 12  | 4   | 17  | 3   | 11  | 8   | 21  | 5   | 13  | 3   | 27  | 4   | 20  | 5   | 31  |
| 1545  | 4   | 11  | 13  | 30  | 6   | 25  | 7   | 31  | 6   | 21  | 9   | 28  | 2   | 13  | 10  | 22  | 5   | 16  | 6   | 24  | 2   | 13  | 5   | 23  | 0   | 15  | 5   | 29  |
| 1600  | 4   | 13  | 4   | 29  | 2   | 24  | 8   | 33  | 7   | 20  | 6   | 27  | 1   | 8   | 7   | 24  | 0   | 12  | 9   | 27  | 3   | 15  | 6   | 24  | 4   | 18  | 8   | 25  |
| 1615  | 4   | 13  | 6   | 27  | 8   | 21  | 9   | 33  | 5   | 20  | 12  | 35  | 6   | 10  | 7   | 28  | 7   | 15  | 6   | 29  | 4   | 14  | 6   | 20  | 6   | 14  | 9   | 27  |
| 1630  | 3   | 15  | 6   | 29  | 6   | 22  | 9   | 33  | 6   | 24  | 7   | 34  | 3   | 12  | 9   | 33  | 8   | 20  | 6   | 27  | 11  | 20  | 5   | 22  | 3   | 13  | 2   | 24  |
| 1645  | 4   | 15  | 6   | 22  | 3   | 19  | 4   | 30  | 2   | 20  | 2   | 27  | 6   | 16  | 5   | 28  | 1   | 16  | 11  | 32  | 0   | 18  | 2   | 19  | 3   | 16  | 5   | 24  |
| 1700  | 3   | 14  | 4   | 22  | 4   | 21  | 6   | 28  | 12  | 25  | 6   | 27  | 9   | 24  | 4   | 25  | 7   | 23  | 2   | 25  | 4   | 19  | 0   | 13  | 2   | 14  | 5   | 21  |
| 1715  | 0   | 10  | 5   | 21  | 4   | 17  | 4   | 23  | 5   | 25  | 7   | 22  | 3   | 21  | 5   | 23  | 9   | 25  | 5   | 24  | 0   | 15  | 1   | 8   | 2   | 10  | 1   | 13  |
| 1730  | 5   | 12  | 6   | 21  | 5   | 16  | 4   | 18  | 7   | 26  | 3   | 18  | 2   | 20  | 4   | 18  | 1   | 18  | 2   | 20  | 2   | 6   | 0   | 3   | 5   | 12  | 3   | 14  |
| 1745  | 12  | 20  | 4   | 19  | 4   | 17  | 2   | 16  | 5   | 29  | 2   | 18  | 0   | 14  | 3   | 16  | 1   | 18  | 0   | 9   | 0   | 6   | 2   | 3   | 2   | 11  | 2   | 11  |
| 1800  | 1   | 18  | 3   | 18  | 8   | 21  | 3   | 13  | 2   | 19  | 3   | 15  | 2   | 7   | 3   | 15  | 1   | 12  | 1   | 8   | 3   | 5   | 4   | 7   | 0   | 9   | 0   | 6   |
| 1815  | 5   | 23  | 0   | 13  | 3   | 20  | 2   | 11  | 0   | 14  | 0   | 8   | 0   | 4   | 0   | 10  | 0   | 3   | 1   | 4   | 0   | 5   | 0   | 6   | 0   | 7   | 0   | 5   |
| 1830  | 1   | 19  | 0   | 7   | 4   | 19  | 0   | 7   | 0   | 7   | 0   | 5   | 0   | 2   | 0   | 6   | 0   | 2   | 0   | 2   | 0   | 3   | 0   | 6   | 0   | 2   | 0   | 2   |
| 1845  | 4   | 11  | 1   | 4   | 5   | 20  | 3   | 8   | 0   | 2   | 0   | 3   | 0   | 2   | 0   | 3   | 0   | 1   | 0   | 2   | 0   | 3   | 0   | 4   | 0   | 0   | 0   | 0   |
| 1900  | 1   | 11  | 2   | 3   | 0   | 12  | 0   | 5   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 1   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 1915  | 0   | 6   | 0   | 3   | 0   | 9   | 0   | 3   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 1930  | 0   | 5   | 0   | 3   | 0   | 5   | 0   | 3   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 1945  | 0   | 1   | 0   | 2   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2000  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2015  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2030  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2045  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2100  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2115  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2130  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2145  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2200  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2215  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2230  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2245  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2300  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2315  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2330  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| 2345  | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   | 0   |
| TOTAL | 151 | N/A | 241 | N/A | 198 | N/A | 321 | N/A | 186 | N/A | 315 | N/A | 120 | N/A | 215 | N/A | 143 | N/A | 227 | N/A | 131 | N/A | 194 | N/A | 135 | N/A | 204 | N/A |
| AM    |     | 10  |     | 26  |     | 15  |     | 34  |     | 17  |     | 35  |     | 14  |     | 22  |     | 11  |     | 27  |     | 21  |     | 26  |     | 15  |     | 22  |
| NOON  |     | 25  |     | 30  |     | 25  |     | 42  |     | 26  |     | 42  |     | 14  |     | 25  |     | 24  |     | 29  |     | 22  |     | 25  |     | 19  |     | 24  |
| PM    |     | 23  |     | 30  |     | 25  |     | 35  |     | 29  |     | 41  |     | 24  |     | 33  |     | 25  |     | 32  |     | 20  |     | 27  |     | 20  |     | 35  |
| EVEN  |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |     | 0   |

Telephone: (510) 232-1271

Fax: (510) 232-1272



# B A Y M E T R I C S

## CHABOT DAM PROJECT IN SAN LEANDRO

| Date      | 2-Nov-12 Friday  |        |        |        | 3-Nov-12 Saturday |        |        |        | 4-Nov-12 Sunday** |        |        |        | 5-Nov-12 Monday |        |        |        | 6-Nov-12 Tuesday |        |        |        | 7-Nov-12 Wednesday |        |        |        | 8-Nov-12 Thursday |        |        |        |
|-----------|--|--------|--------|--------|-------------------|--------|--------|--------|-------------------|--------|--------|--------|-----------------|--------|--------|--------|------------------|--------|--------|--------|--------------------|--------|--------|--------|-------------------|--------|--------|--------|
| Location  | 3. Along Lake Chabot Road between Astor Drive & Fairmont Drive |        |        |        |                   |        |        |        |                   |        |        |        |                 |        |        |        |                  |        |        |        |                    |        |        |        |                   |        |        |        |
| Direction | EB   |        | WB     |        | EB                |        | WB     |        | EB                |        | WB     |        | EB              |        | WB     |        | EB               |        | WB     |        | EB                 |        | WB     |        | EB                |        | WB     |        |
| Time      | 15 MIN   | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN | 15 MIN          | 60 MIN | 15 MIN | 60 MIN | 15 MIN           | 60 MIN | 15 MIN | 60 MIN | 15 MIN             | 60 MIN | 15 MIN | 60 MIN | 15 MIN            | 60 MIN | 15 MIN | 60 MIN |
| 1200      | 2  | 0      | 2      | 0      | 3                 | 0      | 1      | 0      | 3                 | 0      | 5      | 0      | 1               | 0      | 0      | 0      | 2                | 0      | 2      | 0      | 0                  | 0      | 3      | 0      | 1                 | 0      | 1      | 0      |
| 1215      | 2  | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 1                 | 0      | 0      | 0      | 1               | 0      | 2      | 0      | 1                | 0      | 0      | 0      | 2                  | 0      | 1      | 0      | 1                 | 0      | 1      | 0      |
| 1230      | 1  | 0      | 0      | 0      | 2                 | 0      | 0      | 0      | 1                 | 0      | 1      | 0      | 1               | 0      | 1      | 0      | 2                | 0      | 1      | 0      | 1                  | 0      | 2      | 0      | 0                 | 0      | 0      | 0      |
| 1245      | 1  | 6      | 0      | 2      | 3                 | 8      | 1      | 2      | 0                 | 5      | 2      | 8      | 0               | 3      | 2      | 5      | 0                | 5      | 1      | 4      | 0                  | 3      | 0      | 6      | 0                 | 2      | 1      | 3      |
| 100       | 0  | 4      | 0      | 0      | 0                 | 5      | 2      | 3      | 2                 | 4      | 1      | 4      | 0               | 2      | 1      | 6      | 1                | 4      | 0      | 2      | 0                  | 3      | 0      | 3      | 2                 | 3      | 0      | 2      |
| 115       | 2  | 4      | 0      | 0      | 1                 | 6      | 2      | 5      | 4                 | 7      | 1      | 5      | 0               | 1      | 0      | 4      | 1                | 4      | 1      | 3      | 0                  | 1      | 0      | 2      | 1                 | 3      | 0      | 1      |
| 130       | 1  | 4      | 0      | 0      | 0                 | 4      | 1      | 6      | 0                 | 6      | 0      | 4      | 1               | 1      | 0      | 3      | 1                | 3      | 1      | 3      | 0                  | 0      | 0      | 0      | 0                 | 3      | 0      | 1      |
| 145       | 0  | 3      | 0      | 0      | 0                 | 1      | 1      | 6      | 0                 | 6      | 2      | 4      | 4               | 5      | 0      | 1      | 1                | 4      | 0      | 2      | 0                  | 0      | 0      | 0      | 1                 | 4      | 0      | 0      |
| 200       | 2  | 5      | 0      | 0      | 0                 | 1      | 0      | 4      | 0                 | 4      | 0      | 3      | 0               | 5      | 0      | 0      | 0                | 3      | 0      | 2      | 1                  | 1      | 1      | 1      | 0                 | 2      | 1      | 1      |
| 215       | 0  | 3      | 2      | 2      | 0                 | 0      | 3      | 5      | 0                 | 0      | 1      | 3      | 0               | 5      | 2      | 2      | 0                | 2      | 0      | 1      | 0                  | 1      | 0      | 1      | 0                 | 1      | 0      | 1      |
| 230       | 0  | 2      | 1      | 3      | 1                 | 1      | 1      | 5      | 0                 | 0      | 1      | 4      | 0               | 4      | 0      | 2      | 0                | 1      | 0      | 0      | 1                  | 2      | 0      | 1      | 0                 | 1      | 1      | 2      |
| 245       | 0  | 2      | 0      | 3      | 3                 | 4      | 0      | 4      | 0                 | 0      | 0      | 2      | 0               | 0      | 0      | 2      | 0                | 0      | 0      | 0      | 0                  | 2      | 0      | 1      | 0                 | 0      | 0      | 2      |
| 300       | 0  | 0      | 0      | 3      | 0                 | 4      | 1      | 5      | 0                 | 0      | 2      | 4      | 0               | 0      | 0      | 2      | 0                | 0      | 0      | 0      | 1                  | 2      | 0      | 0      | 0                 | 0      | 1      | 2      |
| 315       | 0  | 0      | 0      | 1      | 0                 | 4      | 0      | 2      | 0                 | 0      | 0      | 3      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 2                  | 0      | 0      | 0      | 0                 | 0      | 0      | 2      |
| 330       | 1  | 1      | 0      | 0      | 1                 | 4      | 0      | 1      | 0                 | 0      | 0      | 2      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 1                  | 0      | 0      | 0      | 1                 | 1      | 0      | 1      |
| 345       | 0  | 1      | 0      | 0      | 0                 | 1      | 0      | 1      | 0                 | 0      | 0      | 2      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 1                  | 2      | 0      | 0      | 0                 | 1      | 0      | 1      |
| 400       | 0  | 1      | 0      | 0      | 0                 | 1      | 0      | 0      | 0                 | 0      | 0      | 0      | 0               | 0      | 0      | 0      | 0                | 0      | 0      | 0      | 1                  | 0      | 0      | 0      | 0                 | 1      | 0      | 0      |
| 415       | 0  | 1      | 0      | 0      | 0                 | 1      | 0      | 0      | 0                 | 0      | 0      | 0      | 1               | 1      | 1      | 1      | 0                | 0      | 0      | 0      | 0                  | 1      | 0      | 0      | 1                 | 2      | 1      | 1      |
| 430       | 2  | 2      | 1      | 1      | 0                 | 0      | 0      | 0      | 0                 | 0      | 0      | 0      | 1               | 2      | 0      | 1      | 0                | 1      | 0      | 0      | 0                  | 1      | 0      | 0      | 1                 | 2      | 2      | 3      |
| 445       | 1  | 3      | 2      | 3      | 0                 | 0      | 0      | 0      | 1                 | 1      | 0      | 0      | 0               | 2      | 2      | 3      | 0                | 0      | 3      | 3      | 0                  | 0      | 1      | 1      | 0                 | 2      | 0      | 3      |
| 500       | 1  | 4      | 1      | 4      | 0                 | 0      | 0      | 0      | 0                 | 1      | 1      | 1      | 1               | 3      | 2      | 5      | 1                | 1      | 4      | 7      | 0                  | 0      | 2      | 3      | 3                 | 5      | 2      | 5      |
| 515       | 1  | 5      | 0      | 4      | 0                 | 0      | 2      | 2      | 0                 | 1      | 0      | 1      | 1               | 3      | 2      | 6      | 2                | 3      | 3      | 10     | 4                  | 4      | 3      | 6      | 2                 | 6      | 1      | 5      |
| 530       | 1  | 4      | 4      | 7      | 1                 | 1      | 3      | 5      | 1                 | 2      | 1      | 2      | 0               | 2      | 3      | 9      | 2                | 5      | 2      | 12     | 1                  | 5      | 6      | 12     | 3                 | 8      | 5      | 8      |
| 545       | 2  | 5      | 7      | 12     | 1                 | 2      | 0      | 5      | 1                 | 2      | 2      | 4      | 2               | 4      | 9      | 16     | 0                | 5      | 4      | 13     | 1                  | 6      | 6      | 17     | 3                 | 11     | 3      | 11     |
| 600       | 4  | 8      | 6      | 17     | 2                 | 4      | 5      | 10     | 1                 | 3      | 2      | 5      | 2               | 5      | 10     | 24     | 3                | 7      | 14     | 23     | 3                  | 9      | 8      | 23     | 1                 | 9      | 11     | 20     |
| 615       | 1  | 8      | 8      | 25     | 1                 | 5      | 2      | 10     | 2                 | 5      | 2      | 7      | 3               | 7      | 8      | 30     | 4                | 9      | 10     | 30     | 1                  | 6      | 11     | 31     | 1                 | 8      | 12     | 31     |
| 630       | 4  | 11     | 9      | 30     | 5                 | 9      | 2      | 9      | 3                 | 7      | 4      | 10     | 2               | 9      | 14     | 41     | 9                | 16     | 20     | 48     | 11                 | 16     | 11     | 36     | 10                | 15     | 16     | 42     |
| 645       | 9  | 18     | 13     | 36     | 6                 | 14     | 1      | 10     | 1                 | 7      | 2      | 10     | 6               | 13     | 24     | 56     | 7                | 23     | 15     | 59     | 6                  | 21     | 16     | 46     | 7                 | 19     | 19     | 58     |
| 700       | 3  | 17     | 22     | 52     | 15                | 27     | 4      | 9      | 2                 | 8      | 3      | 11     | 5               | 16     | 21     | 67     | 5                | 25     | 24     | 69     | 10                 | 28     | 29     | 67     | 7                 | 25     | 24     | 71     |
| 715       | 2  | 18     | 17     | 61     | 22                | 48     | 7      | 14     | 5                 | 11     | 8      | 17     | 14              | 27     | 29     | 88     | 17               | 38     | 30     | 89     | 10                 | 37     | 29     | 85     | 15                | 39     | 31     | 90     |
| 730       | 7  | 21     | 41     | 93     | 20                | 63     | 11     | 23     | 9                 | 17     | 7      | 20     | 9               | 34     | 50     | 124    | 12               | 41     | 45     | 114    | 18                 | 44     | 41     | 115    | 12                | 41     | 40     | 114    |
| 745       | 25   | 37     | 47     | 127    | 16                | 73     | 6      | 28     | 7                 | 23     | 6      | 24     | 18              | 46     | 56     | 156    | 24               | 58     | 67     | 166    | 20                 | 58     | 63     | 162    | 20                | 54     | 63     | 158    |
| 800       | 17   | 51     | 51     | 156    | 26                | 84     | 14     | 38     | 7                 | 28     | 11     | 32     | 28              | 69     | 47     | 182    | 31               | 84     | 57     | 199    | 27                 | 75     | 49     | 182    | 20                | 67     | 56     | 190    |
| 815       | 9  | 58     | 64     | 203    | 11                | 73     | 13     | 44     | 16                | 39     | 11     | 35     | 17              | 72     | 60     | 213    | 12               | 79     | 57     | 226    | 12                 | 77     | 62     | 215    | 10                | 62     | 58     | 217    |
| 830       | 20   | 71     | 36     | 198    | 7                 | 60     | 11     | 44     | 15                | 45     | 17     | 45     | 15              | 78     | 43     | 206    | 15               | 82     | 30     | 211    | 12                 | 71     | 34     | 208    | 16                | 66     | 44     | 221    |
| 845       | 12   | 58     | 33     | 184    | 9                 | 53     | 16     | 54     | 15                | 53     | 16     | 55     | 20              | 80     | 34     | 184    | 22               | 80     | 39     | 183    | 20                 | 71     | 44     | 189    | 17                | 63     | 35     | 193    |
| 900       | 15   | 56     | 31     | 164    | 24                | 51     | 26     | 66     | 7                 | 53     | 18     | 62     | 18              | 70     | 33     | 170    | 16               | 65     | 44     | 170    | 12                 | 56     | 33     | 173    | 16                | 59     | 22     | 159    |
| 915       | 15   | 62     | 17     | 117    | 17                | 57     | 19     | 72     | 15                | 52     | 14     | 65     | 15              | 68     | 20     | 130    | 11               | 64     | 25     | 138    | 16                 | 60     | 27     | 138    | 9                 | 58     | 18     | 119    |
| 930       | 11   | 53     | 15     | 96     | 14                | 64     | 18     | 79     | 13                | 50     | 35     | 83     | 17              | 70     | 20     | 107    | 11               | 60     | 20     | 128    | 13                 | 61     | 22     | 126    | 13                | 55     | 12     | 87     |
| 945       | 17   | 58     | 18     | 81     | 16                | 71     | 27     | 90     | 20                | 55     | 16     | 83     | 15              | 65     | 24     | 97     | 14               | 52     | 28     | 117    | 11                 | 52     | 17     | 99     | 12                | 50     | 21     | 73     |
| 1000      | 15   | 58     | 15     | 65     | 21                | 68     | 26     | 90     | 19                | 67     | 12     | 77     | 9               | 56     | 20     | 84     | 15               | 51     | 20     | 93     | 8                  | 48     | 27     | 93     | 14                | 48     | 23     | 74     |
| 1015      | 14   | 57     | 18     | 66     | 13                | 64     | 16     | 87     | 15                | 67     | 26     | 89     | 15              | 56     | 18     | 82     | 13               | 53     | 20     | 88     | 13                 | 45     | 14     | 80     | 9                 | 48     | 18     | 74     |
| 1030      | 11   | 57     | 12     | 63     | 21                | 71     | 31     | 100    | 17                | 71     | 22     | 76     | 20              | 59     | 23     | 85     | 17               | 59     | 30     | 98     | 14                 | 46     | 22     | 80     | 11                | 46     | 16     | 78     |
| 1045      | 13   | 53     | 19     | 64     | 16                | 71     | 18     | 91     | 16                | 67     | 19     | 79     | 12              | 56     | 21     | 82     | 11               | 56     | 20     | 90     | 14                 | 49     | 11     | 74     | 11                | 45     | 12     | 69     |
| 1100      | 14   | 52     | 21     | 70     | 22                | 72     | 23     | 88     | 20                | 68     | 15     | 82     | 15              | 62     | 11     | 73     | 19               | 60     | 14     | 84     | 8                  | 49     | 13     | 60     | 6                 | 37     | 11     | 57     |
| 1115      | 16   | 54     | 13     | 65     | 10                | 69     | 9      | 81     | 17                | 70     | 24     | 80     | 13              | 60     | 15     | 70     | 11               | 58     | 16     | 80     | 19                 | 55     | 16     | 62     | 9                 | 37     | 12     | 51     |

|       |       |     |       |     |     |     |     |     |     |     |     |     |       |     |       |     |       |     |       |     |       |     |       |     |     |     |       |     |
|-------|-------|-----|-------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-------|-----|-------|-----|-------|-----|-------|-----|-------|-----|-------|-----|-----|-----|-------|-----|
| 1130  | 18    | 61  | 14    | 67  | 13  | 61  | 23  | 73  | 26  | 79  | 19  | 77  | 16    | 56  | 11    | 58  | 14    | 55  | 21    | 71  | 9     | 50  | 21    | 61  | 21  | 47  | 16    | 51  |
| 1145  | 19    | 67  | 16    | 64  | 14  | 59  | 21  | 76  | 17  | 80  | 14  | 72  | 12    | 56  | 20    | 57  | 14    | 58  | 16    | 67  | 22    | 58  | 24    | 74  | 14  | 50  | 22    | 61  |
| 1200  | 16    | 69  | 25    | 68  | 22  | 59  | 17  | 70  | 22  | 82  | 19  | 76  | 18    | 59  | 14    | 60  | 19    | 58  | 24    | 77  | 31    | 81  | 21    | 82  | 20  | 64  | 20    | 70  |
| 1215  | 14    | 67  | 20    | 75  | 37  | 86  | 12  | 73  | 17  | 82  | 22  | 74  | 9     | 55  | 22    | 67  | 19    | 66  | 20    | 81  | 18    | 80  | 18    | 84  | 17  | 72  | 10    | 68  |
| 1230  | 17    | 66  | 13    | 74  | 21  | 94  | 16  | 66  | 17  | 73  | 16  | 71  | 18    | 57  | 15    | 71  | 17    | 69  | 16    | 76  | 20    | 91  | 27    | 90  | 11  | 62  | 12    | 64  |
| 1245  | 18    | 65  | 14    | 72  | 20  | 100 | 24  | 69  | 20  | 76  | 22  | 79  | 11    | 56  | 12    | 63  | 20    | 75  | 22    | 82  | 14    | 83  | 30    | 96  | 25  | 73  | 24    | 66  |
| 1300  | 19    | 68  | 14    | 61  | 25  | 103 | 24  | 76  | 20  | 74  | 27  | 87  | 13    | 51  | 19    | 68  | 14    | 70  | 19    | 77  | 23    | 75  | 24    | 99  | 15  | 68  | 13    | 59  |
| 1315  | 16    | 70  | 19    | 60  | 23  | 89  | 12  | 76  | 18  | 75  | 21  | 86  | 18    | 60  | 10    | 56  | 16    | 67  | 18    | 75  | 10    | 67  | 15    | 96  | 15  | 66  | 8     | 57  |
| 1330  | 26    | 79  | 19    | 66  | 22  | 90  | 19  | 79  | 28  | 86  | 27  | 97  | 11    | 53  | 22    | 63  | 22    | 72  | 16    | 75  | 21    | 68  | 18    | 87  | 19  | 74  | 20    | 65  |
| 1345  | 18    | 79  | 15    | 67  | 18  | 88  | 28  | 83  | 22  | 88  | 24  | 99  | 19    | 61  | 16    | 67  | 22    | 74  | 18    | 71  | 28    | 82  | 20    | 77  | 14  | 63  | 20    | 61  |
| 1400  | 12    | 72  | 17    | 70  | 15  | 78  | 23  | 82  | 22  | 90  | 17  | 89  | 20    | 68  | 14    | 62  | 17    | 77  | 19    | 71  | 14    | 73  | 21    | 74  | 11  | 59  | 17    | 65  |
| 1415  | 19    | 75  | 19    | 70  | 16  | 71  | 25  | 95  | 23  | 95  | 20  | 88  | 13    | 63  | 17    | 69  | 17    | 78  | 13    | 66  | 25    | 88  | 13    | 72  | 20  | 64  | 14    | 71  |
| 1430  | 25    | 74  | 16    | 67  | 23  | 72  | 20  | 96  | 18  | 85  | 21  | 82  | 15    | 67  | 13    | 60  | 22    | 78  | 23    | 73  | 10    | 77  | 21    | 75  | 11  | 56  | 15    | 66  |
| 1445  | 20    | 76  | 23    | 75  | 19  | 73  | 19  | 87  | 15  | 78  | 30  | 88  | 19    | 67  | 16    | 60  | 31    | 87  | 24    | 79  | 25    | 74  | 18    | 73  | 10  | 52  | 18    | 64  |
| 1500  | 20    | 84  | 20    | 78  | 17  | 75  | 21  | 85  | 16  | 72  | 21  | 92  | 16    | 63  | 20    | 66  | 25    | 95  | 21    | 81  | 25    | 85  | 27    | 79  | 19  | 60  | 19    | 66  |
| 1515  | 30    | 95  | 23    | 82  | 23  | 82  | 18  | 78  | 24  | 73  | 22  | 94  | 13    | 63  | 22    | 71  | 31    | 109 | 15    | 83  | 24    | 84  | 28    | 94  | 21  | 61  | 20    | 72  |
| 1530  | 32    | 102 | 16    | 82  | 18  | 77  | 16  | 74  | 25  | 80  | 10  | 83  | 31    | 79  | 16    | 74  | 29    | 116 | 18    | 78  | 26    | 100 | 22    | 95  | 18  | 68  | 14    | 71  |
| 1545  | 13    | 95  | 28    | 87  | 13  | 71  | 16  | 71  | 17  | 82  | 21  | 74  | 25    | 85  | 23    | 81  | 27    | 112 | 26    | 80  | 26    | 101 | 18    | 95  | 29  | 87  | 22    | 75  |
| 1600  | 27    | 102 | 32    | 99  | 19  | 73  | 16  | 66  | 19  | 85  | 25  | 78  | 37    | 106 | 33    | 94  | 35    | 122 | 24    | 83  | 33    | 109 | 23    | 91  | 27  | 95  | 17    | 73  |
| 1615  | 26    | 98  | 22    | 98  | 20  | 70  | 19  | 67  | 20  | 81  | 24  | 80  | 39    | 132 | 21    | 93  | 25    | 116 | 24    | 92  | 28    | 113 | 23    | 86  | 26  | 100 | 27    | 80  |
| 1630  | 33    | 99  | 30    | 112 | 18  | 70  | 14  | 65  | 12  | 68  | 12  | 82  | 31    | 132 | 24    | 101 | 30    | 117 | 25    | 99  | 45    | 132 | 19    | 83  | 38  | 120 | 25    | 91  |
| 1645  | 31    | 117 | 22    | 106 | 17  | 74  | 18  | 67  | 23  | 74  | 18  | 79  | 32    | 139 | 30    | 108 | 36    | 126 | 21    | 94  | 35    | 141 | 23    | 88  | 35  | 126 | 19    | 88  |
| 1700  | 35    | 125 | 27    | 101 | 17  | 72  | 21  | 72  | 31  | 86  | 14  | 68  | 32    | 134 | 19    | 94  | 37    | 128 | 22    | 92  | 48    | 156 | 19    | 84  | 35  | 134 | 19    | 90  |
| 1715  | 42    | 141 | 25    | 104 | 15  | 67  | 14  | 67  | 12  | 78  | 16  | 60  | 39    | 134 | 23    | 96  | 48    | 151 | 23    | 91  | 32    | 160 | 16    | 77  | 25  | 133 | 29    | 92  |
| 1730  | 40    | 148 | 15    | 89  | 8   | 57  | 17  | 70  | 14  | 80  | 14  | 62  | 27    | 130 | 21    | 93  | 29    | 150 | 14    | 80  | 43    | 158 | 22    | 80  | 32  | 127 | 27    | 94  |
| 1745  | 44    | 161 | 21    | 88  | 20  | 60  | 8   | 60  | 10  | 67  | 15  | 59  | 30    | 128 | 27    | 90  | 36    | 150 | 17    | 76  | 32    | 155 | 20    | 77  | 16  | 108 | 21    | 96  |
| 1800  | 32    | 158 | 18    | 79  | 16  | 59  | 16  | 55  | 11  | 47  | 10  | 55  | 29    | 125 | 20    | 91  | 19    | 132 | 17    | 71  | 25    | 132 | 28    | 86  | 14  | 87  | 22    | 99  |
| 1815  | 23    | 139 | 29    | 83  | 10  | 54  | 18  | 59  | 5   | 40  | 7   | 46  | 26    | 112 | 20    | 88  | 15    | 99  | 16    | 64  | 27    | 127 | 19    | 89  | 20  | 82  | 13    | 83  |
| 1830  | 16    | 115 | 18    | 86  | 20  | 66  | 23  | 65  | 7   | 33  | 13  | 45  | 20    | 105 | 14    | 81  | 20    | 90  | 13    | 63  | 28    | 112 | 12    | 79  | 13  | 63  | 3     | 59  |
| 1845  | 26    | 97  | 17    | 82  | 7   | 53  | 13  | 70  | 8   | 31  | 9   | 39  | 15    | 90  | 13    | 67  | 16    | 70  | 12    | 58  | 23    | 103 | 12    | 71  | 9   | 56  | 16    | 54  |
| 1900  | 28    | 93  | 21    | 85  | 10  | 47  | 15  | 69  | 15  | 35  | 10  | 39  | 14    | 75  | 13    | 60  | 24    | 75  | 10    | 51  | 17    | 95  | 16    | 59  | 15  | 57  | 8     | 40  |
| 1915  | 13    | 83  | 18    | 74  | 3   | 40  | 16  | 67  | 3   | 33  | 10  | 42  | 13    | 62  | 9     | 49  | 13    | 73  | 11    | 46  | 14    | 82  | 15    | 55  | 11  | 48  | 13    | 40  |
| 1930  | 9     | 76  | 8     | 64  | 6   | 26  | 9   | 53  | 5   | 31  | 11  | 40  | 12    | 54  | 6     | 41  | 11    | 64  | 9     | 42  | 17    | 71  | 12    | 55  | 9   | 44  | 2     | 39  |
| 1945  | 14    | 64  | 7     | 54  | 4   | 23  | 8   | 48  | 3   | 26  | 7   | 38  | 10    | 49  | 9     | 37  | 12    | 60  | 7     | 37  | 10    | 58  | 7     | 50  | 7   | 42  | 2     | 25  |
| 2000  | 8     | 44  | 8     | 41  | 13  | 26  | 6   | 39  | 5   | 16  | 7   | 35  | 14    | 49  | 5     | 29  | 13    | 49  | 7     | 34  | 7     | 48  | 6     | 40  | 7   | 34  | 3     | 20  |
| 2015  | 11    | 42  | 11    | 34  | 7   | 30  | 4   | 27  | 5   | 18  | 2   | 27  | 8     | 44  | 7     | 27  | 7     | 43  | 7     | 30  | 13    | 47  | 4     | 29  | 8   | 31  | 5     | 12  |
| 2030  | 6     | 39  | 3     | 29  | 6   | 30  | 4   | 22  | 4   | 17  | 2   | 18  | 11    | 43  | 4     | 25  | 14    | 46  | 6     | 27  | 6     | 36  | 3     | 20  | 7   | 29  | 3     | 13  |
| 2045  | 16    | 41  | 4     | 26  | 4   | 30  | 4   | 18  | 7   | 21  | 4   | 15  | 4     | 37  | 7     | 23  | 5     | 39  | 5     | 25  | 3     | 29  | 3     | 16  | 7   | 29  | 2     | 13  |
| 2100  | 6     | 39  | 3     | 21  | 6   | 23  | 7   | 19  | 5   | 21  | 1   | 9   | 3     | 26  | 2     | 20  | 4     | 30  | 3     | 21  | 10    | 32  | 8     | 18  | 4   | 26  | 4     | 14  |
| 2115  | 8     | 36  | 9     | 19  | 7   | 23  | 5   | 20  | 4   | 20  | 1   | 8   | 9     | 27  | 5     | 18  | 7     | 30  | 9     | 23  | 5     | 24  | 6     | 20  | 3   | 21  | 6     | 15  |
| 2130  | 6     | 36  | 3     | 19  | 1   | 18  | 7   | 23  | 3   | 19  | 5   | 11  | 7     | 23  | 2     | 16  | 3     | 19  | 5     | 22  | 5     | 23  | 8     | 25  | 3   | 17  | 0     | 12  |
| 2145  | 5     | 25  | 5     | 20  | 4   | 18  | 6   | 25  | 3   | 15  | 2   | 9   | 5     | 24  | 0     | 9   | 5     | 19  | 5     | 22  | 5     | 25  | 5     | 27  | 1   | 11  | 2     | 12  |
| 2200  | 6     | 25  | 3     | 20  | 5   | 17  | 4   | 22  | 2   | 12  | 3   | 11  | 7     | 28  | 4     | 11  | 2     | 17  | 5     | 24  | 2     | 17  | 4     | 23  | 2   | 9   | 4     | 12  |
| 2215  | 5     | 22  | 5     | 16  | 6   | 16  | 5   | 22  | 4   | 12  | 4   | 14  | 4     | 23  | 8     | 14  | 3     | 13  | 3     | 18  | 4     | 16  | 4     | 21  | 2   | 8   | 4     | 10  |
| 2230  | 8     | 24  | 0     | 13  | 2   | 17  | 2   | 17  | 0   | 9   | 2   | 11  | 5     | 21  | 2     | 14  | 2     | 12  | 2     | 15  | 7     | 18  | 0     | 13  | 4   | 9   | 1     | 11  |
| 2245  | 12    | 31  | 6     | 14  | 5   | 18  | 1   | 12  | 1   | 7   | 1   | 10  | 3     | 19  | 0     | 14  | 3     | 10  | 3     | 13  | 2     | 15  | 4     | 12  | 2   | 10  | 0     | 9   |
| 2300  | 12    | 37  | 2     | 13  | 4   | 17  | 4   | 12  | 1   | 6   | 3   | 10  | 3     | 15  | 0     | 10  | 2     | 10  | 3     | 11  | 3     | 16  | 0     | 8   | 1   | 9   | 3     | 8   |
| 2315  | 3     | 35  | 2     | 10  | 4   | 15  | 4   | 11  | 1   | 3   | 3   | 9   | 0     | 11  | 4     | 6   | 2     | 9   | 2     | 10  | 1     | 13  | 1     | 5   | 3   | 10  | 5     | 9   |
| 2330  | 3     | 30  | 2     | 12  | 3   | 16  | 0   | 9   | 3   | 6   | 1   | 8   | 1     | 7   | 0     | 4   | 3     | 10  | 1     | 9   | 3     | 9   | 1     | 6   | 2   | 8   | 0     | 8   |
| 2345  | 4     | 22  | 0     | 6   | 1   | 12  | 1   | 9   | 2   | 7   | 1   | 8   | 1     | 5   | 1     | 5   | 2     | 9   | 1     | 7   | 2     | 9   | 2     | 4   | 3   | 9   | 2     | 10  |
| TOTAL | 1,184 | N/A | 1,273 | N/A | 977 | N/A | 986 | N/A | 871 | N/A | 940 | N/A | 1,090 | N/A | 1,283 | N/A | 1,172 | N/A | 1,348 | N/A | 1,197 | N/A | 1,355 | N/A | 967 | N/A | 1,205 | N/A |
| AM    |       | 71  |       | 203 |     | 84  |     | 90  |     | 55  |     | 83  |       | 80  |       | 213 |       | 84  |       | 226 |       | 77  |       | 215 |     | 67  |       | 221 |
| NOON  |       | 79  |       | 75  |     | 103 |     | 100 |     | 95  |     | 99  |       | 68  |       | 85  |       | 87  |       | 98  |       | 91  |       | 99  |     | 74  |       | 78  |
| PM    |       | 161 |       | 112 |     | 82  |     | 85  |     | 86  |     | 94  |       | 139 |       | 108 |       | 151 |       | 99  |       | 160 |       | 95  |     | 134 |       | 99  |
| EVEN  |       | 44  |       | 41  |     | 30  |     | 39  |     | 21  |     | 35  |       | 49  |       | 29  |       | 49  |       | 34  |       | 48  |       | 40  |     | 34  |       | 20  |

Telephone: (510) 232-1271

Fax: (510) 232-1272

## **APPENDIX G**

---

### Air Quality Calculations



**Chabot Dam - Outlet Works (off-road)**  
**Alameda County, Annual**

**1.0 Project Characteristics**

---

**1.1 Land Usage**

**1.2 Other Project Characteristics**

|                     |       |                                  |     |                        |                                |
|---------------------|-------|----------------------------------|-----|------------------------|--------------------------------|
| <b>Urbanization</b> | Rural | <b>Wind Speed (m/s)</b>          | 2.2 | <b>Utility Company</b> | Pacific Gas & Electric Company |
| <b>Climate Zone</b> | 4     | <b>Precipitation Freq (Days)</b> | 63  |                        |                                |

**1.3 User Entered Comments**

- Project Characteristics -
- Land Use -
- Construction Phase - Outlet Works from PD
- Off-road Equipment - project description
- Off-road Equipment - project description
- Trips and VMT - all on-road emissions handled off model with EMFAC2013

**2.0 Emissions Summary**

---

## 2.1 Overall Construction

### Unmitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| 2014         | 0.11        | 0.71        | 0.43        | 0.00        | 0.00          | 0.04         | 0.04        | 0.00           | 0.04          | 0.04        | 0.00        | 83.97        | 83.97        | 0.01        | 0.00        | 84.15        |
| <b>Total</b> | <b>0.11</b> | <b>0.71</b> | <b>0.43</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.04</b>  | <b>0.04</b> | <b>0.00</b>    | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>83.97</b> | <b>83.97</b> | <b>0.01</b> | <b>0.00</b> | <b>84.15</b> |

### Mitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| 2014         | 0.11        | 0.71        | 0.43        | 0.00        | 0.00          | 0.04         | 0.04        | 0.00           | 0.04          | 0.04        | 0.00        | 83.97        | 83.97        | 0.01        | 0.00        | 84.15        |
| <b>Total</b> | <b>0.11</b> | <b>0.71</b> | <b>0.43</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.04</b>  | <b>0.04</b> | <b>0.00</b>    | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>83.97</b> | <b>83.97</b> | <b>0.01</b> | <b>0.00</b> | <b>84.15</b> |

## 2.2 Overall Operational

### Unmitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### Mitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 3.0 Construction Detail

---

### 3.1 Mitigation Measures Construction

### 3.2 Demolition - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.02        | 0.16        | 0.08        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 20.69        | 20.69        | 0.00        | 0.00        | 20.72        |
| <b>Total</b> | <b>0.02</b> | <b>0.16</b> | <b>0.08</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>20.69</b> | <b>20.69</b> | <b>0.00</b> | <b>0.00</b> | <b>20.72</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |



### 3.2 Demolition - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2    | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.02        | 0.16        | 0.08        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 20.69        | 20.69        | 0.00        | 0.00        | 20.72        |
| <b>Total</b> | <b>0.02</b> | <b>0.16</b> | <b>0.08</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>20.69</b> | <b>20.69</b> | <b>0.00</b> | <b>0.00</b> | <b>20.72</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Construct Outlet Works - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.09        | 0.54        | 0.35        | 0.00        |               | 0.04         | 0.04        |                | 0.04          | 0.04        | 0.00        | 63.28        | 63.28        | 0.01        | 0.00        | 63.43        |
| <b>Total</b> | <b>0.09</b> | <b>0.54</b> | <b>0.35</b> | <b>0.00</b> |               | <b>0.04</b>  | <b>0.04</b> |                | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>63.28</b> | <b>63.28</b> | <b>0.01</b> | <b>0.00</b> | <b>63.43</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Construct Outlet Works - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.09        | 0.54        | 0.35        | 0.00        |               | 0.04         | 0.04        |                | 0.04          | 0.04        | 0.00        | 63.28        | 63.28        | 0.01        | 0.00        | 63.43        |
| <b>Total</b> | <b>0.09</b> | <b>0.54</b> | <b>0.35</b> | <b>0.00</b> |               | <b>0.04</b>  | <b>0.04</b> |                | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>63.28</b> | <b>63.28</b> | <b>0.01</b> | <b>0.00</b> | <b>63.43</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 4.0 Mobile Detail

---

### 4.1 Mitigation Measures Mobile

#### 4.2 Trip Summary Information

| Land Use | Average Daily Trip Rate |          |        | Unmitigated | Mitigated  |
|----------|-------------------------|----------|--------|-------------|------------|
|          | Weekday                 | Saturday | Sunday | Annual VMT  | Annual VMT |
| Total    |                         |          |        |             |            |

#### 4.3 Trip Type Information

| Land Use | Miles      |            |             | Trip %     |            |             |
|----------|------------|------------|-------------|------------|------------|-------------|
|          | H-W or C-W | H-S or C-C | H-O or C-NW | H-W or C-W | H-S or C-C | H-O or C-NW |
|          |            |            |             |            |            |             |

### 5.0 Energy Detail

---

#### 5.1 Mitigation Measures Energy

### 6.0 Area Detail

---

#### 6.1 Mitigation Measures Area

|              | ROG       | NOx       | CO        | SO2       | Fugitive PM10 | Exhaust PM10 | PM10 Total | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2  | NBio- CO2 | Total CO2 | CH4       | N2O       | CO2e      |
|--------------|-----------|-----------|-----------|-----------|---------------|--------------|------------|----------------|---------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|
| Category     | tons/yr   |           |           |           |               |              |            |                |               |             | MT/yr     |           |           |           |           |           |
| Mitigated    | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| Unmitigated  | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| <b>Total</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b>     | <b>NA</b>    | <b>NA</b>  | <b>NA</b>      | <b>NA</b>     | <b>NA</b>   | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> |

## 6.2 Area by SubCategory

### Unmitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 6.2 Area by SubCategory

### Mitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |             |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 7.0 Water Detail

---

### 7.1 Mitigation Measures Water

## 8.0 Waste Detail

---

### 8.1 Mitigation Measures Waste

## 9.0 Vegetation

---

## Chabot Dam - Conventional Earthwork Alameda County, Annual

### 1.0 Project Characteristics

---

#### 1.1 Land Usage

#### 1.2 Other Project Characteristics

|                     |       |                                  |     |                        |                                |
|---------------------|-------|----------------------------------|-----|------------------------|--------------------------------|
| <b>Urbanization</b> | Rural | <b>Wind Speed (m/s)</b>          | 2.2 | <b>Utility Company</b> | Pacific Gas & Electric Company |
| <b>Climate Zone</b> | 4     | <b>Precipitation Freq (Days)</b> | 63  |                        |                                |

#### 1.3 User Entered Comments

- Project Characteristics -
- Land Use -
- Construction Phase - project description
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD

Off-road Equipment - PD

Off-road Equipment - PD

Off-road Equipment - PD

## 2.0 Emissions Summary

---

### 2.1 Overall Construction

#### Unmitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2     | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| 2014         | 0.01        | 0.05        | 0.04        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 6.13          | 6.13          | 0.00        | 0.00        | 6.14          |
| 2015         | 0.59        | 4.48        | 2.89        | 0.01        | 0.00          | 0.24         | 0.24        | 0.00           | 0.24          | 0.24        | 0.00        | 480.99        | 480.99        | 0.05        | 0.00        | 481.98        |
| <b>Total</b> | <b>0.60</b> | <b>4.53</b> | <b>2.93</b> | <b>0.01</b> | <b>0.00</b>   | <b>0.24</b>  | <b>0.24</b> | <b>0.00</b>    | <b>0.24</b>   | <b>0.24</b> | <b>0.00</b> | <b>487.12</b> | <b>487.12</b> | <b>0.05</b> | <b>0.00</b> | <b>488.12</b> |

#### Mitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2     | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| 2014         | 0.01        | 0.05        | 0.04        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 6.13          | 6.13          | 0.00        | 0.00        | 6.14          |
| 2015         | 0.59        | 4.48        | 2.89        | 0.01        | 0.00          | 0.24         | 0.24        | 0.00           | 0.24          | 0.24        | 0.00        | 480.99        | 480.99        | 0.05        | 0.00        | 481.98        |
| <b>Total</b> | <b>0.60</b> | <b>4.53</b> | <b>2.93</b> | <b>0.01</b> | <b>0.00</b>   | <b>0.24</b>  | <b>0.24</b> | <b>0.00</b>    | <b>0.24</b>   | <b>0.24</b> | <b>0.00</b> | <b>487.12</b> | <b>487.12</b> | <b>0.05</b> | <b>0.00</b> | <b>488.12</b> |



## 2.2 Overall Operational

### Unmitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### Mitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 3.0 Construction Detail

---

### 3.1 Mitigation Measures Construction

### 3.2 Dewater - Installation (Rig) - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.02        | 0.02        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.72        | 3.72        | 0.00        | 0.00        | 3.73        |
| <b>Total</b> | <b>0.00</b> | <b>0.02</b> | <b>0.02</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.72</b> | <b>3.72</b> | <b>0.00</b> | <b>0.00</b> | <b>3.73</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.2 Dewater - Installation (Rig) - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.02        | 0.02        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.72        | 3.72        | 0.00        | 0.00        | 3.73        |
| <b>Total</b> | <b>0.00</b> | <b>0.02</b> | <b>0.02</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.72</b> | <b>3.72</b> | <b>0.00</b> | <b>0.00</b> | <b>3.73</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.2 Dewater - Installation (Rig) - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.03        | 0.04        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 5.59        | 5.59        | 0.00        | 0.00        | 5.59        |
| <b>Total</b> | <b>0.00</b> | <b>0.03</b> | <b>0.04</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>5.59</b> | <b>5.59</b> | <b>0.00</b> | <b>0.00</b> | <b>5.59</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.2 Dewater - Installation (Rig) - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.03        | 0.04        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 5.59        | 5.59        | 0.00        | 0.00        | 5.59        |
| <b>Total</b> | <b>0.00</b> | <b>0.03</b> | <b>0.04</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>5.59</b> | <b>5.59</b> | <b>0.00</b> | <b>0.00</b> | <b>5.59</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Dewater - Installation (Dozer) - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.03        | 0.01        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 2.41        | 2.41        | 0.00        | 0.00        | 2.42        |
| <b>Total</b> | <b>0.00</b> | <b>0.03</b> | <b>0.01</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>2.41</b> | <b>2.41</b> | <b>0.00</b> | <b>0.00</b> | <b>2.42</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Dewater - Installation (Dozer) - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.03        | 0.01        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 2.41        | 2.41        | 0.00        | 0.00        | 2.42        |
| <b>Total</b> | <b>0.00</b> | <b>0.03</b> | <b>0.01</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>2.41</b> | <b>2.41</b> | <b>0.00</b> | <b>0.00</b> | <b>2.42</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.4 Dewater - Operation - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.26        | 2.04        | 1.34        | 0.00        |               | 0.11         | 0.11        |                | 0.11          | 0.11        | 0.00        | 226.50        | 226.50        | 0.02        | 0.00        | 226.93        |
| <b>Total</b> | <b>0.26</b> | <b>2.04</b> | <b>1.34</b> | <b>0.00</b> |               | <b>0.11</b>  | <b>0.11</b> |                | <b>0.11</b>   | <b>0.11</b> | <b>0.00</b> | <b>226.50</b> | <b>226.50</b> | <b>0.02</b> | <b>0.00</b> | <b>226.93</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |



### 3.4 Dewater - Operation - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.26        | 2.04        | 1.34        | 0.00        |               | 0.11         | 0.11        |                | 0.11          | 0.11        | 0.00        | 226.50        | 226.50        | 0.02        | 0.00        | 226.93        |
| <b>Total</b> | <b>0.26</b> | <b>2.04</b> | <b>1.34</b> | <b>0.00</b> |               | <b>0.11</b>  | <b>0.11</b> |                | <b>0.11</b>   | <b>0.11</b> | <b>0.00</b> | <b>226.50</b> | <b>226.50</b> | <b>0.02</b> | <b>0.00</b> | <b>226.93</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.5 Prep HR&Stockpile - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.05        | 0.35        | 0.23        | 0.00        |               | 0.02         | 0.02        |                | 0.02          | 0.02        | 0.00        | 36.04        | 36.04        | 0.00        | 0.00        | 36.13        |
| <b>Total</b> | <b>0.05</b> | <b>0.35</b> | <b>0.23</b> | <b>0.00</b> |               | <b>0.02</b>  | <b>0.02</b> |                | <b>0.02</b>   | <b>0.02</b> | <b>0.00</b> | <b>36.04</b> | <b>36.04</b> | <b>0.00</b> | <b>0.00</b> | <b>36.13</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.5 Prep HR&Stockpile - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.05        | 0.35        | 0.23        | 0.00        |               | 0.02         | 0.02        |                | 0.02          | 0.02        | 0.00        | 36.04        | 36.04        | 0.00        | 0.00        | 36.13        |
| <b>Total</b> | <b>0.05</b> | <b>0.35</b> | <b>0.23</b> | <b>0.00</b> |               | <b>0.02</b>  | <b>0.02</b> |                | <b>0.02</b>   | <b>0.02</b> | <b>0.00</b> | <b>36.04</b> | <b>36.04</b> | <b>0.00</b> | <b>0.00</b> | <b>36.13</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.6 Excavation - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.10        | 0.79        | 0.51        | 0.00        |               | 0.04         | 0.04        |                | 0.04          | 0.04        | 0.00        | 84.70        | 84.70        | 0.01        | 0.00        | 84.88        |
| <b>Total</b> | <b>0.10</b> | <b>0.79</b> | <b>0.51</b> | <b>0.00</b> |               | <b>0.04</b>  | <b>0.04</b> |                | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>84.70</b> | <b>84.70</b> | <b>0.01</b> | <b>0.00</b> | <b>84.88</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.6 Excavation - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.10        | 0.79        | 0.51        | 0.00        |               | 0.04         | 0.04        |                | 0.04          | 0.04        | 0.00        | 84.70        | 84.70        | 0.01        | 0.00        | 84.88        |
| <b>Total</b> | <b>0.10</b> | <b>0.79</b> | <b>0.51</b> | <b>0.00</b> |               | <b>0.04</b>  | <b>0.04</b> |                | <b>0.04</b>   | <b>0.04</b> | <b>0.00</b> | <b>84.70</b> | <b>84.70</b> | <b>0.01</b> | <b>0.00</b> | <b>84.88</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.7 Site Prep for Filing - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.06        | 0.04        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 5.37        | 5.37        | 0.00        | 0.00        | 5.38        |
| <b>Total</b> | <b>0.01</b> | <b>0.06</b> | <b>0.04</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>5.37</b> | <b>5.37</b> | <b>0.00</b> | <b>0.00</b> | <b>5.38</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.7 Site Prep for Filing - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.06        | 0.04        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 5.37        | 5.37        | 0.00        | 0.00        | 5.38        |
| <b>Total</b> | <b>0.01</b> | <b>0.06</b> | <b>0.04</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>5.37</b> | <b>5.37</b> | <b>0.00</b> | <b>0.00</b> | <b>5.38</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.8 Place and Compact Fill - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2     | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.15        | 1.16        | 0.69        | 0.00        |               | 0.06         | 0.06        |                | 0.06          | 0.06        | 0.00        | 116.09        | 116.09        | 0.01        | 0.00        | 116.35        |
| <b>Total</b> | <b>0.15</b> | <b>1.16</b> | <b>0.69</b> | <b>0.00</b> |               | <b>0.06</b>  | <b>0.06</b> |                | <b>0.06</b>   | <b>0.06</b> | <b>0.00</b> | <b>116.09</b> | <b>116.09</b> | <b>0.01</b> | <b>0.00</b> | <b>116.35</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |



### 3.8 Place and Compact Fill - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.15        | 1.16        | 0.69        | 0.00        |               | 0.06         | 0.06        |                | 0.06          | 0.06        | 0.00        | 116.09        | 116.09        | 0.01        | 0.00        | 116.35        |
| <b>Total</b> | <b>0.15</b> | <b>1.16</b> | <b>0.69</b> | <b>0.00</b> |               | <b>0.06</b>  | <b>0.06</b> |                | <b>0.06</b>   | <b>0.06</b> | <b>0.00</b> | <b>116.09</b> | <b>116.09</b> | <b>0.01</b> | <b>0.00</b> | <b>116.35</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.9 Site Finish HR&Stockpiles - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.06        | 0.05        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 6.72        | 6.72        | 0.00        | 0.00        | 6.73        |
| <b>Total</b> | <b>0.01</b> | <b>0.06</b> | <b>0.05</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>6.72</b> | <b>6.72</b> | <b>0.00</b> | <b>0.00</b> | <b>6.73</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.9 Site Finish HR&Stockpiles - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.06        | 0.05        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 6.72        | 6.72        | 0.00        | 0.00        | 6.73        |
| <b>Total</b> | <b>0.01</b> | <b>0.06</b> | <b>0.05</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>6.72</b> | <b>6.72</b> | <b>0.00</b> | <b>0.00</b> | <b>6.73</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 4.0 Mobile Detail

---

### 4.1 Mitigation Measures Mobile

#### 4.2 Trip Summary Information

| Land Use | Average Daily Trip Rate |          |        | Unmitigated | Mitigated  |
|----------|-------------------------|----------|--------|-------------|------------|
|          | Weekday                 | Saturday | Sunday | Annual VMT  | Annual VMT |
| Total    |                         |          |        |             |            |

#### 4.3 Trip Type Information

| Land Use | Miles      |            |             | Trip %     |            |             |
|----------|------------|------------|-------------|------------|------------|-------------|
|          | H-W or C-W | H-S or C-C | H-O or C-NW | H-W or C-W | H-S or C-C | H-O or C-NW |
|          |            |            |             |            |            |             |

### 5.0 Energy Detail

---

#### 5.1 Mitigation Measures Energy

### 6.0 Area Detail

---

#### 6.1 Mitigation Measures Area

|              | ROG       | NOx       | CO        | SO2       | Fugitive PM10 | Exhaust PM10 | PM10 Total | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2  | NBio- CO2 | Total CO2 | CH4       | N2O       | CO2e      |
|--------------|-----------|-----------|-----------|-----------|---------------|--------------|------------|----------------|---------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|
| Category     | tons/yr   |           |           |           |               |              |            |                |               |             | MT/yr     |           |           |           |           |           |
| Mitigated    | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| Unmitigated  | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| <b>Total</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b>     | <b>NA</b>    | <b>NA</b>  | <b>NA</b>      | <b>NA</b>     | <b>NA</b>   | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> |

## 6.2 Area by SubCategory

### Unmitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 6.2 Area by SubCategory

### Mitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |             |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 7.0 Water Detail

---

### 7.1 Mitigation Measures Water

## 8.0 Waste Detail

---

### 8.1 Mitigation Measures Waste

## 9.0 Vegetation

---

**CDSM Construction (off-road)**  
**Alameda County, Annual**

**1.0 Project Characteristics**

---

**1.1 Land Usage**

**1.2 Other Project Characteristics**

**Urbanization** Rural

**Wind Speed (m/s)** 2.2

**Utility Company** Pacific Gas & Electric Company

**Climate Zone** 4

**Precipitation Freq (Days)** 63

**1.3 User Entered Comments**

- Project Characteristics -
- Construction Phase - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD
- Off-road Equipment - PD

Land Use -

Construction Off-road Equipment Mitigation -

## 2.0 Emissions Summary

---

### 2.1 Overall Construction

#### Unmitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| 2014         | 0.24        | 2.46        | 0.98        | 0.00        | 0.00          | 0.10         | 0.10        | 0.00           | 0.10          | 0.10        | 0.00        | 273.74        | 273.74        | 0.02        | 0.00        | 274.16        |
| 2015         | 0.07        | 0.52        | 0.31        | 0.00        | 0.00          | 0.03         | 0.03        | 0.00           | 0.03          | 0.03        | 0.00        | 53.19         | 53.19         | 0.01        | 0.00        | 53.31         |
| <b>Total</b> | <b>0.31</b> | <b>2.98</b> | <b>1.29</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.13</b>  | <b>0.13</b> | <b>0.00</b>    | <b>0.13</b>   | <b>0.13</b> | <b>0.00</b> | <b>326.93</b> | <b>326.93</b> | <b>0.03</b> | <b>0.00</b> | <b>327.47</b> |

#### Mitigated Construction

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Year         | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| 2014         | 0.26        | 2.27        | 1.17        | 0.00        | 0.00          | 0.10         | 0.10        | 0.00           | 0.10          | 0.10        | 0.00        | 273.74        | 273.74        | 0.02        | 0.00        | 274.16        |
| 2015         | 0.07        | 0.52        | 0.31        | 0.00        | 0.00          | 0.03         | 0.03        | 0.00           | 0.03          | 0.03        | 0.00        | 53.19         | 53.19         | 0.01        | 0.00        | 53.31         |
| <b>Total</b> | <b>0.33</b> | <b>2.79</b> | <b>1.48</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.13</b>  | <b>0.13</b> | <b>0.00</b>    | <b>0.13</b>   | <b>0.13</b> | <b>0.00</b> | <b>326.93</b> | <b>326.93</b> | <b>0.03</b> | <b>0.00</b> | <b>327.47</b> |



## 2.2 Overall Operational

### Unmitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### Mitigated Operational

|              | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Area         | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 3.0 Construction Detail

---

### 3.1 Mitigation Measures Construction

Use Cleaner Engines for Construction Equipment

Use DPF for Construction Equipment

### 3.2 Prep HR&Stockpile - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.03        | 0.19        | 0.12        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 18.02        | 18.02        | 0.00        | 0.00        | 18.07        |
| <b>Total</b> | <b>0.03</b> | <b>0.19</b> | <b>0.12</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>18.02</b> | <b>18.02</b> | <b>0.00</b> | <b>0.00</b> | <b>18.07</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.2 Prep HR&Stockpile - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.03        | 0.19        | 0.12        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 18.02        | 18.02        | 0.00        | 0.00        | 18.07        |
| <b>Total</b> | <b>0.03</b> | <b>0.19</b> | <b>0.12</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>18.02</b> | <b>18.02</b> | <b>0.00</b> | <b>0.00</b> | <b>18.07</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Excavation of CDSM Platform - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2    | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.01        | 0.11        | 0.07        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 10.71        | 10.71        | 0.00        | 0.00        | 10.74        |
| <b>Total</b> | <b>0.01</b> | <b>0.11</b> | <b>0.07</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>10.71</b> | <b>10.71</b> | <b>0.00</b> | <b>0.00</b> | <b>10.74</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.3 Excavation of CDSM Platform - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.01        | 0.11        | 0.07        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 10.71        | 10.71        | 0.00        | 0.00        | 10.74        |
| <b>Total</b> | <b>0.01</b> | <b>0.11</b> | <b>0.07</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>10.71</b> | <b>10.71</b> | <b>0.00</b> | <b>0.00</b> | <b>10.74</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.4 Setup CDSM Rigs - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.03        | 0.25        | 0.13        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 32.31        | 32.31        | 0.00        | 0.00        | 32.36        |
| <b>Total</b> | <b>0.03</b> | <b>0.25</b> | <b>0.13</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>32.31</b> | <b>32.31</b> | <b>0.00</b> | <b>0.00</b> | <b>32.36</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.4 Setup CDSM Rigs - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.03        | 0.24        | 0.13        | 0.00        |               | 0.01         | 0.01        |                | 0.01          | 0.01        | 0.00        | 32.31        | 32.31        | 0.00        | 0.00        | 32.36        |
| <b>Total</b> | <b>0.03</b> | <b>0.24</b> | <b>0.13</b> | <b>0.00</b> |               | <b>0.01</b>  | <b>0.01</b> |                | <b>0.01</b>   | <b>0.01</b> | <b>0.00</b> | <b>32.31</b> | <b>32.31</b> | <b>0.00</b> | <b>0.00</b> | <b>32.36</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.5 CDSM Production - 2014

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.17        | 1.91        | 0.67        | 0.00        |               | 0.07         | 0.07        |                | 0.07          | 0.07        | 0.00        | 212.70        | 212.70        | 0.01        | 0.00        | 212.99        |
| <b>Total</b> | <b>0.17</b> | <b>1.91</b> | <b>0.67</b> | <b>0.00</b> |               | <b>0.07</b>  | <b>0.07</b> |                | <b>0.07</b>   | <b>0.07</b> | <b>0.00</b> | <b>212.70</b> | <b>212.70</b> | <b>0.01</b> | <b>0.00</b> | <b>212.99</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |



### 3.5 CDSM Production - 2014

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2      | Total CO2     | CH4         | N2O         | CO2e          |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|---------------|---------------|-------------|-------------|---------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |               |               |             |             |               |
| Off-Road     | 0.19        | 1.73        | 0.85        | 0.00        |               | 0.07         | 0.07        |                | 0.07          | 0.07        | 0.00        | 212.70        | 212.70        | 0.01        | 0.00        | 212.99        |
| <b>Total</b> | <b>0.19</b> | <b>1.73</b> | <b>0.85</b> | <b>0.00</b> |               | <b>0.07</b>  | <b>0.07</b> |                | <b>0.07</b>   | <b>0.07</b> | <b>0.00</b> | <b>212.70</b> | <b>212.70</b> | <b>0.01</b> | <b>0.00</b> | <b>212.99</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.6 Tear Down CDSM Rigs - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.03        | 0.01        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.40        | 3.40        | 0.00        | 0.00        | 3.41        |
| <b>Total</b> | <b>0.00</b> | <b>0.03</b> | <b>0.01</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.40</b> | <b>3.40</b> | <b>0.00</b> | <b>0.00</b> | <b>3.41</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.6 Tear Down CDSM Rigs - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.00        | 0.02        | 0.01        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.40        | 3.40        | 0.00        | 0.00        | 3.41        |
| <b>Total</b> | <b>0.00</b> | <b>0.02</b> | <b>0.01</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.40</b> | <b>3.40</b> | <b>0.00</b> | <b>0.00</b> | <b>3.41</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.7 Place and Compact Fill - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.06        | 0.46        | 0.28        | 0.00        |               | 0.02         | 0.02        |                | 0.02          | 0.02        | 0.00        | 46.43        | 46.43        | 0.00        | 0.00        | 46.53        |
| <b>Total</b> | <b>0.06</b> | <b>0.46</b> | <b>0.28</b> | <b>0.00</b> |               | <b>0.02</b>  | <b>0.02</b> |                | <b>0.02</b>   | <b>0.02</b> | <b>0.00</b> | <b>46.43</b> | <b>46.43</b> | <b>0.00</b> | <b>0.00</b> | <b>46.53</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.7 Place and Compact Fill - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2     | Total CO2    | CH4         | N2O         | CO2e         |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|--------------|--------------|-------------|-------------|--------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |              |              |             |             |              |
| Off-Road     | 0.06        | 0.46        | 0.27        | 0.00        |               | 0.02         | 0.02        |                | 0.02          | 0.02        | 0.00        | 46.43        | 46.43        | 0.00        | 0.00        | 46.53        |
| <b>Total</b> | <b>0.06</b> | <b>0.46</b> | <b>0.27</b> | <b>0.00</b> |               | <b>0.02</b>  | <b>0.02</b> |                | <b>0.02</b>   | <b>0.02</b> | <b>0.00</b> | <b>46.43</b> | <b>46.43</b> | <b>0.00</b> | <b>0.00</b> | <b>46.53</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.8 Site Finish HR&Stockpile - 2015

#### Unmitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.03        | 0.03        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.36        | 3.36        | 0.00        | 0.00        | 3.37        |
| <b>Total</b> | <b>0.01</b> | <b>0.03</b> | <b>0.03</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.36</b> | <b>3.36</b> | <b>0.00</b> | <b>0.00</b> | <b>3.37</b> |

#### Unmitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

### 3.8 Site Finish HR&Stockpile - 2015

#### Mitigated Construction On-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Off-Road     | 0.01        | 0.03        | 0.03        | 0.00        |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 3.36        | 3.36        | 0.00        | 0.00        | 3.37        |
| <b>Total</b> | <b>0.01</b> | <b>0.03</b> | <b>0.03</b> | <b>0.00</b> |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>3.36</b> | <b>3.36</b> | <b>0.00</b> | <b>0.00</b> | <b>3.37</b> |

#### Mitigated Construction Off-Site

|              | ROG         | NOx         | CO          | SO2         | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |
|--------------|-------------|-------------|-------------|-------------|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| Category     | tons/yr     |             |             |             |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |
| Hauling      | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Vendor       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Worker       | 0.00        | 0.00        | 0.00        | 0.00        | 0.00          | 0.00         | 0.00        | 0.00           | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b>   | <b>0.00</b>  | <b>0.00</b> | <b>0.00</b>    | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 4.0 Mobile Detail

---

### 4.1 Mitigation Measures Mobile

#### 4.2 Trip Summary Information

| Land Use | Average Daily Trip Rate |          |        | Unmitigated | Mitigated  |
|----------|-------------------------|----------|--------|-------------|------------|
|          | Weekday                 | Saturday | Sunday | Annual VMT  | Annual VMT |
| Total    |                         |          |        |             |            |

#### 4.3 Trip Type Information

| Land Use | Miles      |            |             | Trip %     |            |             |
|----------|------------|------------|-------------|------------|------------|-------------|
|          | H-W or C-W | H-S or C-C | H-O or C-NW | H-W or C-W | H-S or C-C | H-O or C-NW |
|          |            |            |             |            |            |             |

### 5.0 Energy Detail

---

#### 5.1 Mitigation Measures Energy

### 6.0 Area Detail

---

#### 6.1 Mitigation Measures Area



|              | ROG       | NOx       | CO        | SO2       | Fugitive PM10 | Exhaust PM10 | PM10 Total | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2  | NBio- CO2 | Total CO2 | CH4       | N2O       | CO2e      |           |
|--------------|-----------|-----------|-----------|-----------|---------------|--------------|------------|----------------|---------------|-------------|-----------|-----------|-----------|-----------|-----------|-----------|-----------|
| Category     | tons/yr   |           |           |           |               |              |            |                |               |             | MT/yr     |           |           |           |           |           |           |
| Mitigated    | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| Unmitigated  | 0.00      |           |           |           |               | 0.00         | 0.00       |                | 0.00          | 0.00        | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      | 0.00      |
| <b>Total</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b>     | <b>NA</b>    | <b>NA</b>  | <b>NA</b>      | <b>NA</b>     | <b>NA</b>   | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> | <b>NA</b> |

## 6.2 Area by SubCategory

### Unmitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio- CO2   | Total CO2   | CH4         | N2O         | CO2e        |             |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 6.2 Area by SubCategory

### Mitigated

|                       | ROG         | NOx | CO | SO2 | Fugitive PM10 | Exhaust PM10 | PM10 Total  | Fugitive PM2.5 | Exhaust PM2.5 | PM2.5 Total | Bio- CO2    | NBio-CO2    | Total CO2   | CH4         | N2O         | CO2e        |             |
|-----------------------|-------------|-----|----|-----|---------------|--------------|-------------|----------------|---------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|-------------|
| SubCategory           | tons/yr     |     |    |     |               |              |             |                |               |             | MT/yr       |             |             |             |             |             |             |
| Architectural Coating | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| Consumer Products     | 0.00        |     |    |     |               | 0.00         | 0.00        |                | 0.00          | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        | 0.00        |
| <b>Total</b>          | <b>0.00</b> |     |    |     |               | <b>0.00</b>  | <b>0.00</b> |                | <b>0.00</b>   | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> | <b>0.00</b> |

## 7.0 Water Detail

---

### 7.1 Mitigation Measures Water

## 8.0 Waste Detail

---

### 8.1 Mitigation Measures Waste

## 9.0 Vegetation

---

Chabot Dam  
Construction Emissions Summary

10-hour Operational  
Conventional Earthwork

| Construction Phase/Emission Source                       | Pollutants (tons) |                 |              |                 |                  |                   | Metric Tons<br>CO <sub>2</sub> e | Metric Tons<br>CO <sub>2</sub> e | Days |
|--|-------------------|-----------------|--------------|-----------------|------------------|-------------------|----------------------------------|----------------------------------|------|
|  | ROG               | NO <sub>x</sub> | CO           | SO <sub>x</sub> | PM <sub>10</sub> | PM <sub>2.5</sub> |                                  |                                  |      |
| Outlet Works subtotal                                    | 0.13              | 1.17            | 0.60         | 0.00            | 0.06             | 0.05              | 192                              | 188                              | 225  |
| <i>Off-Road</i>  | 0.11              | 0.71            | 0.43         | 0               | 0.04             | 0.04              | 84                               | 84                               |      |
| <i>On-Road</i>   | 0.02              | 0.46            | 0.17         | 0.00            | 0.02             | 0.01              | 108                              | 104                              |      |
| Conventional Earthwork subtotal<br>(includes dewatering) | 0.72              | 7.33            | 3.81         | 0.02            | 0.34             | 0.31              | 1,117                            | 1,098                            |      |
| <i>Off-Road</i>  | 0.60              | 4.53            | 2.93         | 0.01            | 0.24             | 0.24              | 488                              | 488                              |      |
| <i>On-Road</i>   | 0.12              | 2.80            | 0.88         | 0.01            | 0.10             | 0.07              | 629                              | 610                              |      |
| Internal and External Trips subtotal                     | 0.03              | 0.65            | 0.12         | 0.00            | 0.02             | 0.01              | 121                              | 119                              |      |
| <b>Total Emissions (tons)</b>                            | <b>0.88</b>       | <b>9.15</b>     | <b>4.52</b>  | <b>0.02</b>     | <b>0.42</b>      | <b>0.38</b>       | <b>1,429</b>                     | <b>1,405</b>                     |      |
| <b>Average Daily Emissions (lbs/day)</b>                 | <b>7.83</b>       | <b>81.33</b>    | <b>40.21</b> | <b>0.17</b>     | <b>3.72</b>      | <b>3.34</b>       |                                  |                                  |      |
| <b>Mitigated Daily Emissions (lbs/day)</b>               | <b>7.83</b>       | <b>65.06</b>    | <b>40.21</b> | <b>0.17</b>     | <b>3.72</b>      | <b>3.34</b>       |                                  |                                  |      |
| <b>BAAQMD Thresholds of Significance</b>                 | <b>54</b>         | <b>54</b>       |              |                 | <b>82</b>        | <b>54</b>         |                                  |                                  |      |

CDSM

| Construction Phase/Emission Source         | Pollutants (tons) |                 |              |                 |                  |                   | Metric Tons<br>CO <sub>2</sub> e | Metric Tons<br>CO <sub>2</sub> e | Days |
|--|-------------------|-----------------|--------------|-----------------|------------------|-------------------|----------------------------------|----------------------------------|------|
|  | ROG               | NO <sub>x</sub> | CO           | SO <sub>x</sub> | PM <sub>10</sub> | PM <sub>2.5</sub> |                                  |                                  |      |
| Outlet Works subtotal                      | 0.13              | 1.17            | 0.60         | 0.00            | 0.06             | 0.05              | 192                              | 188                              | 115  |
| <i>Off-Road</i>                            | 0.11              | 0.71            | 0.43         | 0               | 0.04             | 0.04              | 84                               | 84                               |      |
| <i>On-Road</i>                             | 0.02              | 0.46            | 0.17         | 0.00            | 0.02             | 0.01              | 108                              | 104                              |      |
| CDSM subtotal                              | 0.39              | 4.16            | 1.97         | 0.00            | 0.18             | 0.16              | 637                              | 627                              |      |
| <i>Off-Road</i>                            | 0.33              | 2.84            | 1.54         | 0               | 0.13             | 0.13              | 337                              | 337                              |      |
| <i>On-Road</i>                             | 0.06              | 1.32            | 0.43         | 0.00            | 0.05             | 0.03              | 300                              | 291                              |      |
| Internal and External Trips subtotal       | 0.03              | 0.65            | 0.12         | 0.00            | 0.02             | 0.01              | 121                              | 119                              |      |
| <b>Total Emissions (tons)</b>              | <b>0.55</b>       | <b>5.98</b>     | <b>2.69</b>  | <b>0.01</b>     | <b>0.26</b>      | <b>0.23</b>       | <b>950</b>                       | <b>934</b>                       |      |
| <b>Average Daily Emissions (lbs/day)</b>   | <b>9.50</b>       | <b>103.94</b>   | <b>46.74</b> | <b>0.09</b>     | <b>4.45</b>      | <b>3.99</b>       |                                  |                                  |      |
| <b>Mitigated Daily Emissions (lbs/day)</b> | <b>9.50</b>       | <b>83.15</b>    | <b>46.74</b> | <b>0.09</b>     | <b>4.45</b>      | <b>3.99</b>       |                                  |                                  |      |
| <b>BAAQMD Thresholds of Significance</b>   | <b>54</b>         | <b>54</b>       |              |                 | <b>82</b>        | <b>54</b>         |                                  |                                  |      |

Chabot Dam  
Construction On-Road Emissions

| Phase                               | Duration (work days) | One-Way Trips       |                    |                   | Total Activity |             | Total Pollutants (tons) |             |                 |             |                 |                  | Metric Tons CO <sub>2</sub> e | Metric Tons CO <sub>2</sub> e (LCFS/Pav) |                   |       |
|-------------------------------------|----------------------|---------------------|--------------------|-------------------|----------------|-------------|-------------------------|-------------|-----------------|-------------|-----------------|------------------|-------------------------------|--|-------------------|-------|
|                                     |                      | Daily One-Way Trips | Equipment Delivery | Material Delivery | Hauling        | Total Trips | Total Distance          | ROG         | NO <sub>x</sub> | CO          | SO <sub>x</sub> | PM <sub>10</sub> |                               |  | PM <sub>2.5</sub> |       |
| <b>Outlet Work</b>                  | <b>70</b>            |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Mobilization                        | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 49                  | 9                  | 40                | 0              | 409         | 12,270                  | 0.00        | 0.12            | 0.02        | 0.00            | 0.00             | 0.00                          | 0.00                                     | 22.74             | 22.40 |
| Worker Trips                        | 10                   | 46                  |                    |                   |                | 460         | 9,200                   | 0.00        | 0.00            | 0.01        | 0.00            | 0.00             | 0.00                          | 0.00                                     | 3.65              | 3.28  |
| Demobilization                      | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 8                   | 4                  | 0                 | 4              | 44          | 1,320                   | 0.00        | 0.01            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.00                                     | 2.45              | 2.41  |
| Worker Trips                        | 10                   | 54                  |                    |                   |                | 540         | 10,800                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 0.00                                     | 4.28              | 3.85  |
| Construct Outlet Works Upgrade      | 30                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 30                   | 40                  | 20                 | 20                | 0              | 620         | 18,600                  | 0.01        | 0.18            | 0.03        | 0.00            | 0.01             | 0.00                          | 34.47                                    | 33.96             |       |
| Worker Trips                        | 30                   | 54                  |                    |                   |                | 1,620       | 32,400                  | 0.00        | 0.02            | 0.05        | 0.00            | 0.00             | 0.00                          | 12.84                                    | 11.54             |       |
| Demobilization                      | 20                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 20                   | 45                  | 5                  | 20                | 0              | 405         | 12,150                  | 0.00        | 0.12            | 0.02        | 0.00            | 0.00             | 0.00                          | 22.52                                    | 22.18             |       |
| Worker Trips                        | 20                   | 30                  |                    |                   |                | 600         | 12,000                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.76                                     | 4.28              |       |
| <b>Outlet Works Total</b>           |                      |                     |                    |                   |                |             |                         | <b>0.02</b> | <b>0.46</b>     | <b>0.17</b> | <b>0.00</b>     | <b>0.02</b>      | <b>0.01</b>                   | <b>107.70</b>                            | <b>103.89</b>     |       |
| <b>Dewatering For Conventional</b>  | <b>210</b>           |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Mobilization                        | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 16                  |                    |                   |                | 160         | 3,200                   | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 1.27                                     | 1.14              |       |
| Installation                        | 40                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 40                   | 2                   | 0                  | 2                 | 0              | 80          | 2,400                   | 0.00        | 0.02            | 0.00        | 0.00            | 0.00             | 0.00                          | 4.45                                     | 4.38              |       |
| Worker Trips                        | 40                   | 16                  |                    |                   |                | 640         | 12,800                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 5.07                                     | 4.56              |       |
| Operation                           | 150                  |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 150                  | 6                   | 4                  | 2                 | 0              | 304         | 9,120                   | 0.00        | 0.09            | 0.02        | 0.00            | 0.00             | 0.00                          | 16.90                                    | 16.65             |       |
| Worker Trips                        | 150                  | 4                   |                    |                   |                | 600         | 12,000                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.76                                     | 4.28              |       |
| Demobilization                      | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 8                   |                    |                   |                | 80          | 1,600                   | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.63                                     | 0.57              |       |
| <b>Dewatering Total</b>             |                      |                     |                    |                   |                |             |                         | <b>0.01</b> | <b>0.13</b>     | <b>0.06</b> | <b>0.00</b>     | <b>0.01</b>      | <b>0.00</b>                   | <b>33.53</b>                             | <b>32.02</b>      |       |
| <b>Conventional Earthwork</b>       | <b>150</b>           |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Mobilization                        | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 56                  |                    |                   |                | 560         | 11,200                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.44                                     | 3.99              |       |
| Prep HR and Stockpiles              | 20                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 20                   | 20                  | 16                 | 4                 | 0              | 96          | 2,880                   | 0.00        | 0.03            | 0.00        | 0.00            | 0.00             | 0.00                          | 5.34                                     | 5.26              |       |
| Worker Trips                        | 20                   | 72                  |                    |                   |                | 1,440       | 28,800                  | 0.00        | 0.02            | 0.04        | 0.00            | 0.00             | 0.00                          | 11.41                                    | 10.26             |       |
| Excavation                          | 30                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 30                   | 72                  | 10                 | 4                 | 58             | 1,870       | 56,100                  | 0.02        | 0.53            | 0.10        | 0.00            | 0.02             | 0.01                          | 103.97                                   | 102.41            |       |
| Worker Trips                        | 30                   | 126                 |                    |                   |                | 3,780       | 75,600                  | 0.01        | 0.04            | 0.11        | 0.00            | 0.00             | 0.00                          | 29.96                                    | 26.94             |       |
| Site Prep for Filling               | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 43                  | 3                  | 40                | 0              | 403         | 12,090                  | 0.00        | 0.11            | 0.02        | 0.00            | 0.00             | 0.00                          | 22.41                                    | 22.07             |       |
| Worker Trips                        | 10                   | 40                  |                    |                   |                | 400         | 8,000                   | 0.00        | 0.00            | 0.01        | 0.00            | 0.00             | 0.00                          | 3.17                                     | 2.85              |       |
| Place and Compact Fill              | 50                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 50                   | 114                 | 4                  | 74                | 36             | 5,504       | 165,120                 | 0.06        | 1.57            | 0.28        | 0.00            | 0.05             | 0.03                          | 306.03                                   | 301.44            |       |
| Worker Trips                        | 50                   | 96                  |                    |                   |                | 4,800       | 96,000                  | 0.01        | 0.05            | 0.14        | 0.00            | 0.01             | 0.00                          | 38.05                                    | 34.21             |       |
| Site Finishing (HR and Stockpiles)  | 20                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 20                   | 59                  | 9                  | 50                | 0              | 1,009       | 30,270                  | 0.01        | 0.29            | 0.05        | 0.00            | 0.01             | 0.01                          | 56.10                                    | 55.26             |       |
| Worker Trips                        | 20                   | 60                  |                    |                   |                | 1,200       | 24,000                  | 0.00        | 0.01            | 0.03        | 0.00            | 0.00             | 0.00                          | 9.51                                     | 8.55              |       |
| Demobilization                      | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 56                  |                    |                   |                | 560         | 11,200                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.44                                     | 3.99              |       |
| <b>Conventional Earthwork Total</b> |                      |                     |                    |                   |                |             |                         | <b>0.12</b> | <b>2.67</b>     | <b>0.82</b> | <b>0.01</b>     | <b>0.10</b>      | <b>0.07</b>                   | <b>595.28</b>                            | <b>577.67</b>     |       |
| <b>CDSM Option</b>                  | <b>115</b>           |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Mobilization                        | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 56                  |                    |                   |                | 560         | 11,200                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.44                                     | 3.99              |       |
| Prep HR and Stockpiles              | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 20                  | 16                 | 4                 | 0              | 56          | 1,680                   | 0.00        | 0.02            | 0.00        | 0.00            | 0.00             | 0.00                          | 3.11                                     | 3.07              |       |
| Worker Trips                        | 10                   | 72                  |                    |                   |                | 720         | 14,400                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 5.71                                     | 5.13              |       |
| Excavation CDSM Platform            | 5                    |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 5                    | 27                  | 7                  | 4                 | 16             | 107         | 3,210                   | 0.00        | 0.03            | 0.01        | 0.00            | 0.00             | 0.00                          | 5.95                                     | 5.86              |       |
| Worker Trips                        | 5                    | 76                  |                    |                   |                | 380         | 7,600                   | 0.00        | 0.00            | 0.01        | 0.00            | 0.00             | 0.00                          | 3.01                                     | 2.71              |       |
| Setup 2 CDSM Rigs                   | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 50                  | 10                 | 40                | 0              | 410         | 12,300                  | 0.00        | 0.12            | 0.02        | 0.00            | 0.00             | 0.00                          | 22.80                                    | 22.45             |       |
| Worker Trips                        | 10                   | 72                  |                    |                   |                | 720         | 14,400                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 5.71                                     | 5.13              |       |
| CDSM Production                     | 25                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 25                   | 45                  | 5                  | 40                | 0              | 1,005       | 30,150                  | 0.01        | 0.29            | 0.05        | 0.00            | 0.01             | 0.01                          | 55.88                                    | 55.04             |       |
| Worker Trips                        | 25                   | 72                  |                    |                   |                | 1,800       | 36,000                  | 0.00        | 0.02            | 0.05        | 0.00            | 0.00             | 0.00                          | 14.27                                    | 12.83             |       |
| Strength Test                       | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 0                   | 0                  | 0                 | 0              | -           | -                       | -           | -               | -           | -               | -                | -                             | -  | -                 | -     |
| Worker Trips                        | 10                   | 40                  |                    |                   |                | 400         | 8,000                   | 0.00        | 0.00            | 0.01        | 0.00            | 0.00             | 0.00                          | 3.17                                     | 2.85              |       |
| Tear Down 2 CDSM Rigs               | 5                    |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 5                    | 76                  | 6                  | 70                | 0              | 356         | 10,680                  | 0.00        | 0.10            | 0.02        | 0.00            | 0.00             | 0.00                          | 19.79                                    | 19.50             |       |
| Worker Trips                        | 5                    | 56                  |                    |                   |                | 280         | 5,600                   | 0.00        | 0.00            | 0.01        | 0.00            | 0.00             | 0.00                          | 2.22                                     | 2.00              |       |
| Place and Compact Fill              | 20                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 20                   | 104                 | 10                 | 70                | 24             | 1,890       | 56,700                  | 0.02        | 0.54            | 0.10        | 0.00            | 0.02             | 0.01                          | 105.09                                   | 103.51            |       |
| Worker Trips                        | 20                   | 70                  |                    |                   |                | 1,400       | 28,000                  | 0.00        | 0.02            | 0.04        | 0.00            | 0.00             | 0.00                          | 11.10                                    | 9.98              |       |
| Site Finishing (HR and Stockpiles)  | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 60                  | 10                 | 50                | 0              | 510         | 15,300                  | 0.01        | 0.15            | 0.03        | 0.00            | 0.00             | 0.00                          | 28.36                                    | 27.93             |       |
| Worker Trips                        | 10                   | 60                  |                    |                   |                | 600         | 12,000                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.76                                     | 4.28              |       |
| Demobilization                      | 10                   |                     |                    |                   |                |             |                         |             |                 |             |                 |                  |                               |  |                   |       |
| Haul Trucks                         | 10                   | 4                   | 4                  | 0                 | 0              | 4           | 120                     | 0.00        | 0.00            | 0.00        | 0.00            | 0.00             | 0.00                          | 0.22                                     | 0.22              |       |
| Worker Trips                        | 10                   | 56                  |                    |                   |                | 560         | 11,200                  | 0.00        | 0.01            | 0.02        | 0.00            | 0.00             | 0.00                          | 4.44                                     | 3.99              |       |
| <b>CDSM Total</b>                   |                      |                     |                    |                   |                |             |                         | <b>0.06</b> | <b>1.32</b>     | <b>0.43</b> | <b>0.00</b>     | <b>0.05</b>      | <b>0.03</b>                   | <b>300.24</b>                            | <b>290.68</b>     |       |

Internal Trips (Worst-Case Scenario)

| Phase                       | Duration (work days) | Daily One-Way Trips | Total One-Way Trips | One-Way Trip Distance (miles) | Total VMT | Pollutants (tons) |                 |             |                 |                  |                   | CO <sub>2</sub> (LCFS/Pavley) |                 |
|-----------------------------|----------------------|---------------------|---------------------|-------------------------------|-----------|-------------------|-----------------|-------------|-----------------|------------------|-------------------|-------------------------------|-----------------|
|                             |                      |                     |                     |                               |           | ROG               | NO <sub>x</sub> | CO          | SO <sub>x</sub> | PM <sub>10</sub> | PM <sub>2.5</sub> |                               | CO <sub>2</sub> |
| Excavation                  | 30                   | 1167                | 35,000              | 0.98                          | 34,271    | 0.01              | 0.33            | 0.06        | 0.00            | 0.01             | 0.01              | 60.34                         | 59.44           |
| Replacement                 | 50                   | 700                 | 35,000              | 0.98                          | 34,271    | 0.01              | 0.33            | 0.06        | 0.00            | 0.01             | 0.01              | 60.34                         | 59.44           |
| <b>Total Internal Trips</b> |                      |                     |                     |                               |           | <b>0.03</b>       | <b>0.65</b>     | <b>0.12</b> | <b>0.00</b>     | <b>0.02</b>      | <b>0.01</b>       | <b>120.68</b>                 | <b>118.87</b>   |

On-Road Emission Factors (SFBAAB-2014)

Chabot Dam  
Construction On-Road Emissions

| Construction Phase/Equipment                    | Start Date | End Date   | Work Days | Number | Hrs/Day | Horsepower | Load Factor | Pollutants (tons) |                 |             |                 |                  |                   |                      |
|---|------------|------------|-----------|--------|---------|------------|-------------|-------------------|-----------------|-------------|-----------------|------------------|-------------------|----------------------|
|   |            |            |           |        |         |            |             | ROG               | NO <sub>x</sub> | CO          | SO <sub>x</sub> | PM <sub>10</sub> | PM <sub>2.5</sub> | MT CO <sub>2</sub> e |
| <b>Outlet Works</b>                             |            |            |           |        |         |            |             | <b>0.11</b>       | <b>0.71</b>     | <b>0.43</b> | <b>0</b>        | <b>0.04</b>      | <b>0.04</b>       | <b>84.15</b>         |
| <i>Demolition</i>                               | 10/15/2014 | 10/28/2014 | 10        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Crane   |            |            |           | 2      | 10      | 208        | 0.2881      |                   |                 |             |                 |                  |                   |                      |
| Loader  |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Dozer (T/L/B)                                   |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Work skiff (Other General Industrial Equipment) |            |            |           | 1      | 10      | 150        | 0.3417      |                   |                 |             |                 |                  |                   |                      |
| Barge (Other Construction Equipment)            |            |            |           | 1      | 10      | 327        | 0.4154      |                   |                 |             |                 |                  |                   |                      |
| <i>Construct Outlet Works</i>                   | 10/29/2014 | 12/9/2014  | 30        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Air compressor                                  |            |            |           | 2      | 10      | 78         | 0.3216      |                   |                 |             |                 |                  |                   |                      |
| Generator                                       |            |            |           | 1      | 10      | 84         | 0.4958      |                   |                 |             |                 |                  |                   |                      |
| Welding Set                                     |            |            |           | 2      | 10      | 46         | 0.3015      |                   |                 |             |                 |                  |                   |                      |
| Dump Truck (Off-Highway Truck)                  |            |            |           | 1      | 10      | 381        | 0.3819      |                   |                 |             |                 |                  |                   |                      |
| Loader  |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Dozer (T/L/B)                                   |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Work skiff (boat) (Other Gen Ind Equip)         |            |            |           | 1      | 10      | 150        | 0.3417      |                   |                 |             |                 |                  |                   |                      |
| <b>Dewatering for Conventional</b>              |            |            |           |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| <i>Installation</i>                             | 12/10/2014 | 2/3/2015   | 40        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 1      | 10      | 358        | 0.3953      | 0                 | 0.02            | 0.02        | 0               | 0                | 0                 | 3.73                 |
| Drill rig                                       |            |            |           | 1      | 10      | 82         | 0.5025      | 0                 | 0.03            | 0.04        | 0               | 0                | 0                 | 5.59                 |
| <i>Operation</i>                                | 2/4/2015   | 9/1/2015   | 150       |        |         |            |             | <b>0</b>          | <b>0.05</b>     | <b>0.06</b> | <b>0</b>        | <b>0</b>         | <b>0</b>          | <b>9.32</b>          |
| Generator                                       |            |            |           | 2      | 10      | 84         | 0.4958      |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 1      | 10      | 358        | 0.3953      |                   |                 |             |                 |                  |                   |                      |
| Drill rig                                       |            |            |           | 1      | 10      | 82         | 0.5025      |                   |                 |             |                 |                  |                   |                      |
| <b>Conventional Earthwork</b>                   |            |            |           |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| <i>Prep of HR and Stockpiles</i>                | 2/25/2015  | 3/24/2015  | 20        |        |         |            |             | 0.01              | 0.05            | 0.04        | 0               | 0                | 0                 | 6.14                 |
| Bulldozer                                       |            |            |           | 1      | 10      | 358        | 0.3953      | 0.59              | 4.48            | 2.89        | 0.01            | 0.24             | 0.24              | 481.98               |
| Compactor (Roller)                              |            |            |           | 1      | 10      | 84         | 0.3752      | <b>0.6</b>        | <b>4.53</b>     | <b>2.93</b> | <b>0.01</b>     | <b>0.24</b>      | <b>0.24</b>       | <b>488.12</b>        |
| Wood grinder/chipper (Other Gen Ind Equip)      |            |            |           | 2      | 10      | 150        | 0.3417      |                   |                 |             |                 |                  |                   |                      |
| Tree trimming vehicle (Aerial Lift)             |            |            |           | 4      | 10      | 34         | 0.3082      |                   |                 |             |                 |                  |                   |                      |
| <i>Excavation</i>                               | 3/25/2015  | 5/5/2015   | 30        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 2      | 10      | 358        | 0.3953      |                   |                 |             |                 |                  |                   |                      |
| Excavator                                       |            |            |           | 2      | 10      | 157        | 0.3819      |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 3      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| <i>Site Preparation for Filling</i>             | 5/6/2015   | 5/19/2015  | 10        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Compactor (Roller)                              |            |            |           | 3      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |
| <i>Place and Compact Fill</i>                   | 5/20/2015  | 7/28/2015  | 50        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 2      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 2      | 10      | 358        | 0.3953      |                   |                 |             |                 |                  |                   |                      |
| Compactor (Roller)                              |            |            |           | 2      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |
| <i>Site Finish HR and Stockpiles</i>            | 7/29/2015  | 8/25/2015  | 20        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Loader  |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Compactor (Roller)                              |            |            |           | 1      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |
| <b>CDSM</b>                                     |            |            |           |        |         |            |             | 0.26              | 2.27            | 1.17        | 0               | 0.1              | 0.1               | 274.16               |
| <i>Prep of HR and Stockpiles</i>                | 10/15/2014 | 10/28/2014 | 10        |        |         |            |             | 0.07              | 0.57            | 0.37        | 0               | 0.03             | 0.03              | 62.63                |
| Bulldozer                                       |            |            |           | 1      | 10      | 358        | 0.3953      | <b>0.33</b>       | <b>2.84</b>     | <b>1.54</b> | <b>0</b>        | <b>0.13</b>      | <b>0.13</b>       | <b>336.79</b>        |
| Compactor (Roller)                              |            |            |           | 1      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |
| Wood grinder/chipper (Other Gen Ind Equip)      |            |            |           | 2      | 10      | 150        | 0.3417      |                   |                 |             |                 |                  |                   |                      |
| Tree trimming vehicle (Aerial Lift)             |            |            |           | 4      | 10      | 34         | 0.3082      |                   |                 |             |                 |                  |                   |                      |
| <i>Excavation of CDSM Platform</i>              | 10/29/2014 | 11/4/2014  | 5         |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 2      | 10      | 358        | 0.3953      |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 3      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| <i>Setup 2 CDSM Rigs</i>                        | 11/5/2014  | 11/18/2014 | 10        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Crane   |            |            |           | 2      | 10      | 208        | 0.2881      |                   |                 |             |                 |                  |                   |                      |
| Grout plant (Other Construction Equipment)      |            |            |           | 2      | 10      | 327        | 0.4154      |                   |                 |             |                 |                  |                   |                      |
| Trailers (Generator)                            |            |            |           | 2      | 10      | 84         | 0.4958      |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 3      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| <i>CDSM Production</i>                          | 11/19/2014 | 12/23/2014 | 25        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Base Rig (Crane)                                |            |            |           | 2      | 10      | 208        | 0.2881      |                   |                 |             |                 |                  |                   |                      |
| Generator                                       |            |            |           | 1      | 10      | 1500       | 0.4958      |                   |                 |             |                 |                  |                   |                      |
| Generator                                       |            |            |           | 2      | 10      | 460        | 0.4958      |                   |                 |             |                 |                  |                   |                      |
| Backhoes  |            |            |           | 2      | 10      | 115        | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 3      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| <i>Tear Down 2 CDSM Rigs</i>                    | 1/7/2015   | 1/13/2015  | 5         |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Crane   |            |            |           | 2      | 10      | 208        | 0.2881      |                   |                 |             |                 |                  |                   |                      |
| <i>Place and Compact Fill</i>                   | 1/14/2015  | 2/10/2015  | 20        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Bulldozer                                       |            |            |           | 2      | 10      | 358        | 0.3953      |                   |                 |             |                 |                  |                   |                      |
| Compactor (Roller)                              |            |            |           | 1      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |
| Rubber tire loaders                             |            |            |           | 3      | 10      | 87         | 0.3618      |                   |                 |             |                 |                  |                   |                      |
| <i>Site Finish HR and Stockpiles</i>            | 2/11/2015  | 2/24/2015  | 10        |        |         |            |             |                   |                 |             |                 |                  |                   |                      |
| Loader  |            |            |           | 1      | 10      | 75         | 0.3685      |                   |                 |             |                 |                  |                   |                      |
| Compactor (Roller)                              |            |            |           | 1      | 10      | 84         | 0.3752      |                   |                 |             |                 |                  |                   |                      |

Note: Totals for CDSM include dewatering



## Cancer Risk Calculation

### Cancer Risk Equations (Risk = Dose-Inhalation \* CPF)

|                                    |                                 |
|------------------------------------|---------------------------------|
| Cancer Potency Factor (Inhalation) | 1.1 mg/kg/day                   |
| Concentration (annual avg)         | 0.3309 $\mu\text{g}/\text{m}^3$ |
| Breathing Rate                     | 302 liter/kg/day                |
| Inhalation Absorption Factor       | 1 DPM                           |
| Exposure Frequency                 | 350 days/year                   |
| Exposure Duration                  | 70 years                        |
| Averaging Time Period              | 25550 days/period               |
| <br>                               |                                 |
| Multiplying Factor                 | 318.55 $\mu\text{g}/\text{m}^3$ |
| Adjustment Exposure Period         | 1.00 years                      |
| <br>                               |                                 |
| Cancer Risk (w/ adjustment)        | 1.51                            |
| <br>                               |                                 |
| Health Hazard REL (DPM)            | 5 $\mu\text{g}/\text{m}^3$      |
| Health Hazard Index                | 0.06618                         |
| <br>                               |                                 |
| Adjustment Factor                  | 0.1                             |
| Concentration                      | 3.309                           |

EMFAC2011 Emission Rates  
 Region Type: Air Basin  
 Region: San Francisco Bay Area  
 Calendar Year: 2014

Season: Annual

Vehicle Classification: EMFAC2007 Categories


| Region      | CalYr | Season | Veh_Class | Fuel | MdlYr     | Speed<br>(miles/hr) | Population<br>(vehicles) | VMT<br>(miles/day) | Trips<br>(trips/day) | ROG_RUNEX<br>(gms/mile) | CO_RUNEX<br>(gms/mile) | NOX_RUNEX<br>(gms/mile) | CO2_RUNEX<br>(gms/mile) | CO2_RUNEX_Pavley<br>(gms/mile) | PM10_RUNEX<br>(gms/mile) | PM10_PMTW<br>(gms/mile) | PM10_PMBW<br>(gms/mile) | PM2_5_RUNEX<br>(gms/mile) | PM2_5_PMTW<br>(gms/mile) | PM2_5_PMBW<br>(gms/mile) | SOX_RUNEX<br>(gms/mile) |             |             |
|-------------|-------|--------|-----------|------|-----------|---------------------|--------------------------|--------------------|----------------------|-------------------------|------------------------|-------------------------|-------------------------|--------------------------------|--------------------------|-------------------------|-------------------------|---------------------------|--------------------------|--------------------------|-------------------------|-------------|-------------|
| San Franci: | 2014  | Annual | LDA       | GAS  | Aggregate | Aggregate           | 2812158                  | 98052435           | 17707132             | 0.045603397             | 1.445620129            | 0.139626932             | 338.9694216             | 301.1292                       | 0.046853                 | 0.002103012             | 0.007999958             | 0.036749814               | 0.019660906              | 0.001910996              | 0.001999999             | 0.01574992  | 0.003407989 |
| San Franci: | 2014  | Annual | LDA       | DSL  | Aggregate | Aggregate           | 13208.48                 | 430993.1           | 77835.36             | 0.050253135             | 0.266568042            | 0.652968874             | 352.2260574             | 310.2152                       | 0.081797                 | 0.037047186             | 0.007999958             | 0.036749815               | 0.051833321              | 0.034083412              | 0.001999999             | 0.015749919 | 0.003362568 |
| San Franci: | 2014  | Annual | LDT1      | GAS  | Aggregate | Aggregate           | 321591.3                 | 11334007           | 1959440              | 0.116224824             | 3.514124064            | 0.368834391             | 390.1254238             | 356.0995                       | 0.049491                 | 0.004740901             | 0.007999959             | 0.036749815               | 0.022066381              | 0.004316472              | 0.001999999             | 0.01574992  | 0.00395364  |
| San Franci: | 2014  | Annual | LDT1      | DSL  | Aggregate | Aggregate           | 455.7314                 | 14866.69           | 2405.855             | 0.088492535             | 0.397213609            | 0.807953569             | 361.2034701             | 319.5704                       | 0.118812                 | 0.074062632             | 0.007999959             | 0.036749815               | 0.085887531              | 0.068137622              | 0.001999999             | 0.01574992  | 0.003448272 |
| San Franci: | 2014  | Annual | LDT2      | GAS  | Aggregate | Aggregate           | 846663.5                 | 31463268           | 5329805              | 0.051116811             | 1.892841029            | 0.249375774             | 461.5361023             | 427.2143                       | 0.046819                 | 0.002069434             | 0.007999958             | 0.036749815               | 0.019638872              | 0.001888963              | 0.001999999             | 0.01574992  | 0.004638739 |
| San Franci: | 2014  | Annual | LDT2      | DSL  | Aggregate | Aggregate           | 418.7829                 | 15363.82           | 2416.487             | 0.058961263             | 0.30035645             | 0.737251306             | 355.0894556             | 316.7681                       | 0.091559                 | 0.046808868             | 0.007999959             | 0.036749816               | 0.060814069              | 0.04306416               | 0.001999999             | 0.01574992  | 0.003389904 |
| San Franci: | 2014  | Annual | T7        | GAS  | Aggregate | Aggregate           | 508.1414                 | 60020.25           | 10166.89             | 1.106436122             | 34.22122993            | 6.044211566             | 584.6674365             | 575.8974                       | 0.045925                 | 0.001174969             | 0.007999959             | 0.036749817               | 0.018754801              | 0.001004891              | 0.001999999             | 0.01574992  | 0.006410078 |
| San Franci: | 2014  | Annual | T7        | DSL  | Aggregate | Aggregate           | 28507.59                 | 3934593            | 0                    | 0.336318773             | 1.536531162            | 8.622808304             | 1760.695678             | 1734.285                       | 0.256558                 | 0.161020539             | 0.035188757             | 0.060348718               | 0.182799821              | 0.148138896              | 0.008797189             | 0.025863736 | 0.01679786  |



## **APPENDIX H**

---

### Noise Calculations



**LEGEND**

| Transportation Noise Sources | Aviation Noise Sources |
|------------------------------|------------------------|
| 75 dB Ldn                    | 75 dB CNEL             |
| 70 dB Ldn                    | 70 dB CNEL             |
| 65 dB Ldn                    | 65 dB CNEL             |
| 60 dB Ldn                    | 60 dB CNEL             |

Source: Illingworth and Rodkin, 2000

# 2000 NOISE CONTOURS

FIGURE 6-2

San Leandro General Plan Update, 2002

# CHABOT DAM SEISMIC RETROFIT NOISE CALCULATIONS

Noise levels are measured in decibel units, a logarithmic scale. The noise level at a given distance from a noise source can be calculated using the Inverse Square Law of Noise formula given below:

$$L_2 = L_1 - 20 \log (R_2/R_1)$$

Where:  $L_1$  = Noise level measured at a distance  $R_1$  from the source and  
 $L_2$  = Noise level at a selected distance  $R_2$  from the source.

The Alameda County Noise Element of 1994 contains graphs and information to estimate noise levels when combining sounds. To combine different sound levels, Figure 1 is used to determine the dB increase based on difference in dB levels between the two sounds. When combining two sounds, each with equal sound levels, the sum of the sounds is the original level plus 3 dB (Alameda County Noise Element 1994). A decibel calculator is available online (<http://sphere.sourceforge.net/flik/misc/db.html>) that estimates noise levels when combining two or more sound sources. The online noise calculator produces the same results as the Alameda County Noise Element Figure 1, but can be used to combine more than two distinct noise sources.

## Noise Levels from Construction Equipment

Noise levels associated with each piece of equipment are shown in **Table 3.9-4**.

| <b>Table 3.9-4<br/>Construction Equipment 50-Foot Noise Emission Limits</b> |   |                  |
|---|---|------------------|
| Equipment Category  | Maximum Noise Level<br>(A-weighted decibels) <sup>1,2</sup> | Short/Continuous |
| Air Compressor <sup>3</sup>   | 70  | Short            |
| Bulldozer   | 85  | Continuous       |
| Concrete Pump   | 76  | Continuous       |
| CDSM Rig  | 75  | Continuous       |
| Crane   | 85  | Continuous       |
| Dump Truck  | 84  | Continuous       |
| Excavator   | 85  | Continuous       |
| Front End Loader  | 80  | Continuous       |
| Generator   | 78  | Continuous       |

**Table 3.9-4  
Construction Equipment 50-Foot Noise Emission Limits**

| <b>Equipment Category</b>     | <b>Maximum Noise Level<br/>(A-weighted decibels)<sup>1,2</sup></b> | <b>Short/Continuous</b> |
|-------------------------------|--|-------------------------|
| Grader                        | 85   | Continuous              |
| Grout Batching                | 85   | Continuous              |
| Hydraulic Backhoe             | 90   | Short                   |
| Jackhammer                    | 85   | Short                   |
| Sheepfoot or Vibrating Roller | 80   | Continuous              |
| Truck (dump, delivery)        | 84   | Continuous              |

Notes:  
<sup>1</sup> Measured at 50 feet from the construction equipment, with a "slow" (1 second) time constant.  
<sup>2</sup> Noise limits apply to total noise emitted from equipment and associated components operating at full power while engaged in its intended operation.  
<sup>3</sup> Portable air compressor rated at 75 cubic feet per minute or greater and that operates at greater than 50 pounds per square inch.  
Source: EBMUD 2010 and Burlison Consulting 2013

The highest noise level would be from a hydraulic backhoe with Lmax of 90 dBA at 50 feet. The maximum noise level for other construction equipment at the dam face would be 85 dBA. Assuming that two pieces of 85 dBA construction equipment were operating at the same time would result in a noise level of 88 dBA.

## **A. WORST CASE DAYTIME NOISE LEVELS**

The worst case daytime noise levels (Table 3.9-5) were calculated as follows for the dam excavation area and stockpile locations. The maximum noise levels would be the same for the CDSM option or the conventional earthwork option.

### **1. DAM EXCAVATION AREA**

#### **CDSM Option + Outlet Works Together**

One Hydraulic Backhoe - Maximum 90 dBA

Earth Moving Equipment - Maximum 85 dBA

Grout Batching - Maximum 85 dBA

#### **Stationary Equipment**

Combination of 2 CDSM Rigs, Pump, and Generator 82 dBA

**Using the Noise Calculator- Combined Noise Level is 92 dBA.**

### Conventional Earthwork + Outlet Works Together

One Hydraulic Backhoe – Maximum 90 dBA

Two pieces of earth moving equipment – 88 dBA

**Using the Noise Calculator- Combined Noise Level is 92 dBA**

### MAXIMUM DAYTIME NOISE LEVEL AT NEAREST SENSITIVE RECEPTOR TO DAM

The nearest residence was measured at 1,500 feet from Chabot Dam.

Using the inverse law, the noise level would be reduced by 29.5 dBA because of the distance from the dam.

$$L_2 = 92 - 20 \log (1,500/50) = 63 \text{ dBA} - \text{Maximum Noise Level}$$

The nearest residence is within 1,500 feet of the dam excavation area; the maximum noise level from construction activities would attenuate to 63 dBA at this residence. A natural noise attenuation factor is the presence of mature trees, vegetation, and topography that would shield many receptors from line-of-sight noise transmission generated by construction activities. This noise level at the nearest residence would be further reduced by an estimated 3 dBA to about 60 dBA because of the elevation difference between the residences and dam excavation area (150 feet) and the attenuation provided by trees and vegetation.

The maximum daytime noise level from the dam to the nearest receptor would be 60 dBA. As a mitigation measure, additional noise reductions would be achieved through engine control and noise control procedures that would further reduce the noise levels to **54 dBA**.

## 2. STAGING AREAS AND HAUL ROUTES

Noise analyses, similar to above, were completed for the potential stockpile locations assuming that one dump truck (84 dBA) and one piece of earth-moving equipment (85 dBA) would be operating at the same time with a combined noise level of 87 dBA.

The project includes two stockpile locations within the park and two external that were evaluated during alternatives analysis.

### 1) Filter Pond Stockpile

The nearest residence to the Filter Pond Stockpile is 800 feet away. The stockpile elevation is 190 feet amsl and the residence is at 98 feet amsl, according to Google Earth. The perceived noise from equipment at the stockpile area would be:

$$L_2 = 87 - 20 \log (800/50) = 63 \text{ dBA}$$

This noise level at the nearest residence would be further reduced by at least 1 dBA to about 62 dBA because of the elevation difference between the residences and stockpile area and the attenuation provided by trees and vegetation. As a mitigation measure, additional noise reductions would be achieved through engine control and noise control procedures that would further reduce the noise levels to **52 dBA**.

## 2) Park Stockpile and Haul Routes

The nearest residence to the Park Stockpile and haul routes is 500 feet away. The stockpile elevation is 112 feet amsl and residence is at 245 feet amsl, according to Google Earth. The perceived noise from equipment at the stockpile area would be:

$$L_2 = 87 - 20 \log (500/50) = 67 \text{ dBA}$$

This noise level at the nearest residence would be further reduced by at least 1 dBA to about 66 dBA because of the elevation difference between the residences and stockpile area and the attenuation provided by trees and vegetation. As a mitigation measure, additional noise reductions would be achieved through engine control and noise control procedures that would further reduce the noise levels to **56 dBA**.

## 3) Quarry Stockpile

The nearest residence to the Quarry Stockpile is 950 feet away. The stockpile elevation is 575 amsl feet and residence is at 473 feet amsl, according to Google Earth. The perceived noise from equipment at the stockpile area would be:

$$L_2 = 87 - 20 \log (950/50) = 61 \text{ dBA}$$

This noise level at the nearest residence would be further reduced by at least 1 dBA to about 60 dBA because of the elevation difference between the residences and stockpile area and the attenuation provided by trees and vegetation. As a mitigation measure, additional noise reductions would be achieved through engine control and noise control procedures that would further reduce the noise levels to **50 dBA**.

## 4) Covington Stockpile

The Covington Stockpile would require dump trucks to traverse Lake Chabot Road adjacent to residences. The stockpile location is adjacent to the east of Highway 580, across the freeway from residences. Intermittent noise from equipment would not be expected to significantly contribute to noise levels experienced by the nearest residents on the west side of the Freeway. Additional traffic noise along Lake Chabot Road would likely not affect nearby residents.

## **B. WORST CASE NIGHTTIME NOISE LEVELS**

Nighttime construction would only occur under the CDSM option and a hydraulic backhoe would not be used concurrently with CDSM. Activities would not occur at the stockpiles or along haul routes during nighttime hours.

### **CDSM Option**

Earth Moving Equipment - Maximum 85 dBA

Grout Batching - Maximum 85 dBA

### **Stationary Equipment**

Combination of 2 CDSM Rigs, Pump, and Generator 82 dBA

**Using the Noise Calculator- Combined Noise Level is 89 dBA.**

## **MAXIMUM NIGHTTIME NOISE LEVEL AT NEAREST SENSITIVE RECEPTOR TO DAM**

The nearest residence was measured at 1,500 feet from Chabot Dam.

Using the inverse law, the noise level would be reduced by 29.5 dBA because of the distance from the dam.

$$L_2 = 89 - 20 \log (1,500/50) = 60 \text{ dBA} - \text{Maximum Noise Level}$$

The nearest residence is within 1,500 feet of the dam excavation area; the maximum noise level from construction activities would attenuate to 60 dBA at this residence. A natural noise attenuation factor is the presence of mature trees, vegetation, and topography that would shield many receptors from line-of-sight noise transmission generated by construction activities. This noise level at the nearest residence would be further reduced by an estimated 3 dBA to about 57 dBA because of the elevation difference between the residences and dam excavation area (150 feet) and the attenuation provided by trees and vegetation.

The maximum nighttime noise level from the dam to the nearest receptor would be 57 dBA. As a mitigation measure, additional noise reductions would be achieved through engine control and noise control procedures that would further reduce the noise levels to **51 dBA**.

# **APPENDIX I**

---

## Hazardous Materials Assessment



---

*Technical Report*

*Chabot Dam Seismic Upgrade*  
**Hazardous Materials  
Assessment**

Prepared for  
East Bay Municipal Utility District  
Engineering & Construction Department

April 2013

Prepared by  
Ninyo & Moore  
Geotechnical and Environmental Sciences Consultants  
1956 Webster Street, Suite 400  
Oakland, California 94501

In association with

**AECOM**

# Contents

| Section                                     | Page |
|---|------|
| Contents.....                               | i    |
| Acronyms and Abbreviations.....             | iii  |
| 1 Introduction.....                         | 1-1  |
| 1.1 Purpose and Scope of Investigation..... | 1-1  |
| 1.2 Limitations.....                        | 1-4  |
| 2 Environmental Setting .....               | 2-1  |
| 2.1 Overview .....                          | 2-1  |
| 2.2 Proposed Project Components .....       | 2-1  |
| 2.2.1 Cement Deep Soil Mixing .....         | 2-1  |
| 2.2.2 Conventional Earthwork.....           | 2-1  |
| 2.2.3 Upper Haul Route.....                 | 2-1  |
| 2.2.4 Lower Haul Route.....                 | 2-1  |
| 2.2.5 Filter Pond Stockpile.....            | 2-2  |
| 2.2.6 Park Stockpile.....                   | 2-2  |
| 2.2.7 Outlet Works.....                     | 2-2  |
| 2.3 Regional Conditions.....                | 2-2  |
| 2.3.1 Project Vicinity Topography.....      | 2-2  |
| 2.3.2 Project Vicinity Geology .....        | 2-2  |
| 2.3.3 Project Vicinity Groundwater.....     | 2-3  |
| 3 Historical Information.....               | 3-1  |
| 3.1 Sanborn Fire Insurance Maps.....        | 3-1  |
| 3.2 Aerial Photographs .....                | 3-1  |
| 3.3 Topographic Maps .....                  | 3-2  |
| 3.4 Oil and Gas Maps.....                   | 3-3  |
| 3.5 City Directories.....                   | 3-3  |
| 3.6 Interviews and Correspondence .....     | 3-3  |
| 3.7 Previous Reports .....                  | 3-3  |
| 4 Environmental Database Review.....        | 4-1  |
| 4.1 Federal Databases.....                  | 4-3  |
| 4.2 State Databases.....                    | 4-4  |
| 4.3 Non-ASTM Databases.....                 | 4-4  |

|     |   |      |
|-----|---|------|
| 5   | Site Reconnaissance.....  | 5-1  |
| 5.1 | Cement Deep Soil Mixing.....  | 5-1  |
| 5.2 | Conventional Earthwork.....   | 5-1  |
| 5.3 | Upper Haul Route.....   | 5-1  |
| 5.4 | Lower Haul Route.....   | 5-1  |
| 5.5 | Filter Pond Stockpile.....  | 5-2  |
| 5.6 | Park Stockpile.....   | 5-2  |
| 5.7 | Outlet Works.....   | 5-3  |
| 6   | Specific Environmental Concerns.....  | 6-1  |
| 7   | Non-Specific Environmental Concerns.....  | 7-1  |
| 8   | Potential Hazardous Materials Impacts and Mitigation Measures.....              | 8-1  |
| 8.1 | Proposed Project-Wide Hazardous Materials Impacts and Mitigation Measures.....  | 8-1  |
| 8.2 | CDSM Hazardous Materials Impacts and Mitigation Measures.....                   | 8-2  |
| 8.3 | Conventional Earthwork Hazardous Materials Impacts and Mitigation Measures..... | 8-2  |
| 8.4 | Upper Haul Route Hazardous Materials Impacts and Mitigation Measures.....       | 8-2  |
| 8.5 | Lower Haul Route Hazardous Materials Impacts and Mitigation Measures.....       | 8-2  |
| 8.6 | Filter Pond Stockpile Hazardous Materials Impacts and Mitigation Measures.....  | 8-2  |
| 8.7 | Park Stockpile Hazardous Materials Impacts and Mitigation Measures.....         | 8-3  |
| 8.8 | Outlet Works Hazardous Materials Impacts and Mitigation Measures.....           | 8-3  |
| 9   | References.....   | 9-1  |
| 10  | List of Preparers.....  | 10-1 |

### Tables

|     |  |
|-----|--|
| 4-1 | Environmental Database Search              |
| 5-1 | Site Reconnaissance Observations           |
| 6-1 | Identified Specific Environmental Concerns |

### Figures

|     |               |
|-----|---------------|
| 1-1 | Site Location |
| 2-2 | Site Plan     |

### Appendices

|   |  |
|---|--|
| A | Historical Research Documentation          |
| B | EDR Radius Map Report with GeoCheck Report |
| C | Project Area Photographs                   |

# Acronyms and Abbreviations

---

|                   |   |
|-------------------|---|
| AAI               | All Appropriate Inquiries   |
| ADMP              | Asbestos Dust Mitigation Plan   |
| Alameda County CS | Alameda County Contaminated Sites database  |
| AST               | Aboveground Storage Tank  |
| ATCM              | Asbestos Airborne Toxic Control Measure   |
| AWP               | Annual Workplan Properties  |
| BAAQMD            | Bay Area Air Quality Management District  |
| CA FID            | California Facility Inventory Database  |
| Cal/EPA           | California Environmental Protection Agency  |
| CDSM              | Cement Deep Soil Mixing   |
| CERCLA            | Comprehensive Environmental Response, Compensation and Liability Act                  |
| CERCLIS           | Comprehensive Environmental Response, Compensation, and Liability Information System  |
| CESQG             | Conditionally Exempt Small Quantity Generators  |
| CHMIRS            | California Hazardous Materials Information Reporting System                           |
| CORRACTS          | Corrective Action Report  |
| CORTESE           | “Cortese” Hazardous Waste & Substances Sites List                                     |
| DOGGR             | California Department of Conservation, Division of Oil, Gas, and Geothermal Resources |
| DTSC              | Department of Toxic Substances Control  |
| EBMUD             | East Bay Municipal Utility District   |
| EBRPD             | East Bay Regional Park District   |
| EDR               | Environmental Data Resources, Inc.  |
| EIR               | Environmental Impact Report   |
| EPA               | U.S. Environmental Protection Agency  |
| ERNS              | Emergency Response Notification System  |
| HAZNET            | Facility and Manifest Data  |
| HCP               | Hazard Communication Program  |
| HMA               | Hazardous Materials Assessment  |
| HMI               | Hazardous Materials Impacts   |
| IIPP              | Injury and Illness Prevention Program   |
| IWMB              | Integrated Waste Management Board   |
| kg                | kilograms   |

---

|            |   |
|------------|---|
| LQG        | Large Quantity Generator  |
| LUST       | leaking underground storage tank                                  |
| MSL        | mean sea level  |
| NFA        | No Further Action   |
| NFRAP      | No Further Remedial Action Planned                                |
| NOA        | naturally occurring asbestos                                      |
| NPL        | National Priorities List  |
| PCBs       | polychlorinated biphenyls   |
| RCRA       | Resource Conservation and Recovery Act                            |
| RWQCB      | Regional Water Quality Control Board                              |
| SLIC       | Spills, Leaks, Investigations, and Cleanups Program               |
| SQG        | Small Quantity Generators   |
| SWEEPS     | Statewide Environmental Evaluation and Planning System            |
| SWF/LF     | Solid Waste Facility/Landfill                                     |
| SWIS       | Solid Waste Information System                                    |
| SWRCB      | State Water Resources Control Board                               |
| TSD        | Treatment, Storage, and Disposal                                  |
| USGS       | U.S. Geological Survey  |
| UST        | underground storage tank  |
| VCP        | Voluntary Cleanup Program   |
| WMUDS/SWAT | Waste Management Unit Database System/Solid Waste Assessment Test |

# 1 Introduction

East Bay Municipal Utility District (EBMUD) authorized Ninyo & Moore (in association with AECOM) to perform this Hazardous Materials Assessment (HMA) for incorporation into the Environmental Impact Report (EIR) for the Chabot Dam Seismic Upgrade Project (proposed project) in the City of Oakland, City of San Leandro, and unincorporated Alameda County (Castro Valley), California.

The HMA was performed to identify contaminated and potentially contaminated areas and other hazardous materials issues in the project area. The project area extends from Lake Chabot and Lake Chabot Park in the north to Lake Chabot Road in the south, and from Estudillo Avenue in the west to Lake Chabot Road in the east (Figures 1 and 2).


The proposed project would include: improving embankment soils on the downstream side of Chabot Dam, to help them withstand shaking generated by maximum credible earthquake on the Hayward Fault without significant strength loss; helping limit permanent deformation or settlement at the dam crest, to acceptable levels; and helping prevent damage to the Outlet Works from design level earthquake—while continuing reservoir and Outlet Works operation during project construction. Embankment soils improvement would be performed by either Cement Deep Soil Mixing (CDSM) or conventional earthwork. Both options would require transportation of excavated soil by either the Upper Haul Route or the Lower Haul Route, to the Filter Pond Stockpile and/or the Park Stockpile. The Outlet Works upgrade would consist of pavilion demolition, relining or replacement of pipes, valve installation, and filling the outlet tower with low-strength flowable fill or concrete.

## 1.1 Purpose and Scope of Investigation

The purpose of the HMA was to evaluate the likelihood that hazardous materials may be present in soil or groundwater beneath the project area as a result of past activities. The likelihood of specific locations in the project area having been contaminated by hazardous materials was ranked according to the following categories:


**High:** property with known or probable contamination in the project area (e.g., a leaking underground storage tank [UST] where remediation has not been started or is not yet finished).

**Moderate:** property with potential or suspected contamination in the project area (e.g., a leaking UST in the final stages of remediation or in post-remediation monitoring; a property with known use for storage of hazardous materials that has received violation notices from inspecting agency or where visual evidence of inadequate chemical and storage practices—such as significant staining—has been observed but where no environmental assessments have occurred; and facilities where USTs are likely to be present and/or facilities that have used significant quantities of hazardous materials, but appear to be abandoned by their former operators).



Source: Thomas Guide 2008, AECOM 2013

Figure 1-1 Site Location



Source: AECOM 2013, Terra Engineers 2013, EBMUD 2013

Figure 1-2 Site Plan



Low: property that is used for or stores hazardous materials but has no significant violations, known releases, or evidence of inadequate chemical handling practices (e.g., USTs or dry cleaning facilities with no documented releases or locations where remediation of previous releases have been completed).

Ninyo & Moore was retained to conduct the HMA, with the data to be incorporated into the EIR for the project area that is outlined in Figure 1-1, to identify locations where unauthorized releases of hazardous materials have occurred. The scope of the HMA included but was not limited to the following tasks:

- reviewing lease records, maps and environmental reports of the project area, if provided by EBMUD, to evaluate probable past uses and their possible impacts on existing environmental conditions;
- conducting interviews with property representatives regarding the environmental status of the project area;
- performing a site reconnaissance to visually identify locations of possibly contaminated surficial soil or surface water, improperly stored hazardous materials, possible sources of polychlorinated biphenyls (PCB), and possible risks of contamination from past activities in the project area and adjacent properties;
- reviewing readily available local regulatory agency files for the project area (requests were made to the County Department of Health Services, the local Air Pollution Control District, and the local Fire and Building Departments);
- reviewing available regulatory agency databases for the project area and properties located within a specified radius of the project area (the purpose of this review was to evaluate possible environmental impacts to the project area through database identification of locations of known hazardous waste sites, landfills, and leaking USTs, permitted facilities that utilize USTs, and facilities that use, store, or dispose hazardous materials);
- reviewing readily available historical documents, including aerial photographs of the project area and adjacent properties, Sanborn Insurance maps, Building Department records (project area only), and reverse city directories, as appropriate; and
- preparing a draft and a final HMA report (with color photographs), documenting findings and providing opinions and recommendations regarding possible environmental impacts in the project area.

In general accordance with applicable sections of ASTM International (ASTM) E 1527-05, the following items (which are out-of-scope items with respect to the HMA) are not addressed: radon, lead in drinking water, wetlands, regulatory compliance, cultural and historic risk, industrial hygiene, health and safety, ecological resources, endangered species, indoor air quality, and high-voltage power lines.

## 1.2 Limitations

This HMA has been prepared for use by EBMUD. The information presented in this report is based on the project scope of the HMA (described in Section 1.1). Ninyo & Moore has relied on information provided by others in the description of historical conditions and review of regulatory databases and files. Ninyo & Moore makes no warranties or guarantees regarding the accuracy or completeness of the information provided or compiled by others. Ninyo & Moore observed the interior and exterior of

the properties during tours provided by site contacts. Ninyo & Moore conducted interviews with individual tenants in the project area.

No HMA can completely eliminate uncertainty regarding the potential for hazardous materials conditions in connection with a property. Performance of the HMA is intended to reduce, but cannot eliminate, uncertainty regarding the presence of hazardous materials conditions. The available data do not provide definitive information relative to past uses, operations, or incidents in the project area or adjacent properties. Existence of contamination in the project area that was not identified during the HMA is possible and cannot be adequately assessed without additional research beyond the scope of the HMA as discussed in this technical report document. Further evaluation of these types of risks could include subsurface exploration, sampling, and/or other forms of testing.

In addition, some substances may be present in the project area or project vicinity, in quantities below those categorized as actionable by existing environmental regulations. Ninyo & Moore cannot be responsible if regulatory standards are changed in the future in a manner that renders the existing project area conditions actionable.

The objective of the HMA was to evaluate whether hazardous materials or other adverse environmental conditions are present because of past or ongoing use of the project area and/or facilities in the project vicinity. The scope of investigation for the HMA is generally consistent with applicable sections of ASTM 2005 guidance (Designation Number E1527-05) and U.S. Environmental Protection Agency (EPA) Standards and Practices for All Appropriate Inquiries (AAI). However, because ASTM and AAI standards were established to provide innocent landowner liability protection under the Comprehensive Environmental Response, Compensation, and Liability Act for the purchaser of a property, and because the proposed project would not involve a purchase transaction, the applicability of the ASTM/AAI standards is limited.

## 2 Environmental Setting

This section provides descriptions of land uses in the project area as well as regional topographic, geologic, and hydrogeologic conditions. It specifically discusses these components of the proposed project: CDSM, Conventional Earthwork, Upper Haul Route, Lower Haul Route, Filter Pond Stockpile, Park Stockpile, and Outlet Works.

### 2.1 Overview

The project area covers approximately 92 acres in the City of Oakland, City of San Leandro, and unincorporated Alameda County (Castro Valley), California (Figure 1-1). Portions of the project area are in the East Bay Regional Park District's (EBRPD) Lake Chabot Regional Park, the City of San Leandro Chabot Park, Lake Chabot, and on EBMUD property. The project area extends from Lake Chabot Road in the south and east to Estudillo Avenue in the west.

### 2.2 Proposed Project Components

#### 2.2.1 Cement Deep Soil Mixing

CDSM would occur on approximately 70,000 square feet of the project area, at a location on the downstream slope of Chabot Dam (Figure 1-2). This area is bound to the north by Chabot Dam crest and the Upper Haul Route, to the west by Chabot Dam spillway, to the east by vacant land, and to the south by vacant land and the Lower Haul Route. The area includes fill material that makes up the downstream slope of Chabot Dam. No structures were observed in this location.

#### 2.2.2 Conventional Earthwork

Conventional earthwork would occur on approximately 141,000 square feet of the project area, at a location on the downstream slope of Chabot Dam (Figure 1-2). This area is bound to the north by Chabot Dam crest and the Upper Haul Route, to the west by the Chabot Dam spillway, to the east by vacant land, and to the south by vacant land and the Lower Haul Route. The area includes fill material that makes up the downstream slope of Chabot Dam. No structures were observed in this location.

#### 2.2.3 Upper Haul Route

The Upper Haul Route is approximately 4,740 feet long and approximately 10 to 16 feet wide. The Upper Haul Route begins at the east side of the Chabot Dam crest and ends at the Filter Pond Stockpile (Figure 1-2). The Upper Haul Route is paved with asphalt west of the eastern side of the Chabot Dam crest. East of the eastern side of the Chabot Dam crest, the Upper Haul Route is an unpaved dirt road. No structures were observed on the Upper Haul Route.

#### 2.2.4 Lower Haul Route

The Lower Haul Route is approximately 2,380 feet long and approximately 15 to 25 feet wide. The Lower Haul Route begins at the downstream toe of Chabot Dam and ends at the Park Stockpile (Figure 1-2). The Lower Haul Route is unpaved and is bordered by vegetation. It crosses San Leandro

Creek approximately 600 feet from its starting point. No structures were observed on the Lower Haul Route.

### 2.2.5 Filter Pond Stockpile

The Filter Pond Stockpile would be located on approximately 64,000 square feet of EBMUD property, on the northwestern portion of the project area (Figure 1-2). The location of the Filter Pond Stockpile is bound to the northwest and northeast by the Upper Haul Route and to the south by vacant land beyond which is the Lower Haul Route. The Filter Pond Stockpile location includes a pair of vacant meadows that are bordered by vegetation. No structures were observed at the Filter Pond Stockpile location.

### 2.2.6 Park Stockpile

The Park Stockpile would be located on approximately 105,000 square feet of EBMUD property, leased to and operated by the City of San Leandro as Chabot Park on the western portion of the project area (Figure 1-2). The location of the Park Stockpile is bound to the northwest and northeast by the Lower Haul Route and to the south by vacant land beyond which is the project area boundary. The Park Stockpile location is within Chabot Park, and observed features included a paved access road, a power pole and pole-mounted transformer, unpaved parking areas, picnic areas, and a swing set.

### 2.2.7 Outlet Works

The Outlet Works are located at the EBMUD-owned appurtenant facilities on the northeastern portion of the project area (Figure 1-2). The Outlet Works location is bound to the east by Lake Chabot, to the north by vacant land, and to the south and west by vacant land beyond which is the Upper Haul Route. The Outlet Works consists of an approximately 48-foot-tall stone masonry tower, capped by a 13-foot-high reinforced concrete pavilion. The tower houses an 8-foot diameter, brick-lined outlet shaft that passes water from Lake Chabot into the 36-inch-diameter water line in Tunnel No. 2.

## 2.3 Regional Conditions

The following discussion includes topographic, geologic, and groundwater conditions in the project vicinity, based on the document review and visual observations of the project area and adjacent property.

### 2.3.1 Project Vicinity Topography

Based on a review of the U.S. Geological Survey (USGS) 7.5-Minute Topographic Quadrangle Maps Series of Hayward, 1993, and San Leandro, 1993, elevation in the project vicinity varies from approximately 150 to 350 feet above mean sea level (MSL) (USGS 1993). The topography is hilly and gently slopes towards Lake Chabot to the north and San Leandro Creek to the southwest.

### 2.3.2 Project Vicinity Geology

The project area is located within the Coast Ranges Geomorphic province. The Coast Ranges are northwest trending and are underlain by marine and non-marine sedimentary rocks. These sedimentary units are underlain by either the Mesozoic Franciscan Formation (metamorphosed

seafloor deposits) or the granitic Salinian Block. The Oakland area is situated on a broad, alluvial plain that slopes gently west from hills to San Francisco Bay. The alluvial plain is comprised of alluvial sediments, derived from erosion of the hills to the east.

Examination of the Geologic Map of the Hayward Quadrangle, Contra Costa and Alameda Counties revealed outcrops of Franciscan Formation rock in the project area (Dibblee 2005). Franciscan Formation rock is associated with naturally occurring asbestos (NOA). Based on the presence of Franciscan Formation rock in the project area, potential exists for its soil to have been affected by NOA, which represents a potential environmental concern for the proposed project.

### 2.3.3 Project Vicinity Groundwater

Project vicinity groundwater depth was obtained from the Summary of August 2011 Field Investigation Program Memo, Chabot Dam Remediation Concept Project (URS2011). According to this memo, the groundwater elevation ranges from 128 to 175 feet above MSL. Groundwater flow direction was not included, but it can be assumed to generally follow topography to the north towards Lake Chabot or to the southwest towards San Leandro Creek.

## 3 Historical Information

The following discussion summarizes the results of the review of historical resources, including Sanborn Fire Insurance Rate maps, aerial photographs, topographic maps, oil and gas maps, and historical city directories, as provided in Environmental Data Resources, Inc. (EDR).

### 3.1 Sanborn Fire Insurance Maps

According to EDR, Sanborn Fire Insurance maps do not exist for the project area. A copy of the Sanborn Fire Insurance Rate Map Report is provided in Appendix A (EDR 2012b).

### 3.2 Aerial Photographs

Aerial photographs have been collected in some areas for the continental United States since the 1920s, with variable coverage and frequency (generally based on an area's importance to national defense). Aerial photographs offer an opportunity for direct observation of conditions across a period of time. These observations may include the locations of tank pits, drums, pits, ponds, lagoons, stained/stressed vegetation, or other development features that can indicate potential contaminant sources.

Aerial photographs of the project area were provided by EDR (EDR2012c). For the HMA, Ninyo & Moore reviewed aerial photographs taken in 1939, 1946, 1958, 1965, 1975, 1982, 1993, 1998, and 2005. These photographs varied in scale and clarity, and were taken from various altitudes. A copy of the EDR Aerial Photo Decade Package is provided in Appendix A.

The aerial photograph review served to verify information gained from other sources and, in some cases, served as the primary source of information. Information gathered from aerial photography is summarized below. Because the project area is quite large, the descriptions include limited data in the interest of brevity, focusing on notable features in locations of potential concern as revealed by regulatory data or the site reconnaissance. Historical features of potential environmental concern that were noted but were not revealed by other sources are described.

**1939 Aerial Photograph:** This is the earliest aerial photograph available. Most of the project area consists of undeveloped, grassy fields and forested hillsides. Visible features include the southwest portion of Lake Chabot, Chabot Dam, the old spillway, and the Outlet Works on the southwest edge of Lake Chabot. Other visible features include the Filter Ponds, apparently in use and filled with water. Numerous unpaved roads crisscross the project area.

**1946 Aerial Photograph:** The project area appears much the same as it did in the 1939 photograph. The northernmost Filter Pond has dried up.

**1958 Aerial Photograph:** The project area appears much the same as it did in the 1939 and 1946 photographs.

**1965 Aerial Photograph:** The project area appears similar to the previous photographs.

**1975 Aerial Photograph:** This photograph is very grainy; smaller on-site features such as the reservoir tower are not observable. The project area appears similar to the previous photographs.

1982 Aerial Photograph: This photograph also is very grainy. The dam, roads, and the southern-most Filter Pond, with cover, are the only observable human-made features. A new spillway can be seen, located west of Chabot Dam.

1993 Aerial Photograph: The project area appears similar to the 1982 photograph.

1998 Aerial Photograph: This photograph is grainy. The southern-most Filter Pond appears to be uncovered and dry. Otherwise, the project area appears similar to the 1993 photograph.

2005 Aerial Photograph: The two former Filter Ponds appear as open, grassy areas. No other obvious changes are notable in this photograph.

Based on information provided by Richard Kanazawa of EBMUD, clean fill was placed on the Filter Ponds in 2003. Because the fill placed on the Filter Pond Stockpile portion of the proposed project was classified as clean fill by EBMUD, it does not represent a potential environmental concern.

Based on the review of aerial photographs, no specific locations of concern were revealed in the project area.

### 3.3 Topographic Maps

Ninyo & Moore obtained historical topographic maps from EDR, for 1899, 1915, 1947, 1948, 1950, 1959, 1968, 1973, 1980, and 1993 (EDR 2012d). USGS 7.5 Minute Series maps for Hayward and San Leandro included the project area. A copy of the EDR Historical Topographic Map Report is provided in Appendix A. The following are brief descriptions of the project area, based on a review of the individual historical topographic maps.

1899 Topographic Map: This is the earliest topographic map available. Chabot Dam is shown on this map. The scale of the map is too large to identify smaller details.

1915 Topographic Map: The project area appears similar to the 1899 topographic map.

1947 Topographic Map: The project area appears developed with Chabot Dam. The elevation of the spillway is listed as 235 feet above MSL.

1948 Topographic Map: The northwestern portion of the project area (Filter Pond Stockpile) is labeled "Chabot Filtration Plant." Otherwise, the project area appears similar to the 1947 topographic map.

1950 Topographic Map: The project area appears similar to the 1948 topographic map.

1959 Topographic Map: The project area appears similar to the 1950 topographic map. The western portion of the project area is labeled "Lake Chabot Park."

1968 Topographic Map: The project area appears similar to the 1959 topographic map.

1973 Topographic Map: The project area appears similar to the 1968 topographic map.

1980 Topographic Map: The project area appears similar to the 1973 topographic map.

1993 Topographic Map: The spillway is shown on the map, west of Chabot Dam. The project area appears similar to the 1980 topographic map.

Based on the review of topographic maps, no specific locations of concern were revealed in the project area.

### 3.4 Oil and Gas Maps

According to the California Department of Conservation, Division of Oil, Gas, and Geothermal Resources (DOGGR), Online Mapping System (DOGGR 2012), the project area does not lie within the administrative boundaries of an oil field. No oil or gas wells are located in the project area.

### 3.5 City Directories

EDR provided a historical city directory report for the project area and project vicinity (EDR 2012e). City directories were searched from 1920 through 2012; no listings were found for the project area. A copy of the EDR-City Directory Abstract is provided in Appendix A.

### 3.6 Interviews and Correspondence

Ninyo & Moore interviewed and/or corresponded by phone/e-mail with the following contacts regarding the proposed project:

- Alameda County: Rosanna Garcia, Environmental Health Department
- Bay Area Air Quality Management District: Rochelle Reed, Public Records Section
- California Environmental Protection Agency: Department of Toxic Substances Control
- City of Oakland: Celestina Pacheco, Fire Prevention Bureau, Hazardous Materials
- City of San Leandro: Gail Chino, Environmental Services Section
- East Bay Municipal Utility District: Bill Maggiore, Richard Kanazawa, John Schroeter, and John Walter
- San Francisco Bay Regional Water Quality Control Board: Melinda Wong, Public Records

Results of the interviews and correspondence revealed no environmental concerns, with the exception of the potential presence of NOA (discussed in Section 2.3.2) as well as the potential presence of asbestos containing materials and lead-based paint in the Outlet Works (discussed in Section 5.7).

### 3.7 Previous Reports

Previous reports regarding environmental concerns were not provided by EBMUD to Ninyo & Moore or AECOM.



## 4 Environmental Database Review

Ninyo & Moore reviewed the EDR Radius Map Report with GeoCheck Report for Lake Chabot Dam; this report is based on an environmental information database search completed by EDR on November 1, 2012, that included federal, state, and local databases (EDR 2012a). This section discusses the databases that contain noted locations of environmental concern and includes the regulatory status of project area facilities and potential environmental impacts of the proposed project. A copy of the EDR Radius Map Report with GeoCheck Report for Lake Chabot Dam is provided in Appendix B.

Groundwater elevation ranged from 128 to 175 feet above MSL (URS 2011). Groundwater flow direction was not reported, but can be assumed to generally follow topography to the north towards Lake Chabot or to the southwest towards San Leandro Creek.

The EDR report also included a list of "orphan sites" that could not be mapped by the addresses included in the file. Ninyo & Moore reviewed this list and found that 1 of the 22 "orphan sites" is a facility located in or adjacent to the project area. This facility is included in the HMA and has been verified by other investigative means (site reconnaissance and historical data review).

Table 4-1 shows the number of facilities within the specified search radii of the project area that are listed in EDR's environmental database search.

**Table 4-1: Environmental Database Search**

| Database(s)   | Description  | Facilities Listed* |
|---|--|--------------------|
| <i>Federal Databases</i>                            |  |                    |
| NPL   | The NPL is the EPA's database of uncontrolled or abandoned hazardous waste facilities that have been listed for priority remedial actions under the Superfund Program. Updated quarterly.  | 0                  |
| CERCLIS/<br>NFRAP                                   | The CERCLIS database is a compilation of facilities that EPA has investigated or is investigating for a release or threatened release of hazardous substances pursuant to the CERCLA of 1980. NFRAP refers to facilities that have been removed and archived from its inventory of CERCLA sites.         | 0                  |
| Institutional<br>Control/<br>Engineering<br>Control | Superfund sites that have either engineering or institutional controls. The data includes the control and the media contaminated.  | 0                  |
| RCRA<br>CORRACTS/<br>TSD                            | The EPA maintains a database of RCRA facilities associated with TSD of hazardous materials that are undergoing "corrective action." A "corrective action" order is issued when a release of hazardous waste or constituents occurs into the environment from a RCRA facility.                            | 0                  |
| RCRA Non-<br>CORRACTS/<br>TSD                       | The RCRA Non-CORRACTS/TSD Database is a compilation by EPA of facilities that report storage, transportation, treatment, or disposal of hazardous waste. Unlike the RCRA CORRACTS/TSD database, the RCRA Non-CORRACTS/TSD database does not include RCRA facilities where corrective action is required. | 0                  |
| RCRA  | The RCRA Generators database, maintained by EPA, lists facilities that generate  | 0                  |

**Table 4-1: Environmental Database Search**

| Database(s)               | Description  | Facilities Listed* |
|---------------------------|--|--------------------|
| Generators                | hazardous waste as part of their normal business practices. Generators are listed as large, small, or conditionally exempt. LQGs produce at least 1,000 kg/month of non-acutely hazardous waste or 1 kg/month of acutely hazardous waste. SQGs produce 100 to 1,000 kg/month of non-acutely hazardous waste. CESQGs are those that generate less than 100 kg/month of non-acutely hazardous waste. |                    |
| ERNS                      | ERNS records and stores information on reported releases of oil and hazardous substances.  | 0                  |
| <i>State Databases</i>    |  |                    |
| Response                  | The Cal Sites database is maintained by Cal/EPA, DTSC. This database contains information on AWP and both known and potentially contaminated properties. Two-thirds of these properties have been classified, based on available information, as needing NFA by DTSC. The remaining properties are in various stages of review and remediation to determine whether a problem exists.              | 0                  |
| EnviroStor                | Identifies confirmed release sites where DTSC is involved in remediation, either in a lead or oversight capacity. These confirmed release sites are generally high priority and high potential risk.   | 0                  |
| SWF/LF                    | The SWF/LF database consists of open and closed solid waste disposal facilities and transfer stations. The data comes from the IWMB's SWIS database.   | 0                  |
| LUST                      | Databases of the LUST information system are maintained by SWRCB and RWQCB.  | 1                  |
| UST/AST                   | The UST Information System and AST database are maintained by SWRCB, which may include the owner and location of the USTs/ASTs.  | 0                  |
| VCP                       | The VCP database is a Cal/EPA listing of properties involved in the voluntary remediation program.   | 0                  |
| Brownfields               | This database is a DTSC tracking system of California Brownfields sites.   | 0                  |
| Indian Reservation        | USGS map layer portrays Native American-administered land within the U.S. with an area equal to or greater than 640 acres.   | 0                  |
| Indian LUST               | This is a database maintained by EPA for LUSTs on Native American land in Arizona, California, New Mexico, and Nevada.   | 0                  |
| Indian UST                | This is a database maintained by EPA for USTs on Native American land.   | 0                  |
| <i>Non-ASTM Databases</i> |  |                    |
| Alameda County CS         | This is a listing of contaminated sites overseen by the Toxic Release Program and LUST Program.  | 1                  |
| HAZNET                    | The HAZNET database contains facility and manifest data.   | 1                  |
| Hist UST                  | The Hist UST database lists historical registered USTs.  | 1                  |
| SLIC                      | The SLIC database is maintained by RWQCB.  | 0                  |
| CA FID USTs               | The FID UST contains active and inactive UST locations and is maintained by SWRCB.   | 1                  |
| SWEEPS USTs               | This UST listing was updated and maintained by a company contracted by SWRCB in the early 1990s. The listing is no longer updated or maintained.   | 1                  |

**Table 4-1: Environmental Database Search**

| Database(s)   | Description   | Facilities Listed* |
|---|---|--------------------|
| CHMIRS  | The CHMIRS contains information on hazardous materials reporting.   | 0                  |
| WMUDS/<br>SWAT  | The WMUDS/SWAT is used for program tracking and inventory of waste management units. The system is maintained by SWRCB.                   | 0                  |
| Hist<br>CORTESE   | The Hist CORTESE database is designated by SWRCB LUST, IWB SWF/LF, and DTSC sites. This listing is no longer updated by the state agency. | 1                  |
| <p>Notes:</p> <p>Alameda County CS – Alameda County Contaminated Sites<br/> AST – Aboveground Storage Tank<br/> AWP – Annual Workplan Properties<br/> CA FID – California Facility Inventory Database<br/> Cal/EPA – California Environmental Protection Agency<br/> CERCLA – Comprehensive Environmental Response, Compensation and Liability Act<br/> CERCLIS – Comprehensive Environmental Response, Compensation, and Liability Information System<br/> CESQG – Conditionally Exempt Small Quantity Generators<br/> CHMIRS – California Hazardous Materials Information Reporting System<br/> CORRACTS – Corrective Action Report<br/> CORTESE – “Cortese” Hazardous Waste &amp; Substances Sites List<br/> DTSC – Department of Toxic Substances Control<br/> EPA – United States Environmental Protection Agency<br/> ERNS – Emergency Response Notification System<br/> HAZNET – Facility and Manifest Data<br/> IWMB – Integrated Waste Management Board<br/> kg – kilograms<br/> LQG – Large Quantity Generator<br/> LUST – Leaking Underground Storage Tanks<br/> NFA – No Further Action<br/> NFRAP – No Further Remedial Action Planned<br/> NPL – National Priorities List<br/> RCRA – Resource Conservation and the Recovery Act<br/> RWQCB – Regional Water Quality Control Board<br/> SLIC – Spills, Leaks, Investigations, and Cleanups Program<br/> SQG – Small Quantity Generators<br/> SWEEPS – Statewide Environmental Evaluation and Planning System<br/> SWF/LF – Solid Waste Facility/Landfill<br/> SWIS – Solid Waste Information System<br/> SWRCB – State Water Resources Control Board<br/> TSD – Treatment, Storage, and Disposal<br/> USGS – United States Geological Survey<br/> UST – Underground Storage Tank<br/> VCP – Voluntary Cleanup Program<br/> WMUDS/SWAT – Waste Management Unit Database System/Solid Waste Assessment Test</p> <p>*Some facilities have multiple listings under a single database.<br/> Source: Data compiled by Ninyo &amp; Moore in 2013</p> |   |                    |

## 4.1 Federal Databases

Facilities in the project area and search radius are not listed in the federal databases.

## 4.2 State Databases

Facilities in the project area are not listed in the Leaking Underground Storage Tank (LUST) database. M&K ARCO #1 at 1401 Grand Avenue in San Leandro, approximately 0.43 miles west and downgradient from the project area, was listed in the database as an open case impacting groundwater. Based on the distance and direction relative to groundwater flow from the project area, the facility is not considered to be an environmental concern for the proposed project.

Facilities in the project area and search radius are not listed in the remaining state databases.

## 4.3 Non-ASTM Databases

One facility is listed in the Non-ASTM database as being in the project area. The facility, the EBMUD Chabot Filter Plant, is listed in the HAZNET database and is located at the end of East Estudillo Avenue. Furthermore, the facility is located within the proposed Filter Pond Stockpile location in the project area. The facility is listed in the database for transportation of approximately 44 tons of contaminated soil from cleanup of a release of unknown origin, extent, or material. Mr. John Walter of EBMUD was contacted regarding this database listing, but Mr. Walter had no additional information relating to the release at the Chabot Filter Plant. The release represents a potential environmental concern. Facilities within the search radius were not listed in the HAZNET database.

Facilities in the project area are not listed in the Alameda County Contaminated Sites (CS) and Hist Cortese databases. One facility within the search radius is listed in the Alameda County CS and Hist Cortese databases—M&K ARCO #1 at 1401 Grand Avenue in San Leandro, approximately 0.43 miles west and crossgradient from the project area. This is the same facility that is listed in the LUST database (discussed in Section 4.2). Based on the distance and direction relative to groundwater flow from the project area, the facility is not considered to be an environmental concern.

Facilities in the project area are not listed in the California Facility Inventory Database (CA FID) UST, Hist UST, and Statewide Environmental Evaluation and Planning System (SWEEPS) UST databases. One facility within the search radius is listed in the CA FID UST, Hist UST, and SWEEPS UST databases as Lake Chabot Road Quarry at 13575 Lake Chabot Road in San Leandro, approximately 0.03 mile east-southeast and crossgradient from the project area. Four gasoline USTs at the facility are listed as inactive. No violations are recorded in the databases, and the facility is not associated with a LUST case. Based on the status of the facility, the facility is not considered to be an environmental concern.

Facilities in the project area and search radius are not listed in the remaining Non-ASTM databases.

## 5 Site Reconnaissance

A site reconnaissance was conducted by Ninyo & Moore on October 29, 2012, with AECOM and EBMUD representatives, to provide specific, current information about the project area that was not obtainable through an environmental records review or historical information review. Photographs of the project area are provided in Appendix C.

During the site reconnaissance, Ninyo & Moore looked for several indicators of potential environmental impacts in the project area, including but not limited to significant staining or degraded pavement, USTs, ASTs, storage of hazardous materials and wastes, groundwater monitoring wells and remediation systems, transformers, pesticide use, industrial facilities, existing or historic fuel stations, stressed vegetation, and the presence of pits, ponds, or lagoons. The presence of features such as ASTs, USTs, or chemical storage areas alone is not sufficient to classify a property as Moderate or High with regard to risk.

Table 5-1 summarizes Ninyo & Moore's observations of the project area. In general, properties were inspected during tours of the facilities, given by EBMUD; interviews with EBMUD staff members also were conducted.

### 5.1 Cement Deep Soil Mixing

Several wells were observed in CDSM locations. These wells are piezometers for monitoring geotechnical conditions of Chabot Dam. The presence of the wells does not represent an environmental concern.

### 5.2 Conventional Earthwork

Several wells were observed in the Conventional Earthwork locations. These wells are piezometers for monitoring geotechnical conditions of Chabot Dam. The presence of the wells does not represent an environmental concern.

### 5.3 Upper Haul Route

Features representing environmental concerns were not observed in the Upper Haul Route during the site reconnaissance.

### 5.4 Lower Haul Route

Features representing environmental concerns were not observed in the Lower Haul Route during the site reconnaissance.

**Table 5-1: Site Reconnaissance Observations**

| Proposed Project Locations  | Existing Project Area Use                    | Chemical Storage Areas | Dumped, Burned Material | Hydraulic Equipment (Lifts) | Electrical Transformers (potentially containing PCBs) | Chemical/Pesticide Mixing Areas | Sumps, Pits, Ponds, Lagoons, Clarifiers | Potentially Lead-Based Paint | Groundwater Monitoring Wells or Other Wells | Remediation Equipment/Evidence or Remediation | Potentially Asbestos Containing Materials | Storage Tanks (underground or aboveground) | Drums | Stressed Vegetation | Discolored/Stained Soils | Degraded/Heavily Stained Pavement |
|---|--|------------------------|-------------------------|-----------------------------|---|---------------------------------|---|------------------------------|---|---|---|--|-------|---------------------|--------------------------|-----------------------------------|
|   |  |                        |                         |                             |   |                                 |   |                              |   |   |   |  |       |                     |                          |                                   |
| CDSM  | Downstream slope of Chabot Dam               | N                      | N                       | N                           | N   | N                               | N                                       | N                            | Y   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Conventional Earthwork  | Downstream slope of Chabot Dam               | N                      | N                       | N                           | N   | N                               | N                                       | N                            | Y   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Upper Haul Route  | Asphalt/concrete paved and unpaved dirt road | N                      | N                       | N                           | N   | N                               | N                                       | N                            | N   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Lower Haul Route  | Asphalt paved and unpaved dirt road          | N                      | N                       | N                           | N   | N                               | N                                       | N                            | N   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Filter Pond Stockpile   | Vacant land                                  | N                      | N                       | N                           | N   | N                               | N                                       | N                            | N   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Park Stockpile  | Chabot Park                                  | N                      | N                       | N                           | Y   | N                               | N                                       | N                            | N   | N   | N   | N  | N     | N                   | N                        | N                                 |
| Outlet Works  | Pavilion, tower, and tunnel                  | N                      | N                       | N                           | N   | N                               | N                                       | N                            | N   | N   | N   | N  | N     | N                   | N                        | N                                 |
| <p>Notes:<br/>                     N – Not observed during reconnaissance<br/>                     Y – Yes, observed during reconnaissance<br/>                     The existence of, for example, tanks or chemical storage areas alone generally is not sufficient to classify a property as Moderate or High with regard to risk. Evidence of a release, such as significant staining, groundwater monitoring wells or remediation equipment, would be cause to classify a property as Moderate or High.<br/>                     Source: Data compiled by Ninyo &amp; Moore in 2013</p> |  |                        |                         |                             |   |                                 |   |                              |   |   |   |  |       |                     |                          |                                   |

## 5.5 Filter Pond Stockpile

Features representing environmental concerns were not observed in the Filter Pond Stockpile location during the site reconnaissance.

## 5.6 Park Stockpile

A pole-mounted transformer was observed on the northern portion of the Park Stockpile location. Historically, PCBs (a group of hazardous substances and suspected human carcinogens) were widely

used as an additive in cooling oils for electrical components. Typical sources of PCBs can include electrical transformers. The use of PCBs in electrical transformers manufactured before 1978 was not regulated by EPA. Electrical transformers manufactured since 1978, which do not contain PCBs, should be stamped to indicate that the product is PCB-free. Ninyo & Moore did not assess the pole-mounted transformer during the site reconnaissance. However, because of the age of the facilities in the project area, the pole-mounted transformer possibly contains PCBs. Therefore, Ninyo & Moore considers the presence of the pole-mounted transformer to be an environmental concern for the proposed project.

## 5.7 Outlet Works

The pavilion and tower observed at the Outlet Works location were painted. Based on the age of these structures (built in 1923), lead-based paint may have been used during the original construction and up to 1978, when the use of lead-based paint was regulated by EPA. Similarly, based on the age of the pavilion and tower structures, tunnel no. 2, and the outlet pipeline, asbestos containing materials may have been used during the original construction. The potential presence of lead-based paint and asbestos containing materials represents an environmental concern for the proposed project.

## 6 Specific Environmental Concerns

Based on the results of Ninyo & Moore's historical research, review of the environmental database, regulatory agency inquiries, and site reconnaissance, project area locations were evaluated and classified as High, Moderate, or Low with regard to the potential for detrimental impacts during project construction activities. Specific locations of High or Moderate risk are presented in Table 6-1. Specific locations that are categorized as High or Moderate risk in Table 6-1 were evaluated based on the information obtained and the likelihood that hazardous materials in them may have an impact on soil and/or groundwater that is likely to be disturbed during project construction.

**Table 6-1: Identified Specific Environmental Concerns**

| Proposed Project Location   | Specific Environmental Concern                         | Reason for Risk Class <sup>1</sup>  | Data Source <sup>2</sup> | Risk Class <sup>3</sup> | Within Project Area | Applicable HMI/Mitigation Measure |
|---|--|---|--------------------------|-------------------------|---------------------|-----------------------------------|
| CDSM  | No specific areas of concern                           | N/A   | N/A                      | N/A                     | N/A                 | HMI-1, HMI-2                      |
| Conventional Earthwork  | No specific areas of concern                           | N/A   | N/A                      | N/A                     | N/A                 | HMI-1, HMI-2                      |
| Upper Haul Route  | No specific areas of concern                           | N/A   | N/A                      | N/A                     | N/A                 | HMI-1, HMI-2                      |
| Lower Haul Route  | No specific areas of concern                           | N/A   | N/A                      | N/A                     | N/A                 | HMI-1, HMI-2                      |
| Filter Pond Stockpile   | HAZNET listing of Chabot Dam Filter Plant              | Lack of specific information regarding the release and subsequent cleanup | D, H                     | M                       | Y                   | HMI-1, HMI-2, HMI-3               |
| Park Stockpile  | Potential presence of PCBs in pole-mounted transformer | Age of construction of Park Stockpile                                     | R, H                     | M                       | Y                   | HMI-1, HMI-2, HMI-4               |
| Outlet Works  | Lead-based paint                                       | Age of construction of Outlet Works                                       | R, H                     | M                       | Y                   | HMI-1, HMI-2, HMI-5               |
|   | Asbestos containing materials                          | Age of construction of Outlet Works                                       | R, H                     | M                       | Y                   | HMI-1, HMI-2, HMI-6               |
| <p>Notes:<br/>           HMI – Hazardous Material Impact<br/>           LUST – Leaking Underground Storage Tank<br/>           N/A – Not Applicable<br/>           Y – Yes<br/> <sup>1</sup>Description of environmental concern/primary reasons for risk class<br/> <sup>2</sup>Indicates primary information sources for listing: R=Reconnaissance, D=Database, H=Historical Documentation, I= Interviews/Correspondence<br/> <sup>3</sup> Risk Class H = high, M = moderate, L = low<br/>           Source: Data compiled by Ninyo &amp; Moore in 2013</p> |  |   |                          |                         |                     |                                   |



## 7 Non-Specific Environmental Concerns

The following are non-specific, widespread concerns in the project area:

Based on the presence of Franciscan Formation rock in the project area, potential exists for its soil to have been affected by NOA.

Project construction activities, including demolition, may encounter or generate hazardous or solid wastes and debris, and may result in exposure of the public and/or the environment to hazardous materials.

## 8 Potential Hazardous Materials Impacts and Mitigation Measures

### 8.1 Proposed Project-Wide Hazardous Materials Impacts and Mitigation Measures

HMI-1: NOA is associated with Franciscan Formation rock that has been determined to be present in the project area. Because of the presence of Franciscan Formation rock, soil in the project area may have been affected by NOA. Project construction activities that disturb soils in the proposed project area, including excavation for CDSM or Conventional Earthwork, soil stockpiling, road construction, and demolition may generate dust that contains NOA, which may result in the exposure of workers, the public, and/or the environment to hazardous materials.

Mitigation Measure HMI-1: Soils to be disturbed in the proposed project area shall be sampled and tested for NOA. If soils to be disturbed in the proposed project area are confirmed to have NOA, project construction activities, including excavation for CDSM or Conventional Earthwork, soil stockpiling, road construction, and demolition, shall be performed under an Asbestos Dust Mitigation Plan (ADMP), in accordance with the Asbestos Airborne Toxic Control Measure (ATCM) as administered by the Bay Area Air Quality Management District (BAAQMD), to reduce public and worker exposure to NOA by employing the best available dust mitigation practices. If soils to be disturbed in the proposed project area are not found to contain NOA, an application for exemption from the ATCM will be submitted to the BAAQMD.

HMI-2: Project construction activities may include the use of hazardous materials (e.g., diesel fuel, oil, lubricants, hydraulic fluid, paints, solvents, cements, and adhesives), may encounter or generate hazardous or solid wastes and debris, and may result in exposure of workers, the public, and/or the environment to hazardous materials.

Mitigation Measure HMI-2 – Implementation of a Hazard Communication Program (HCP) and an Injury and Illness Prevention Program (IIPP) by the construction contractor shall minimize construction worker exposure to hazardous materials. Hazardous waste generated during project construction shall be contained, sampled, and disposed in accordance with all applicable federal, state, and local laws and regulations. With regard to hazardous materials, the licensing and training of personnel, accumulation limits, time limits, reporting, and record keeping shall be regulated by the federal Resource Conservation and Recovery Act (RCRA) and the California Hazardous Waste Control Law.

## 8.2 CDSM Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the CDSM location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

## 8.3 Conventional Earthwork Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Conventional Earthwork location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

## 8.4 Upper Haul Route Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Upper Haul Route location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

## 8.5 Lower Haul Route Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Lower Haul Route location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

## 8.6 Filter Pond Stockpile Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Filter Pond Stockpile location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

In addition, HMI-3 potentially will occur at the Filter Pond Stockpile location.

HMI-3: Project construction activities at the Filter Pond Stockpile location, including grading and stockpiling, potentially will result in exposure of workers, the public, and/or the environment to contaminated soil related to a release of unknown origin at the Chabot Dam Filter Plant.

Mitigation Measure HMI-3: If potentially contaminated soil related to a release at the Chabot Dam Filter Plant is to be disturbed by project construction activities such as grading, then EBMUD or its contractors shall conduct an evaluation of potentially contaminated soil related to the release at the Chabot Dam Filter Plant, including sampling and analysis of shallow soils, for evaluation of contamination.

## 8.7 Park Stockpile Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Park Stockpile location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

In addition, HMI-4 potentially will occur at the Park Stockpile location.

HMI-4: Project construction activities at the Park Stockpile location may include relocating or removal of a pole-mounted transformer that potentially will result in exposure of workers, the public, and/or the environment to hazardous materials.

Mitigation Measure HMI-4: The construction contractor shall assess the pole-mounted transformer for the presence of PCBs, based on the age of the pole-mounted transformer, if project construction activities necessitate the removal or relocation of the pole-mounted transformer. If the pole-mounted transformer is dated prior to 1978, it shall be considered to contain hazardous materials and disposed.

## 8.8 Outlet Works Hazardous Materials Impacts and Mitigation Measures

Impacts HMI-1 and HMI-2 potentially will occur at the Outlet Works location. Mitigation Measure HMI-1 and Mitigation Measure HMI-2 shall be implemented at this location.

In addition, HMI-5 and HMI-6 potentially will occur at the Outlet Works location.

HMI-5: Project construction activities at the Outlet Works location may include demolition of structures potentially painted with lead-based paint, which will result in exposure of workers, the public, and/or the environment to hazardous materials.

Mitigation Measure HMI-5: Before beginning project construction activities, EBMUD or its contractors shall conduct an evaluation of all structures (built before 1980) to be demolished, to evaluate the presence of lead-based paint. Remediation shall be implemented in accordance with the recommendations of these evaluations.

HMI-6: Project construction activities at the Outlet Works location may include demolition of structures constructed with asbestos containing materials, which will result in exposure of workers, the public, and/or the environment to hazardous materials.

Mitigation Measure HMI-6: Before beginning project construction activities, EBMUD or its contractors shall conduct an evaluation of all structures (built before 1980) to be demolished, to evaluate the presence of asbestos containing materials. Remediation shall be implemented in accordance with the recommendations of these evaluations.

With implementation of the proposed mitigation measures, impacts related to potential hazardous materials will be less than significant.

## 9 References

- California Department of Oil, Gas, and Geothermal Resources (DOGGR). 2012. Online Mapping System. Available: <http://maps.conservation.ca.gov/doms/doms-app.html>. Accessed March 25, 2012.
- Dibblee, T. W. Jr. 2005. Geologic Map of the Hayward Quadrangle, Contra Costa and Alameda Counties.
- Environmental Data Resources Inc. (EDR). 2012a (November 1). *The EDR Radius Map Report with GeoCheck Report: Lake Chabot Dam, Lake Chabot, Oakland, California*.
- . 2012b (November 1). *Certified Sanborn (R) Map Report: Lake Chabot Dam, Lake Chabot, Oakland, California*.
- . 2012c (November 7). *The EDR Aerial Photo Decade Package, Lake Chabot Dam, Lake Chabot, Oakland, California*.
- . 2012d (November 2). *EDR Historical Topographic Map Report, Lake Chabot Dam, Lake Chabot, Oakland, California*.
- . 2012e (November 2). *The EDR-City Directory Abstract, Lake Chabot Dam, Lake Chabot, Oakland, California*.
- U.S. Geological Survey (USGS). 1993. 7.5-Minute Topographic Quadrangle Maps Series, Hayward, California, and San Leandro, California.
- Thomas Guide. 2008. Metro Areas of Alameda, Contra Costa, Marin, San Francisco, San Mateo, and Santa Clara Counties.
- URS. 2011 (November 7). *Summary of August 2011 Field Investigation Program Memo, Chabot Dam Remediation Concept Project*.

# 10 List of Preparers

Melissa Terry  
Senior Staff Environmental Scientist

Peter Sims  
Project Environmental Geologist

Kris M. Larson, PG  
Principal Environmental Geologist