

August 20, 2019

ADDENDUM 1

To prospective proposers under RFP for “Relief Well Cleaning at Camanche Reservoir”.

Notice is hereby given that RFP for “Relief Well Cleaning at Camanche Reservoir” of the East Bay Municipal Utility District has been revised as follows:

- A. On title sheet replace response due from “August 23, 2019” to “August 30, 2019”
- B. In B. Scope, replace “It is the intent of these specifications, terms, and conditions to describe the cleaning and video logging of thirteen (13) of the fifteen relief wells located at Camanche Dam.” with “It is the intent of these specifications, terms, and conditions to describe the cleaning and video logging of nine (9) of the fifteen relief wells located at Camanche Dam.”
- C. In B. Scope, second paragraph, replace “The Contractor shall provide all equipment, labor, means and methods to clean the thirteen (13) relief wells...” with “The Contractor shall provide all equipment, labor, means and methods to clean the nine (9) relief wells...”
- D. In E. Specific Requirements, replace the first paragraph entirely with “The Contractor shall provide all the equipment, means and methods to clean nine (9) relief wells located at the downstream toe of Camanche Dam. Wells shall be cleaned to remove debris and reduce screen clogging possibly due to calcium carbonate, iron bacteria, silts, clays, or a combination of sediments and deposits encrusting across the 0.035-inch well screens or within the well casings. The Contractor shall clean one relief well at a time, starting at well W-7 on the south side of the site, and working its way north to W-6, W-8, W-9, W-5, W-10, W-11, W-4 and W-12. Due to safety concerns with active overhead power lines, wells W-1, W-2, W-3, W-14, W-17, and W-18 are not included in the scope of work.
- E. In E. Specific Requirements, near the end of the fourth paragraph, delete: “When cleaning wells W-3 and W-14, the Contractor must take care not to flood the District facilities immediately next to the wells.”
- F. In E. Specific Requirements, after the fourth paragraph add: “The Contractor is allowed to disassemble and reassemble any fencing as needed to access a work area. Contractor shall reinstall fence to original conditions once work in the area has been completed. Contractor shall trim the oak tree branches above well W-17 as needed to allow access for cleaning. Contractor is responsible for disposing of removed trees branches in a legal manner.”

- G. On Calendar of Events replace response due “August 23 by 4:00 p.m.” to “August 30 by 4:00 p.m.”
- H. On page 5 of Exhibit A, replace “Clean and video log all fifteen (15) relief wells located at the downstream toe of Camanche Dam as described in this Request for Proposal” to “Clean and video log the nine (9) relief wells located at the downstream toe of Camanche Dam as described in this Request for Proposal”. See attached revised proposal form.

ACKNOWLEDGMENT OF RECEIPT OF THIS ADDENDUM SHALL BE INDICATED BY INSERTING THE ADDENDUM NUMBER AND ITS DATE ON THE FORM LABELED “PROPOSER INFORMATION AND ACCEPTANCE” IN EXHIBIT A.

A handwritten signature in black ink, appearing to read 'Prashay Mehta', with a stylized, cursive script.

Prashay Mehta, PE
Assistant Engineer



PROPOSAL FORM FOR RFP #PUR DES2

Total Cost shall be submitted on this Proposal Form as is. The prices quoted shall not include Sales Tax or Use Tax; said tax, wherever applicable, will be paid by the District to the General or Professional Service Provider, if licensed to collect, or otherwise directly to the State.

No alterations or changes of any kind to the Proposal Form(s) are permitted. RFP responses that do not comply may be subject to rejection in total. The cost quoted below shall be the cost the District will pay for the term of any contract that is a result of this RFP process.

Description	Estimated Quantity	Unit Cost	Total Cost
Clean and video log the nine (9) relief wells located at the downstream toe of Camanche Dam as described in this Request for Proposal	Lump Sum	N/A	\$
TOTAL COST			\$